

# Preparation for FST Installation

Xu Sun, Gavin Wilks & Zhenyu Ye Yu Hu, Prithwish Tribedy & Flemming Videbaek

## Pre-Installation Goals



Final Goal: identify 36 sets of good FST module & purple cable & gray cable and mount modules & purple cables to the support structure.

- Check routing and length of purple cable and soft cooling tube.
- Check possible leakage of cooling system especially on the joint of the cooling tube.
- Decide mounting order based on the dummy module practice.
- Finalize slow control and online monitoring.
- RO test of all FST modules.

## Pre-Installation Plan



Task	Start Date	End Date	Personel	Status
Purple Cable Routing Check	04/12/2021	04/23/2021	Rahul, Felix, Mike, Flemming, Yu, Prithwish, Xu	Done
Cooling Line Check	04/12/2021	04/23/2021	Rahul, Felix, Mike, Bill, Flemming, Yu, Prithwish, Xu	Done
Cooling Slow Control Update	04/12/2021	05/09/2021	Yu, Prithwish, Xu	In Progress
Setup RO System	04/19/2021	04/23/2021	Xu, Mike, Yu, Prithwish	Done
Mounting Practice with Dummy Modules*	04/12/2021	05/09/2021	Xu, Yu, Prithwish	In Progress
Support Structure Test**	04/26/2021	05/09/2021	Rahul, Bob, Mike, Xu	Next Up
Mount One Module and RO Test	05/10/2021	05/16/2021	Xu, Yu, Prithwish	Not Started
Mount Six Modules and RO Test	05/17/2021	05/23/2021	Xu, Yu, Prithwish	Not Started
Run Cooling System with Modules	05/24/2021	07/19/2021	Xu, Zhenyu, Gavin, Yu, Prithwish, Bill	Not Started
Mount Remaining Modules and RO Test	06/01/2021	07/19/2021	Xu, Zhenyu, Gavin, Yu, Prithwish	Not Started
RO Test Backup Modules and Cables	07/20/2021	08/30/2021	Xu, Zhenyu, Gavin, Yu, Prithwish	Not Started

\* Decide mounting orders.\*\* See Rahul's Talk.

04/26/2021

Xu Sun—fSTAR Face-to-Face Meeting

# Required Equipments



- Setup RO System: 1 MPOD Crate (𝒜) + 3ISEG (𝒜) + 1ARC (𝒜) + 3ARM(𝒜) + 3ABC(𝒜)
- Mount 1 FST Module and RO Test: 1 FST Module (✓) + 1 purple cable (✓) + 1 PPB
  (✓) + 1 gray cable(✓) + light cover (✗)
- Mount 6 FST Modules and RO Test: 6 FST Module (✓) + 6 purple cable (3) + 6 PPB
  (✓) + 6 gray cable(✓) + light cover (X)
- Run Cooling System with FST Modules: Cooling System(✓) + Soft Cooling Tube (✗)
- Mount 36 FST Modules and RO Test: 36 FST Module(30) + 36 purple cable(3) + 36 PPB(✓) + 36 gray cable(✓) + light cover (✗)
- Test Backup FST Modules: dark box (✓) + backup FST modules (X) + backup purple cables (X) + backup PPBs (✓) + backup gray cables (✓)

### Man Power



#### • UIC


- Xu (04/08/2021-FST is ready)
- Gavin (05/24/2021-08/14/2021)
- Zhenyu (06/01/2021-08/20/2021)
- BNL
  - Rahul
  - Mike
  - Bob
  - Bill
  - Flemming
  - Prithwish
  - Yu

### Clean Room Overview






# Purple Cable Length Check



- Purple Cable Length: measured from T-board to the end of cable tray:
  - 1: 38.5 + 5.5 in
  - 2: 36.5 + 5.5 in
  - 3: 45.5 + 5.5 in
  - 4: 34.0 + 5.5 in
  - 5: 45.5 + 5.5 in
  - 6: 52.5 + 5.5 in
- Purple Cables are mounted on the bottom module (6 in previous slide & longest cable) on three disks.
- Cable length:
  - A: 52.5 + 5.5 in
  - B: 47.5 + 5.5 in
  - C: 42.5 + 5.5 in
- The distance between disks is 5 in (measured) and consistent with the difference on cable length.

# New Purple Cable Routing




Old Routing

New Routing

• New routing removes the force from cable but introduce 5.5 in longer purple cable.

# Cooling Tube Status





- Soft cooling tube length: 41.5 cm.
- Soft cooling tube do NOT conflict with other part of detector under current assembly.
- Cooling tube (Stainless Steel) is grounded to the T-Board and Support Structure.

# Dummy Module Mount





#### Issues:

- Screws on support structure are not tighten => causing the movement of module while plugging the soft cooling tube.
- Screws on the fixture of module are not tighten => causing the cooling tube detached from from the heat sink while plugging the soft cooling tube.
- Small deflection still exists while plugging the soft cooling tube.

### Readout System






- Test stand setup in the clean room: 1 MPOD Crate + 3ISEG + 1ARC+ 3ARM + 3ABC
- DAQ software is working properly.
- MPOD crate is online and can be controlled by the slow control.

#### MPOD Crates Slow Control — Expert UC



04/26/2021

#### MPOD Crates Slow Control — Shift Crew UIC



# FST Cooling Slow Control

Pump Start

4.4 degC

0.00 Cyc/min

0.09 Rep/min

16

70

0.0

Alarm 2

16

70

0.0

Setpoint Limits

High 60 60 degC

Low [16 16 degC


.

Coolant

Fluid

Water 🛥

#### EPICS Interface




- Re-use of old IST cooling slow control.
  - FST use the same cooling system as IST => a natural choice to re-use old IST cooling slow control system.
- GUI for Expert
  - Operation, monitor and alarm are all based on sequencer.
  - Need to modify old IST sequencer for FST setup => adjust flow speed limits.
  - Need to modify old IST GUI for 0 FST => adjust naming and pictures.
- Updates will start after the cooling system back online.

# Online Monitoring



IST

EPD -> FST



- Re-use the old IST online QA plots with modification for FST.
- Able to check out and compile old IST code.
- Need to update to FST geometry.
- Will test with the data collected in the DAQ integration test, then send to Jeff for implementation.
- Plan to use similar style as EPD.

Xu Sun—fSTAR Face-to-Face Meeting

### Online Zero-Suppression—Noise


Chip's output signal  $PH_i^k$ (channel k of i-th event) can be described as a sum of following components:  $PH_i^k = S_i^k + P^k + N_i^k + C_i$ 


- $S_i^k$  is the chip response to the injected charge
- $P^k$  is the pedestal level
- $N_i^k$  is the random noise
- $C_i$  is common mode noise

• 
$$C_i = \frac{1}{N_{channel}} \sum_{k=1}^{N_{channel}} (PH_i^k - P^k)$$

- N<sub>channel</sub> is all channels within the same group without signal (hit) => in our analysis we average all channels in same APV and same R-Strip into one group (32 channels in each group)
- Comment Mode Noise (CMN) has significant contribution to the total FST noise (different to IST), therefore, needs to be subtracted in Zero-Suppression DAQ.

#### FST Noise






16

### Online Zero-Suppression—Signal UC

Time Bin 2



Time Bin 1

• Requiring a seed with Threshold larger than 4.0 and 2 Time bin.

- Hit threshold 2.5 with 2 Time Bin requirement can reject non-cluster noise very well.
- Hit threshold 3.5 with 1 Time Bin requirement has the similar effect on noncluster noise after we did a threshold scan.
- The final cluster will include hits with hit threshold 2.5 & 2 time bin or hit threshold 3.5 & 1 time bin when a seed is found.

# Summary and Outlook



- Checked purple cable routing and cooling tube routing.
- Setup DAQ and RO system.
- HV Crate slow control is ready.
- Need to update cooling slow control and online plots.
- Will start real module mounting once the support structure is ready.