



Improvements to the CeC Systems

CeC Experiment at RHIC CeC X Retreat

Jean Clifford Brutus August 16th,2021



@BrookhavenLab

Key Presentations


14:10 → 14:20	Break Break	③ 10m
14:20 → 14:40	Improvements to the CeC systems Speaker: Jean Clifford Brutus	○ 20m
14:40 → 15:00	Photocathodes: production, transfer, QE mapping (M. Gaowei, E. Wang, L. Cultrera, T. Rao) Speaker: John Skaritka (BNL)	③ 20m
15:00 → 15:20	Laser: time and intensity jitter, position stability, (L. Nguyen) Speaker: Patrick Inacker-Mix (BNL)	③ 20m
15:20 → 15:30	Break Break	O 10m
15:30 → 15:50	CeC RF system: voltage and phase jitter and drifts (G. Narayan, F. Severino, Y. Than) Speaker: Thomas Hayes (Brookhaven National Lab)	③ 20m
15:50 → 16:10	Orbit-drifts, noise/jitter, accuracy, slow feed-backs (R. Michnoff, P. Thieberger, A. Di Lieto) Speaker: Igor Pinayev (BNL)	③ 20m
16:10 → 16:30	Diagnostics (including IR) - noise and its suppression (I. Pinayev, M. Paniccia) Speaker: Rob Michnoff (BNL)	③ 20m
16:30 → 16:50	Diagnostics - time resolved emittance and energy spread, (Y. Jing, J.C. Brutus, D. Kayran, I. Pinayev) Speaker: Andrei Sukhanov (BNL)	○ 20m
16:50 → 17:00	Closing	③10m

CeC Shutdown 2021 Upgrades


#	Work
1	500 MHz Removal
2	Horizontal/Vertical Slit
3	Profile Monitor
4	Cathode System Upgrade
5	Replace Q1 in the TRDBL by one with working trim coils - in current quad two out of 4 trim coils are broken
6	500MHz Coax Inspection
7	DCCT
8	Solenoid
9	H/V Trims relocation
10	Wiggler/Undulator
11	Heating Jackets Removal
12	Compensating Coil




CeC Beamline Modifications



Changes to Diagnostics Beamline




Diagnostics Beamline Upgrade



H/V Slit


- Stand modification design completed
- Beamline vented and vacuum components removed
- BPM and ion pump relocated; survey to follow
- Delay from vendor for H/V Slit Custom cross 10/05/21






Profile Monitor and Solenoid


- Stand modification design completed
- Work in progress for relocation of H/V corrector and removal of Diamond detector stand
- Delay from vendor for profile monitor cross 10/05/21 fabrication of new cross in house as backup




Temporally Resolved Optical Gating - TROG

- New stand design completed
- Fabrication in progress












500 MHz Removal

- Design completed
- Design of coax reconfiguration completed
- Parts ordered and in house
- Single 500MHz surveyed: -1.5 mm axis; 0.02 degrees about Y axis










500 MHz & DCCT


- Removal completed
- All parts in house
- Installation in progress







500MHz Coax Inspection/Cleaning



- Received cleaning process from manufacturer
- Spare parts/Replacement parts ordered












































A Coax A Clean 2.JPG


Courtesy: J. Butler, RF Group

Trim modifications in CeC Accelerator

- Take out Gun Trim 2 (large coils): Need to accurately fix Gun Trim 1
- Restore trims after 500Mhz and after DCCT (E-measurement trims)
- Replace trims after 704MHz linac with new H/V correctors
- Replace TRDBL new large aperture with old trims with 2" aperture Keep H and V trims fed in series
- CeC section: Add vertical trim coils at the entrance and at the exit



























Short Diagnostics Undulator: 8 cm period, 0.6 kGs

- Will serve as source of THz radiation at at frequency ~ 5 THz to tune PCA. Will be removed for CeC demonstration.
- Design and prototype in progress










Stray fields studies in CeC section

Comments

- I used milliGauss meter today to investigate nature and values of strat magnetic fields in the CeC section
- Earth magnetic field :
 - Earth magnetic field was observed by walking along the CeC section with hand-held meter. Vertical component of the magnetic field has the same sign by varying from \sim +350 mGs at the start (sol 1) to \sim +500 mGs at the center and to \sim +250 mGs close to the of the CeC section (sol 7). Vertical component varyies from -150 mGs to about +100 mGs
 - RHIC shell screens Earth magnetic field well with remaining components ~ 100 mGs
- Compensating dipole magnets generate magnetic fields \sim 2-4 Gs at length \sim 40 cm, e.g. angular kick \sim 1.8 3.6 mrad opposite to the main dipoles, i.e \sim 0.2-0.4% difference from the first dipole!
- The main finding from today the back-out blankets and especially connecting cables are highly magnetic, have strong residual fields. Since they are not uniform and asymmetric, they are likely responsible for problems we had with angles of solenoids axes and luck ore reproducibility. These blankets and cables need to be removed.
- Details of the stay fields induced by main power supplies are in the following slides



3D probe was placed ~ 5-6 cm above the IR axis.


Results


Point	1	1	1	2	2	2	3	3	3	4	4	4			
ΔB,mGs	Υ	X	Z	Υ	Х	Z	Υ	X	Z	Υ	X	Z			
Dipole 100 A	-150	30	-2000	24	-24	8	8	-1	-2	11	0	0			
Solenoid 1 (1-7)	-5	0	20	-2	-3	-3	0	0	0	0	0	1			
Solenoids 2-6				108	20	600	-180	6	1085	3	0	44			
Solenoids 3-(4)-5				4	1	-40	-139	-73	-1470	11	-6	-660			
30-degree/Sol4				0	0	0	0	0	30	144	42	620			
	5	5	5	6	6	6	7	7	7	8	8	8	9	9	9
	Υ	X	Z	Y	X	Z	Y	X	Z	Y	X	Z	Y	X	Z
Dipole 100 A	9	0	0	3	0	-3	2	2	4	505	-125	490	1,500	300	
Solenoid 1 (1-7)	0	0	0	-3	0	-24	-34	-45	-390	1540	246	Saturated			
Solenoids 2-6	7	0	34	560	70	Saturated	-70	4	640	0	0	60			
Solenoids 3-(4)-5	6	0	-650	33	8	874	-6	0	-54	-16	0	-10			
30-degree/Sol4	-100	-50	670				0	0	0	0	0	2			



Heating Jackets


- Search for explanation for unusual kinks in e-beam trajectory discovered, that in contrast with specifications, heating blankets and their cables have significant amount of magnetic materials, which distort magnetic fields in the CeC section
- Heating Jackets and their cables are highly magnetic and have to be removed from the insides of the solenoids, trims, quads... and the rest of the CeC section.
- 7 correctors need to be taken apart to remove jackets
- When blankets are removed, we need to remeasure stray fields from the solenoids, dipoles and most importantly cables! Table shows that stray fields 1 m from solenoids are rather large for some of them and small for the others we need to understand the reason and check if there are cable loops?







Earth field compensation coil



Summary

- Priority list
- Anthony is checking if we need to run new cable and order more PS for new compensating coils and H/V trims 8-12 weeks lead time
- Design modifications of beamline completed
- 500MHz removal completed
- Damaged quad replacement completed
- 500MHz coax inspection in progress
- Heating jackets removal in progress (7 correctors have to be split)
- DCCT installation in progress
- Delay of parts from KJL for H/V slit and profile monitor looking for backup solution
- TRDBL modifications in progress
- Undulator design and fabrication in progress
- H/V trims relocation design in progress



Thank You!



