



Longitudinally segmented Forward HCal (LFHCal) Concept & R&D



Friederike Bock (ORNL)
EIC Project Detector Calorimetry Review
December 6-7, 2022


Electron-Ion Collider

pHCal ATHENA



- Both detector concepts using longitudinally segmented Steel-Scintillator HCal
- ECCE LFHCal with additional W-layers offers larger shower containment
- Construction method allows to vary tower sizes as function of R to possibly reduce cost

- ⇒ Consensus within WG to recommend ECCE LFHCal for implementation & construction and change plans for eRD107 accordingly
- ⇒ Exploring highly granular/pixelized inlay around beam pipe similar to CALICE W-AHCAL design as future upgrade



LFHCal ECCE

8M tower module - 20 cm x 19.6 cm x 1.50 cm
 - 85 cm x 5 cm LFHCal towers

General considerations

- Both concepts follow similar general idea: highly segmented HCal in $x - y$ & z
- Current simulations don't entirely reflect reality (Steel-HCal response too good) \Rightarrow expecting 1.5 – 2x worse resolution in reality with same reco-algorithms
- SiPM-Readout & integration with ECal can be done in similar way for both

pHICAL

Pros

- Easy construction, tight tolerance assembly, solid mechanical structure
- Good understanding of general cost & risk (STAR FCS)

Cons

- Max. 4 long segments & effi loss due to signal splitting using time response
- Once installed segmentation is fixed
- Needs assembly at IP6

LFHICAL


Pros

- Larger shower containment
- Somewhat flexible segmentation in $x-y$ & z , better performance using ML possible
- Possibility for distributed module assembly & testing


Cons

- More complex assembly & integration (fiber routing)
- No test beam yet
- Higher cost

Concept



The General Idea




Concept:

- PSD [PSD TDR] inspired Fe/W-Scint calorimeter
- 60 layers of Steel (16 mm)-Sci plates (4mm) + 10 layers of W (16 mm)-Sci plates (4mm)
- Multiple towers combined in one module to reduce dead areas, increase granularity
- Read-out:
 - ▶ 7 signals per tower (signals combined from 10 Sci-plates)
 - ▶ readout position: after full HCal
- Modules of different sizes (8M, 4M, 2M, 1M) to maximize coverage & assembly efficiency

Participating institutes:

- ORNL, BNL, FNAL, ISU, GSU, Yale, UCR, UTK, Valpo


Calorimeter Details







parameter	LFHCal
inner radius (envelope)	17 cm
outer radius (envelope)	270 cm
η acceptance	$1.2 < \eta < 3.5$
tower information	
x, y ($R < /> 0.8$ m)	5 cm
z (active depth)	140 cm
z read-out	10 cm
# scintillator plates	70 (0.4 cm each)
# absorber sheets	60 (1.6 cm steel)
	10 (1.6 cm tungsten)
weight	~ 30.6 kg
interaction lengths	$6.9 \lambda / \lambda_0$
Molière radius R_M	21.1 cm (π^\pm shower)
Sampling fraction f	0.040
# towers (inner/outer)	9040
# modules	
8M	1091
4M	76
2M	2
1M	4
# read-out channels	$7 \times 9,040 = 63,280$

- Some flexibility in composition vs. length, current design $6.9 \lambda / \lambda_0$
- Total of 9040 towers with $\sim 64K$ readout channels
- Total cost: \$17.7M (w/o read-out cards)




Simulated Performance



GEANT Implementation in Fun4All







- Largely realistic implementation of geometry, refinements for module edges needed
- First light propagation studies, cross checks planned with test sub-tiles at ORNL (fiber routing)






- Translation of detailed geometry into new EPIC software framework nearly completed
- First resolution studies with significantly simpler geometry on their way

LFHCAL Performance



- Cluster finding and track matching efficiencies good in center of LFHCAL, losses towards edges
- Small η dependence for energy resolution
- Studies to improve clusterization further using ML started
- Exploring possibility to change granularity of readout as function of R
- Performance overestimated at the moment with standard response implementation in GEANT4 Fun4All (1.5x from other setups)




- Problem in original simulation for LFHCAL identified through validation with CALICE geometry in DD4HEP
 - ▶ Integration over too long time
 - ▶ Improved lower energy cut - offs
- Updated resolution parameters with idealized geometry
- Results from realistic geometry including clusterization to follow soon

Mechanical Design, Assembly & Schedule





Current 8M Scintillator Plate Design

- Most scintillator plates produced as 1 unit of 100x200mm plates (8 single tower tiles)
- Separation of tiles edged into the plate (95%) through, refilled with Epoxy-TiO₂ mix
- Wrapped in Tyvek paper and Kapton tape or painted with TiO₂ rich paint






- Fiber thickness chosen for minimal light loss while bending (0.5mm)
→ other geometries for embedding under consideration (i.e. 1/4 circle)
- Originally costed from Uniplast as 1 unit of assembly + material
- Updated estimate including (material, fiber installation by engineer, wrapping by students, tooling)
→ new estimate driving by labor for fiber installation
- Exploring possible robot supported options for tile assembly




- ① Refilling of gaps with TiO_2 -Epoxy mix using collaborative robot
- ② Measuring fiber quality & cutting to desired length
- ③ Laying WLS-fibers in groove, fixating them using a few glue dots
- ④ Roll WLS-fibers up on tray with tile
- ⑤ Tyvek or additional coating with white paint
- ⑥ Stack trays & transport to 8M assembly site



8M assembly detail



- Mount assembled steel/tungsten frame in pivot
- Slot scintillator tiles in frame from back to front
Fibers for bottom side slotted through, caught by tray on bottom
- After 10 tiles sort fibers 5/5 & place plastic strip as separator, tape on top
- Continue till top side finished & cut length of fibers to fit readout
- install cover plate
- Flip module in pivot, remove tray
- Sort fibers & assemble as on top




Stacking Design & Support structure




- Half disk assembled on trolley to be rolled to the side
- Single 8M-modules arranged in "brick-like-structure"
- Notch and groove design for alignment in x & z direction

Schedule




- Schedule fully developed with several long lead procurement items:
 - ▶ Steel, SiPMs, scintillator plastic, WLS fibers
- Partial deliveries from vendors with time allow earlier start of assembly
- Foresee multiple module production sites/stations, default: 6 stations
- Tile assembly simultaneous to scintillator & WLS procurement with slight offset
- Magnetic field map testing starting 04/29
- Single component testing foreseen during assembly
- Final module tests after each module assembly & in complete stack

Read-out Concept




Read-out 8M module

MC




Rec



- High granularity needed to try to distinguish shower maxima close to beam pipe
- **HCal:**
read out in 7 layers longitudinally
desirable min measurable tower energy 3-5 MeV, max 20-30 GeV in single tower segment

- LFHCAL 1 SiPM per 10 fibers (7 per tower) -i.e Hamamatsu S13360-3025PE (14.4K pixels)
- HCal readout at end of module (max. 10cm)
- Small light collection prisms might be needed in front of SiPM
- Idea to use each 1 H2GCROC3 (up to 70 channels) for readout of HCal (ideally common chip/board design with WSciFi-ECAL & ALICE FoCal-H)


Current Read-out Concept



- The H2GCROC3 requires the L1 trigger for readout, with the maximum speed of 960 kHz
- The expected hit rate in one channel of LFHCal is up to 50 kHz:
 - ▶ With possible 4 sample readout we would reach a maximum of 200 kHz
 - ▶ Compatible with streaming readout towards the EPIC DAQ system

Details see Norbert's talk

R&D activities & plans



eRD107 - Plans & Milestones

① Prototype tile production using machining & injection molding (04/23)

- ▶ Assembled prototype tiles using machined scintillator plates
- ▶ Assembled prototype tiles using injection molded scintillator tiles
- ▶ Documentation of procedures for manual assembly of tiles & WLS fibers

② Reconstruction optimization (09/23)

- ▶ Write-up of optimization results from simulations

③ Sensor board development (07/23)

- ▶ First prototype of sensor board for Si-PM readout (together with eRD109)

④ Small test module assembly (07/23)




- ▶ First prototype of single segment of 8M module



⑤ First automated scintillator tile assembly (08/23)

- ▶ Assembled prototype tiles
- ▶ Documentation and Evaluation of procedures for automated assembly of tiles & WLS fibers

⑥ Tile Characterization (08/23)

- ▶ Write-up of test bench & test beam measurement for all assembled tile-prototypes







Prototype tile production using machining & injection molding

- Vendor replacement needed for Uniplast
 - a) Machining plastic scintillator plates (\sim \$80/tile, 3 yr prod. time)
 - b) Injection molding tile (\sim \$4 – 6/tile, 3 month prod. time)
- Opportunity for significant cost reduction w/ injection molding
- Performance and mechanical stability tests needed in both cases

First automated scintillator tile assembly


- Tile assembly time & labor extensive w/ classical methods
- Exploring automated assembly using collaborative robots for:
 - ▶ Refilling sub-segmentation with TiO_2
 - ▶ Fiber laying and fixating in groves
 - ▶ Automatic measurements of WLS-fiber quality

- Characterization of assembled tiles according to:
 - ▶ Light yield
 - ▶ Cross-talk among different tiles
 - ▶ Response uniformity
 - ▶ Durability and mechanical stability
- Initial geometry optimization using TracePro simulations
- Usage of available test-stands at universities for tile characterization
- Possibility to test multiple scintillator materials/dopant concentration in particular for injection molding
- Development of a SiPM board and WLS fiber connector suitable for production module




- Full 8M module assembly with single component testing
 - ① Scintillator tiles
 - ② Single segment of 8M module (20cm) including initial read-out design
 - ③ Full mechanical mock-up of 8M module
 - ④ Full 8M modules including initial read-out design
- Main measurements
 - ▶ Characterization of spatial distribution and uniformity of MIP response for different tile types
 - ▶ Saturation behavior of combined tile and SiPM readout system for single segment
 - ▶ Measuring the individual and combined response of tiles to EM-showers
 - ▶ Spatial and energy resolution of partial and full module LFHCAL module
 - ▶ Combined test-beam w/ pECal to characterize LFHCAL partial and full module response behind ECal
- Current Read-out electronics design based on CMS-SiPM-HGCROC (ASIC)
Final electronics R&D for EIC specific readout board within eRD109 based on same ASIC with possible small modifications

Summary



- LFHCAL concept adapted from established calorimeter (PSD calorimeter)
- Mechanical design far advanced
- Simulation setups in good shape with realistic geometries
- Performance goals for EIC physics reached with proposed concept with potential for improvements with modern reconstruction techniques
- Workforce is experienced in building large scale calorimeter systems (ALICE EMCal, sPHENIX ECal)
- Challenges in construction process addressed by dedicated R&D plans
- Performance validation foreseen in test beams during next 2 years

Thanks!



Conservative Cost Estimate

Example 8M module costs:

Material procurement	Units	Unit Pricing
Absorber plates + support	1	\$1750
Scintillator plates	70	\$65
tyvek + capton	4.04	\$0.4
WLS fibers	1360	\$3
8M module cost:	1091	\$9822

Assembly labor	hours	cost
installing fiber mech. engineer	17.5 h	\$2680.5
tile wrapping PhD students	7 h	\$140
tower assembly mech. engineer	0.083 h	\$12.8
tower assembly PhD Student	1.92 h	\$38.4
tower assembly Undergrad	11 h	\$220
tower assembly Postdoc	1 h	\$71
tower assembly PhD Student	4.5	\$90
8M module cost:	1091	\$2252.7

Electronics	Units	Unit Pricing
SiPMs	56	\$10
mounting boards	1	\$10
cable+HV/LV	1	~\$822
8M module cost:	1091	\$1392


Additional costs:

- R&D cost: 393K
- Tooling: 200K
- Support Structure: 100K
- Installation: 382K

Total costs:

- estimated for:
1091x8M module, 76x4M modules, 2x2M modules, 4x1M modules
- Module prices don't exactly scale as labor doesn't scale
- Cost adapted to US prices w/o relying on Uniplast
- **total unescalated cost: \$17.7M**
→ estimates w/ Uniplast quotes \$11.2M

Calorimeter Details & PED request



parameter	LFHCal
inner radius (envelope)	17 cm
outer radius (envelope)	270 cm
η acceptance	$1.2 < \eta < 3.5$
tower information	
x, y ($R < / > 0.8$ m)	5 cm
z (active depth)	140 cm
z read-out	10 cm
# scintillator plates	70 (0.4 cm each)
# absorber sheets	60 (1.6 cm steel)
	10 (1.6 cm tungsten)
weight	~ 30.6 kg
interaction lengths	$6.9 \lambda / \lambda_0$
Molière radius R_M	21.1 cm (π^\pm shower)
Sampling fraction f	0.040
# towers (inner/outer)	9040
# modules	
8M	1091
4M	76
2M	2
1M	4
# read-out channels	$7 \times 9,040 = 63,280$

activity	cost in FY23 k\$		total cost in FY23 k\$
	ORNL	BNL	
Support structure design & integration with pECal	75	0	75
Rail/slide design	0	50	50
test production of module	20	0	20
tooling design + function test	50	0	50
Total	145	50	195

eRD107 Funding request

activity	cost in FY23 k\$									total cost in FY23 k\$
	ORNL	FNAL	BNL	UTK	GSU	Yale	ISU	Valpo	UCR	
Machined Tiles	11.7	0	0	0	0	0	0	0	0	11.7
Injection Molded Tiles	2.0	52.9	0	0	0	0	0	0	0	54.9
Auto Tile Assembly	20.0	0	0	0	0	0	0	0	0	20.0
Tile Char. (Lab)	16.0	0	0	0	0	0	0	0	0	16.0
Sensor Board	12.2	0	0	0	0	0	0	0	0	12.2
LFHCAL Mechanics	21.7	0	0	0	0	0	0	0	0	21.7
Tile Char. (Beam)	1.0	0	2.0	2.0	2.0	2.0	2.0	1.0	2.0	14.0
Total	84.6	52.9	2.0	2.0	2.0	2.0	2.0	1.0	2.0	150.5

institute	cost in FY23 k\$				total cost in FY23 k\$
	eng. and tech.	material	equipment	travel	
ORNL	29.8	16.8	36.0	2.0	84.6
FNAL	52.9	0	0	0.0	52.9
BNL	0	0	0	2.0	2.0
UTK	0	0	0	2.0	2.0
GSU	0	0	0	2.0	2.0
Yale	0	0	0	2.0	2.0
ISU	0	0	0	2.0	2.0
Valpo	0	0	0	1.0	1.0
UCR	0	0	0	2.0	2.0
Total	82.7	16.8	36.0	15.0	150.5

- Largest fraction of funding for engineers and technicians
- Additional funds used for material, test equipment & travel for test beam campaigns
- Significant in-kind contribution from universities and laboratories for assembly, simulation and data analysis (~ 2140h)
- Parallel PED request for mechanical & electrical engineering support will be submitted to further final design of LFHCAL

Task	Estimated cost in \$ per year		
	FY24	FY25	FY26
mechanical engineering	40K	40K	20K
electrical engineering	30K	30K	20K
materials	30K	30K	40K
test beam support	10K	10K	10K
total	110K	110K	90K

eRD107: Detailed cost table

Institute	Item	Cost per item in \$	Number of items	Total cost in \$	To be compl. by
	Machined Scintillator Tiles:				Q1/2023
ORNL	BC-408 plastic scintillator sheet	~ 150	20	3K	
ORNL	BCF-91A WLS fiber	1500	1	1.5K	
ORNL	tile machining	180/h	40h	7.2K	Q4/2022
ORNL/UTK	tile assembly		40h	(in kind) 0K	Q4/2022
	Injection Molded Scintillator Tiles:				Q2/2023
FNAL	mold design + production	50 000	1	50K	Q4/2022
ORNL	travel			2K	
FNAL	raw material + dopant			(in kind) 0K	
FNAL	injection molder setup + operation	180/h	16h	2.9K	Q1/2023
ORNL/UTK	tile assembly		40h	(in kind) 0K	Q1/2023
	Automated Tile Assembly:				2024
ORNL	robotic arm	20 000	1	20K	
ORNL	robot programming and evaluation		40h	(in kind) 0K	Q3/2023
	Tile Characterization (Lab Bench):				Q3/2023
ORNL/UTK	scintillator material characterization		20h	(in kind) 0K	Q2/2023
ORNL	waveform sampling readout (8ch)	16000	1	16K	
GSU/Yale/UCR	tile lightyield testing		160h	(in kind) 0K	Q3/2023
ISU/BNL	tile simulation		160h	(in kind) 0K	Q3/2023
	Sensor Board:				Q1/2023
ORNL	mechanical engineer	180/h	15h	2.7K	
ORNL	sensors: silicon photomultipliers	30	300	9K	
ORNL	sensor board production, assembly	50	10	0.5K	Q1/2023
	Reconstruction Optimization:				2025
UTK/Yale/BNL	simulations/digitization/reconstruction/analysis		640h	(in kind) 0K	
	LHCAL Mechanics:				Q3/2023
ORNL	mechanical engineer	180/h	105h	18.9K	
ORNL	absorber material + fasteners	40	70	2.8K	
UTK/Yale	absorber machining	100/h	20h	(in kind) 0K	Q2/2023
	Tile Characterization (Test Beam):				Q3/2023
ORNL	assembly and shipping			1K	
All	test beam travel			13K	
ORNL/UTK	test beam preparation		80h	(in kind) 0K	Q2/2023
ORNL	test beam		120h	(in kind) 0K	Q3/2023
Yale	test beam		120h	(in kind) 0K	Q3/2023
BNL	test beam		120h	(in kind) 0K	Q3/2023
UTK	test beam		120h	(in kind) 0K	Q3/2023
GSU	test beam		120h	(in kind) 0K	Q3/2023
ISU	test beam		120h	(in kind) 0K	Q3/2023
Valpo	test beam		120h	(in kind) 0K	Q3/2023
UCR	test beam		120h	(in kind) 0K	Q3/2023
Total				150.5K	