

Test Beam plans: LFHCal mini module

August 16, 2023

Friederike Bock & Norbert Novitzky (ORNL)

F. Bock (ORNL), O. Hartbrich (ORNL), N. Novitzky (ORNL), K. Read (ORNL), N. Schmidt (ORNL)


September test beam plans

Dates: 6th – 13th Sept.


Main purpose: Scintillator characterization & HGCROC tests

- Setup consists out of maximum 10 layers of 8M tile assemblies of each
 - ▶ 4mm scintillator
 - ▶ $\approx 0.2\text{mm}$ ESR foil
 - ▶ $\approx 0.2\text{mm}$ flexible PCB
 - ▶ $\approx 0.2\text{mm}$ Kapton tape
- Fixed in plastic frame with cut outs in the center with slots for holding assemblies
- Each 8M tile assembly with 8 channel readout
- Connected via 16 channel $\approx 8\text{ m}$ micro-coax-cable assemblies to CAEN DT5202 64ch CITIROC SiPM readout unit or HGCROC


8M tile assembly



Plastic frame



September test beam plans (2)



Integration:

- Ideally in front of FoCal-H (part time could be behind it)
- Working with Ton on putting it into the setup
- Ideally should be movable by $\approx \pm 10$ cm in x direction
- Most interesting to us: π beam effectively we would like to see MIPs in all layers using just the tile setup as a hodoscope
- Could be taken out during e-beam or layers significantly reduced (i.e down to 1-3)

Main expected measurements:

- Light yields per tile (possibly position dependent)
- Cross talk estimates of different tiles
- Use it as testing setup for SiPM-HGCROC while taking data with Focal-H using CAEN & VMM read-out
- If placed behind FoCal-H, measure part of leakage


October test beam plans

Dates: 11th – 18th Oct.


Main purpose: Scintillator characterization & HGCROC tests

- Setup consists out of maximum 14 layers of 8M tile assemblies & corresponding layers of absorber plates out of steel or tungsten
- Fixed in steel frame with slots for tile assemblies & absorber plates
- Same read-out setup as for September test beam


8M tile assembly



absorber plate



Steel frame



October test beam plans (2)

Integration:

- Ideally after FoCal-E if Focal-H not being run, otherwise after FoCal-H
- Will work with Ton on putting it into the setup
- Ideally should be movable by $\approx \pm 10$ cm in x direction, same as for September test beam
- Most interesting to us: π beam & e-beam if FoCal-H not there, otherwise only π

Main expected measurements:

- Shower profile measurements with different absorbers
- Cross talk estimates of different tiles
- Use it as testing setup for SiPM-HGCROC while taking data with Focal-H using CAEN & VMM read-out
- If placed behind FoCal-H, measure part of leakage