



Electron-Ion Collider Project Overview and Proposal Status


Peter Jones, University of Birmingham



WP1 – MAPS Institutes




Electron-Ion Collider (EIC)



■ Overview of the facility

The EIC is to be built at the [Brookhaven National Laboratory](#) (BNL)



■ Uniqueness

World's first [polarised electron, polarised proton/light-ion collider](#)

World's first [polarised electron, heavy-ion collider](#)

■ Overarching science questions

How does the [mass](#) and [spin](#) of the nucleon arise from its constituents?

What are the emergent properties of [dense systems of gluons](#)?

■ Key features

High Luminosity: $10^{33}-10^{34} \text{ cm}^{-2}\text{s}^{-1}$

Highly polarised beams: 70%

Wide range of energy: 20-140 GeV

Wide range of ion species: p-U


■ US DOE Project Overview

Total Project Cost = [\\$2.4B](#)



Expected start of Construction in [2025](#)

Expected start of Operations in [2032](#)

EIC Project Scope: Detector Work Packages




■ ePIC Central Detector and Ancillary Detectors




WP2: Electron tagger

UK-led Detector R&D (stems from current UKRI Infrastructure Preliminary Activity)


International Project Schedule and Full Infrastructure Project



Critical Decision (CD) Milestones
 CD-0 Approve Mission Need
 CD-1 Approve Cost Range
 CD-2 Approve Baseline Performance
 CD-3 Approve Start Construction
 CD-4A Approve Start of Operations
 CD-4 Approve Project Completion



EIC Full Infrastructure Project – Deliverables



- **WP1 – Silicon Tracker:** Precision tracking and vertexing in the central detector

Novel 65 nm stitched (wafer-scale) monolithic active pixel sensors; developed in partnership with CERN/ALICE-ITS3. **Deliverable:** Build ~33% of central silicon tracker – 2 x barrel layers.

Institutes: [Birmingham](#), [Brunel](#), [Lancaster](#), [Liverpool](#), [Oxford](#), [STFC RAL](#), [STFC DL](#)

- **WP2 – Electron Tagger:** Precision tracking of low- Q^2 scattered electrons

Low- Q^2 tagger using pixel sensors. **Deliverable:** Build two tracking stations in the far backward region. Timepix4 is the baseline technology.

Institutes: [Glasgow](#), [STFC DL](#) + [Lancaster](#) (beam impedance studies)

- **WP3 – Luminosity Monitor:** Bunch-by-bunch measurement of collision luminosity

Design of the luminosity monitor comprising a pair spectrometer (PS) and photon detector (PD).

Deliverables: Build the two calorimeters needed for the PS and half the modules needed for the PD.

Institutes: [York](#)

- **WP4 – Accelerator Deliverables:**

WP4.1 Cavity design and cryomodels for the ERL


WP4.2 Design of crab cavity LLRF feedback system

WP4.3 Design and delivery of EO-BPM instrumentation

WP4.4 ERL simulation and design

Institutes: [Cockcroft Institute](#) ([Lancaster](#), [Liverpool](#), [ASTeC](#)), [John Adams Institute](#) ([Oxford](#), [Royal Holloway](#)) and [STFC DL](#)

EIC Full Infrastructure Proposal – Timeline



■ Peer Review

Submitted standard proposal and cost justification – submitted 10th February

Peer Review Meeting – 22nd March

Feedback received – 31st March

■ STFC Prioritisation

UKRI Proforma application (last year's version) – submitted 19th April

Internal Review by STFC departments (Estates, Digital Research Infrastructure, Finance, Impact, Sustainability)

Review by SB/TAAB followed by STFC Council and STFC Executive Board

Feedback received – 1st June

■ UKRI Infrastructure Process


Preparation of final proposal using this year's UKRI Proforma

Submission to STFC EB – 30th June

Submission to UKRI IF – 24th July

Decision from UKRI IAC expected – November 2023

EIC Full Infrastructure Project – Feedback



■ Peer Review

Criteria: 1 – Community Support and Demand; 2 – Research and Innovation Excellence; 3 – Impact Potential; 4 – Capability to Deliver; 5 – Added Value; 6 – Budget Justification

Rated very highly against criteria: 2 – Research and Innovation Excellence; 3 – Impact Potential; 5 – Added Value

Against criteria 1 – Community Support and Demand, panel commented on small community but recognized potential to grow.

Main concerns fell within criteria 4 – Capability to Deliver and 6 – Budget Justification, largely due to the UK committing funding at a very early stage in the project.

Main points: concern over level of contingency, uncertainty around future governance (e.g., subscription costs) and access arrangements affecting ability of new groups to join.


■ STFC Prioritisation

Descope accelerator work package to maximise fit to scope of Infrastructure Fund.

Ensure sufficient provision for open access data and other computing requirements is costed into the proposal.

Increase level of contingency to mitigate the risk of slippage in the international project schedule.

EIC Full Infrastructure Project – Costs



Updated Costing Model

STFC Overheads now appear under **Other UKRI Funding** and is not a cost to the UKRI IF
HEIs will be funded at **100% FEC**


After descoping WP4, total project cost has gone down from **£59.6m** to **£51.8m**

For WP1, the cost has gone down from **£30.3m** to **£27.9m** (Note that institute costs have gone up!)

			9 months			3 months						£m
Project Work Packages			Cost £k (1 decimal place)									
WP	Breakdown	Description	25/26	26/27	27/28	28/29	29/30	30/31	31/32	32/33	33/34	
1	Staff Costs	Academic Staff	437.1	665.9	689.7	690.8	684.8	664.7	792.0	190.1		
1	Staff Costs	PDRAs	571.1	785.3	762.7	848.4	674.3	608.7	692.0	166.9		
1	Staff Costs	Engineers	644.2	1096.9	1254.9	978.5	685.5	584.8	83.5	0.0		
1	Staff Costs	Technicians	230.5	376.0	556.9	677.0	680.1	546.4	47.1	11.8		
1	Staff Costs	Total	1882.9	2924.0	3264.2	3194.7	2724.7	2404.7	1614.7	368.8	0.0	
1	Non-Staff Costs	Equipment	242.8	376.9	414.6	394.7	324.5	246.5	0.0	0.0		
1	Non-Staff Costs	Consumables	291.4	452.3	497.5	473.6	389.4	295.9	0.0	0.0		
1	Non-Staff Costs	Travel	85.0	131.9	145.1	138.1	113.6	86.3	150.0	150.0		
1	Non-Staff Costs	Other	114.8	630.5	2934.5	143.9	111.0	73.4	71.8	0.0		
1	Non-Staff Costs	Total	733.9	1591.5	3991.7	1150.3	938.5	702.1	221.8	150.0	0.0	
1	Total	Total for Work Package	2616.8	4515.5	7255.9	4345.1	3663.2	3106.9	1836.4	518.8	0.0	

Description	Work Package	25/26	26/27	27/28	28/29	29/30	30/31	31/32	32/33	33/34	£m
STFC Overheads	WP1	432.7	733.1	872.0	736.2	554.5	374.1	61.8	0.0	0.0	3.8
STFC Overheads	WP2	13.7	17.6	23.5	19.6	9.8	9.8	0.0	0.0	93.9	0.2
STFC Overheads	WP4	185.7	388.5	475.8	426.2	189.4	0.0	0.0	0.0	0.0	1.7
STFC Overheads	WP5	52.4	72.4	74.9	77.5	80.2	83.1	86.0	21.5	0.0	0.5
STFC Overheads	Total for Project	684.6	1211.5	1446.2	1259.6	834.0	467.0	147.7	21.5	93.9	6.1

EIC Full Infrastructure Project – Contingency



Contingency is work-in-progress

Currently, contingency includes: 1 – Extra year of staff effort; 2 – Indexation on the extra effort; 3 – Flat rate of 20% on Equipment and Consumables; 4 – 50% on silicon wafer costs; 5 – An extra percentage point on inflation

The US Project carries about 35% as contingency

UKRI will award half of the contingency as WA; half will be held by STFC

Profiling contingency is important: needs to appear where needed

Note: early CD-4A is **April 2031**, CD-4A is **April 2032**; project ends **July 2032**; with contingency **July 2033**

Adding an additional 6 months contingency, grants end in March 2034 (CD-4 + 2 years)


Staff costs WPs 1-3 & 5	2555.5	3775.6	4126.5	4025.3	3523.2	3191.4	2389.6	576.0			
Staff costs with delay			3775.6	4126.5	4025.3	3523.2	3191.4	2389.6	576.0		
Surplus/Deficit			350.9	249.7	-252.4	-331.8	-801.7	-1813.7	-576.0		

Contingency WPs 1, 2, 3 & 5	25/26	26/27	27/28	28/29	29/30	30/31	31/32	32/33	33/34			
Add 1 year staff effort; reprofile FY27/28+					252.4	331.8	801.7	1813.7	576.0	3.8		
Add indexation			132.1	144.4	140.9	123.3	111.7	83.6	20.2	0.8	1.035	Indexation
Equip & Cons	132.8	342.9	380.1	283.5	189.7	134.5	21.0	0.0	0.0	1.5	0.2	Scale
Silicon Costs			692.5	692.5						1.4	0.5	Yield
Indexation	0.0	63.1	184.4	175.8	193.5	209.7	172.6	47.7		1.0	1.01	
Total WPs 1, 2, 3 & 5	132.8	342.9	1204.8	1120.5	583.0	589.6	934.4	1897.3	596.1	7.4	20%	

Contingency WP 4	25/26	26/27	27/28	28/29	29/30	30/31	31/32	32/33	33/34			
Original estimate	146.7	261.5	503.5	421.1	200.6					1.5		
Total WP4	146.7	261.5	503.5	421.1	200.6					1.5	27%	

Backup

Full Infrastructure In-kind Contribution



- Detector partnerships ~30% in-kind (project detector)

GPB estimated cost = \$300m

Project cost = \$200m; in-kind contribution = \$100m


- ATHENA costing

\$7.3m material, \$13.7m staff effort = \$21m total (with indexation \$9.1m + \$17.1m = \$26.2m)

At today's exchange rate (\$1 = £0.78), ATHENA indexed cost is £7.1m + £13.3m = £20.4m

UK bid appears high by comparison: £9.5m + £18.4 = £27.9m plus contingency

Project Delivery (Academics and Senior Research Fellows)



▪ Birmingham (NP/PP)

Peter Jones (co-PI, WP1)
Paul Newman (WP1)
Laura Gonella (WP1)

▪ Brunel (PP)

Liliana Teodorescu (WP1)

▪ Glasgow (NP)

Daria Sokhan (co-PI, WP2)
Ken Livingston (WP2 leader)
Derek Glazier (WP2)

▪ Lancaster (PP/AP)

Harald Fox (WP1)
Graeme Burt (WP4 leader)
Robert Apsimon (WP2)

▪ Liverpool (NP)

Marielle Chartier (WP1)

▪ Oxford (PP)

Georg Viehhauser (WP1 leader)
Todd Huffman (WP1)
Claire Gwenlan (WP1)

▪ York (NP)

Dan Watts (WP3 leader)
Nick Zachariou (WP3)
Mikhail Bashkanov (WP3)

▪ STFC RAL (PP)

Ian Sedgwick (WP1)
Fergus Wilson (WP1)

▪ STFC DL (NP/AP)

Roy Lemmon (WP1)
Marcello Borri (WP1)
Richard Smith (PM)
Niklas Templeton (WP4)

Key


NP = Nuclear Physics

PP = Particle Physics

AP = Accelerator Physics

PM = Project Manager

WP1 – Silicon Tracker (BHM, BRU, LAN, LIV, OXF, STFC DL, STFC RAL)



▪ Central tracking and vertexing

Approximately 10 m² detector comprising **vertex layers**, **barrel layers** and **disks**

65 nm MAPS technology driven by physics requirements and validated with simulations

Proposed ITS3 sensor meets EIC needs


- Partnership with CERN minimises risk

EIC will use same concept for **vertex layers**:


- Wafer-scale, stitched sensors, thinned and bent around the beam pipe

EIC specific development needed for the **barrel layers** and **disks**:

- large area stitched sensor (not wafer scale), and “conventional” low mass support structures





ALICE-ITS3 development




ePIC-SVT Vertex and Barrel layers

ePIC-SVT Vertex layers

Project Delivery (Project Organisation)



Cost Estimation – WP1 – Definition of Tasks/Responsibilities



NOTES		
Sagitta L3 = 11% Si area – 50 staves, 200 sensors Spares: 10 staves, 40 sensors		
Sagitta L4 = 26% Si area – 78 staves, 624 sensors Spares: 12 staves, 96 sensors		
TO BUILD: 150 staves, 960 sensors, 480 modules (w/o yield)		
Prototypes below mean multiple versions of an object during the R&D phase.		
We will work within the international collaboration and some of these development will be common/have overlap to work on disks, e.g. DAQ.		
Tasks in grey start, and in some cases complete, in the preliminary phase.		
ACTIVITY		INSTITUTES
Sensor design	ITS3 ER2 (submission in preliminary phase, Q1-24)	RAL-TD
	ITS3 ER3	RAL-TD
	EIC LAS v1 (submission in preliminary phase, Q2-24)	RAL-TD
	EIC LAS v2 (pre-production)	RAL-TD
	Production	RAL-TD
Sensor characterisation	ITS3 ER2 (delivered by foundry Q3-24)	BHM DL-TD BRU LIV LAN
	ITS3 ER3	BHM DL-TD BRU LIV LAN
	EIC LAS v1 (delivered by foundry Q4-24)	BHM DL-TD BRU LIV LAN
	EIC LAS v2	BHM DL-TD BRU LIV LAN
	Production testing QC/QA (incl. wafer probing)	BHM BRU
Flexible Printed Circuit (FPC)	Prototypes: design & testing	DL-TD OX
	Pre-production design & testing	DL-TD OX
	Production design & testing	DL-TD OX
Modules	Prototypes: assembly & testing	BHM RAL-PPD (BRU) LIV
	Pre-Production: assembly & testing	BHM RAL-PPD (BRU) LIV
	Production: assembly & testing (QC/QA)	BHM RAL-PPD (BRU) (LIV)
Powering	Regulator characterisation	BHM OX (RAL-PPD)
	Data and grounding schemes development	BHM OX (RAL-PPD)
	Current source development and testing	BHM OX (RAL-PPD)
	Prototypes SP chain testing	BHM OX (RAL-PPD)
	Pre-production SP chain testing	BHM OX (RAL-PPD)
	Production SP chain validation	BHM OX (RAL-PPD)
Staves with cooling	Mechanical stave structure prototypes development and testing	OX DL-TD
	Cooling prototypes development & testing	OX DL-TD
	Prototypes stave w/cooling & FPC assembly & testing	OX DL-TD
	Pre-production stave w/cooling & FPC assembly & testing	OX DL-TD
	Production assembly & testing (QC/QA)	OX DL-TD
Loading modules onto staves (electrical staves)	Prototypes electrical staves loading & testing (mech, el, therm)	RAL-PPD DL-TD
	Pre-production electrical staves loading & testing (mech, el, therm)	RAL-PPD DL-TD
	Production electrical staves loading & testing (mech, el, therm)	RAL-PPD DL-TD
DAQ	Sensor & module: prototypes characterisation	DL-TD BRU LAN
	Sensor & module: pre-production testing	DL-TD BRU
	Sensor & module: production testing	DL-TD BRU
	Electrical staves: prototype testing	RAL-PPD BHM
	Electrical staves: pre-production testing	RAL-PPD BHM
	Electrical staves: production testing	RAL-PPD BHM
	L3 and L4 testing (after integration)	RAL-PPD BHM
Tooling	Module assembly tooling: prototypes, pre-prod, prod	BHM
	Stave loading tooling: prototypes, pre-prod, prod	RAL-PPD
	Integration tooling	OX RAL-PPD
Global support & integration	Prototype global support development and testing	OX DL-TD (LIV)
	Pre-production global support development and testing	OX DL-TD
	Production global support development and testing	OX DL-TD
	L3 and L4 assembly	OX RAL-PPD
	L3 and L4 electrical/mech/therm tests	OX RAL-PPD
	Shipment of layers to BNL	OX RAL-PPD

.....



Gantt chart: EIC Full Infrastructure Project

Version: 2.0
Author: Peter Jones (p.g.jones@bham.ac.uk)

Version: 2.0
Author: Peter Jones (p.g.jones@bham.ac.uk)

[illegible]

ID	Task	Start Time	End Time	Duration Q
WP1 - Silicon Tracker				
1	Sensor Design	01/07/2025	30/09/2027	9
2	Sensor Characterisation	01/07/2025	31/12/2027	10
3	Sensor Production Testing (QC/QA)	01/01/2028	31/12/2028	4
4	Flexible Printed Circuits – Design and Testing	01/07/2025	30/09/2027	9
5	Flexible Printed Circuits – Production and Testing	01/10/2027	31/12/2028	5
6	Modules - Prototypes	01/01/2026	31/03/2027	5
7	Modules - Preproduction	01/04/2027	30/06/2028	5
8	Modules - Production	01/07/2028	31/12/2029	6
9	Staves - Prototypes	01/07/2025	31/12/2026	6
10	Staves - Preproduction	01/01/2027	31/12/2027	4
11	Staves - Production	01/01/2028	31/12/2029	8
12	Staves - Loading	01/04/2029	30/09/2030	6
13	Global Support and Integration - Design, Prototyping and Testing	01/07/2026	30/06/2028	8
14	Global Support and Integration - Production and Testing	01/07/2028	31/12/2029	6
15	Layers Assembly and Testing	01/01/2030	31/12/2030	4
16	Shipment to BNL	01/01/2031	31/03/2031	1
17	Installation and Commissioning	01/04/2031	30/06/2032	5
WP2 - Electron Trigger				
1	Vacuum and Window Design	01/07/2025	30/06/2026	4
2	Prototype Development (2 x timepix4)	01/07/2025	31/12/2026	6
3	Final Design	01/07/2025	31/12/2027	10
4	PCB for Prototype Tracking Layer (12 x Timepix 4)	01/01/2026	30/06/2028	10
5	Mechanics and Cooling	01/01/2027	31/12/2028	8
6	Construction	01/09/2028	31/12/2030	10
7	Delivery to BNL	01/01/2031	31/01/2031	1
8	Installation and Commissioning	01/04/2031	30/06/2032	5
WP3 - Luminosity Monitor				
1	Pair Spectrometer - Design and Prototype	01/07/2025	31/03/2028	11
2	Pair Spectrometer - Construction and Testing	01/04/2027	31/03/2030	12
3	Pair Spectrometer - Delivery to BNL	01/04/2030	30/04/2030	1
4	Pair Spectrometer - Installation and Commissioning	01/07/2030	30/06/2032	8
5	Photon Detector - Design and Prototype	01/07/2025	31/03/2028	11
6	Photon Detector - Construction and Testing	01/04/2027	31/03/2030	12
7	Photon Detector - Delivery to BNL	01/04/2030	30/04/2030	1
8	Photon Detector - Installation and Commissioning	01/07/2030	30/06/2032	8
9	All Development	01/07/2025	30/06/2032	28
WP4 - Accelerator				
1	Cryomodule and Tooling Design	01/07/2025	01/05/2027	8
2	Acceptance testing of US cavities	01/01/2027	01/06/2028	6
3	Procurement of cryomodules subsystems	01/01/2027	01/03/2028	6
4	Cryomodule Assembly	01/05/2027	01/06/2029	9
5	Final testing and shipping	01/06/2029	31/12/2029	3
6	Define scope of LLRF synchronisation and feedback task	01/07/2025	30/09/2025	1
7	Conceptual design of beam feedback system	01/10/2025	31/12/2026	5
1	Conceptual design of LLRF synchronisation system	01/10/2025	31/12/2026	5
2	Technical specification of LLRF synchronisation system	01/01/2027	31/12/2027	4
3	Technical specification of beam feedback system	01/01/2027	31/12/2027	4
4	Document integrated LLRF synchronisation and feedback system	01/01/2028	30/06/2028	2
5	Simulate and optimise design of EO BPM with BC parameters	01/07/2025	31/12/2025	2
1	Build and bench test EO-waveguide prototype	01/01/2026	30/06/2026	2
2	Beam test EO prototype at EIC	01/07/2026	30/06/2027	4
3	Review results and finalise design	01/07/2027	31/12/2027	2
4	Technical design of EO-BPM for EIC	01/01/2027	30/06/2028	6
5	Model BBU threshold current for combined 1st and 3rd harmonic cavities for electron cooler and pre-cooler	01/07/2025	31/12/2026	6
6	Determine initial budget for electron cooler and pre-cooler	01/01/2027	30/06/2028	10
7	Optimisation of bunch stretching schemes for cooler and pre-cooler at 100 GeV ant 275 GeV	01/10/2025	30/09/2027	8
8	Design of required tunable beamlines to switch between operation modes	01/10/2027	31/12/2028	5