

eRD107: Longitudinally separated Forward HCal (LFHCal)

August 28, 2023


**Friederike Bock (ORNL)
for the eRD107 consortium**

Participating institutes: ORNL, BNL, FNAL, ISU, GSU, Yale, UCR, UTK, Valpo


The General Idea

Concept:


- CALICE AHCAL inspired W/Fe-Scintillator calorimeter with SiPM on-tile-readout (modification since last review)
- Two main parts:
 - ▶ LFHCal built mostly out of $10 \times 20 \times 140 \text{ cm}^3$ 8M modules
 - ▶ Insert built out of 2 halves surrounding the beam pipe
- **LFHCal:**
 - ▶ 4 layers of tungsten + 61 layers of steel interleaved with scintillator material
 - ▶ Transverse tower size $5 \times 5 \text{ cm}^2$
 - ▶ Multiple consecutive tiles summed to 7 longitudinal segments per tower
- **Insert:**
 - ▶ 10 layers of tungsten + 54 layers of steel interleaved with scintillator
 - ▶ Hexagonal tiles of 8 cm^2 each read-out individually




LFHCal 8M Scintillator Tile assembly



- Tiles of $\approx 0.4 \times 5 \times 5 \text{ cm}^3$ with dimples individually wrapped in ESR foil assembled in a grid of 4x2 tiles
- 8 tiles are backed by a flexible PCB equipped with 8 SiPMs and LEDs sandwiched with Kapton foil
- Flexible PCB wrapped around side of absorber to connect with long PCB along the side of the module
- Tiles either injection molded or machined out of cast sheets



Rec



- High granularity needed to try to distinguish shower maxima close to beam pipe
- **LFHCal:**
 read out in 7 layers longitudinally (5 or 10 SiPMs summed)
 desirable min measurable tower energy 3-5 MeV, max 20-30 GeV in single tower segment
- **insert:**
 read out every single tile
 desirable min measurable tower energy $\sim 0.1 - 0.5 \text{ MeV/tile}$

- SiPMs mounted to flexible PCBs, passive signal transfer to back side of calorimeter using long transfer PCB
- 1 SiPM-HGCROC (up to 70 channels) per 8M module (56 channels), 320 HGCROCs for insert readout

① Prototype tile production using machining & injection molding

- ▶ Ongoing machining studies for tile production
- ▶ Mold production for injection molded tiles in progress

② Reconstruction optimization

- ▶ Realistic implementation of geometry in ePIC software stack
- ▶ Integration with high granularity insert in progress

③ Tile Characterization


- ▶ Vendor survey of SiPM vendors and types conducted
- ▶ First light yield studies of machined tiles with different dimple sizes, machining techniques and wrappings ongoing

④ Sensor board development

- ▶ First prototype of sensor board delivered and being tested prior to test beam

⑤ Small test module assembly

- ▶ First prototype of single segment of 8M module being assembled for TB in Sep./Oct.



(a) Light-tight Faraday box with connector panel



(b) SiPM on a PCB board



(c) T10-SiPM holder with readout wire



(d) T10-SiPM holder with SiPM board






(e) SiPM holder with hole to allow 400 nm LED photon





(f) Two T10-SiPM holders on shelf



- Started machining tiles at ORNL in LFHCal geometry
 - Established procedures for high quality tile machining
- Produced tiles with different dimple sizes
- Received machined tiles from Eljen
 - larger variance in size than anticipated
- Mold in production for original sized tiles with different dimples, 1/4-size tiles & hexagonal tiles for insert



Reconstruction optimization




- Implementation of realistic geometry in ePIC software stack
- Single pion response in accordance with expectations & meeting YR requirements
- First version of clusterization algorithm working well at high E
- Integration with insert ongoing
- Ongoing studies to improve clusterization algorithm using ML started during several workshops
 - ▶ ePIC Calorimeter Workshop (Apr. 23')
 - ▶ HGS-HiRe Power Week - Machine Learning (Jul. 23')




- Two parallel test setups for tile characterization (Yale & ORNL)
- SiPM test board produced
- Developed multiple 3D printed test stands for single SiPM & Cosmics data taking
- Vendor survey for available $\approx 1 \times 1$ mm & 3×3 mm SiPMs regarding
 - Availability
 - Data accuracy in data sheets
 - Production stability


Yale







ORNL



Histogram of Breakdown Voltage



- Single photon spectra for every SiPM
- Characterized different SiPM gains as function of V_{ov}
- Started measuring cosmics MIP light yields for different SiPMs types
- Testing different scintillator materials (EJ-200, BC-408 & Fermilab injection molded)
- Systematic evaluation of impact of machining defects ongoing



Test beam plans & preparation Sep. 23'



Dates: 6th – 13th Sept.

Main purpose: Scintillator characterization & HGCROC tests

- Parasitic to FoCal-H test beam at SPS
- Setup consists out of maximum 10 layers of 8M tile assemblies
- Fixed in plastic frame with cut outs in the center with slots for holding assemblies
- Each 8M tile assembly with 8 channel readout
- Connected via 16 channel \approx 8 m micro-coax-cable assemblies to CAEN DT5202 64ch CITIROC SiPM readout unit or HGCROC

Main expected measurements:

- Light yields per tile
- Cross talk estimates of different tiles
- Use it as testing setup for SiPM-HGCROC while taking data with Focal-H using CAEN & VMM read-out
- If placed behind FoCal-H, measure part of leakage



Test beam plans & preparation Oct. 23'

Dates: 11th – 18th Oct.


Main purpose: Scintillator characterization & HGCROC tests

- Parasitic with FoCal-E at PS
- Setup consists out of maximum 14 layers of 8M tile assemblies & corresponding layers of absorber plates out of steel or tungsten
- Fixed in steel frame with slots for tile assemblies & absorber plates
- Same read-out setup as for September test beam


Main expected measurements:

- Shower profile measurements with different absorbers
- Cross talk estimates of different tiles
- Use it as testing setup for SiPM-HGCROC


8M tile assembly



absorber plate




Steel frame



1 Tile production optimization using machining & injection molding (04/24)

- Evaluation of different scintillator machining techniques
- Comparative review of different vendor capabilities regarding adherence to tolerances as well as optimizing the light yield and its stability for large number of tiles
- Documentation of procedures for optimizing the light yield of injection molded tiles during the production process
- High quality prototype tiles to equip two 8M modules for test beam studies




2 Reconstruction optimization (09/24)

- Write-up of optimization results from simulations

3 Sensor board development (03/24)

- First prototype of sensor board for Si-PM readout (together with eRD109)




4 Test module assembly (04/24)

- First prototype of full 8M module

5 Tile Characterization (08/2024)

- Write-up of test bench & test beam measurement for all assembled tile-prototypes
- First concept of a monitoring system to be installed in the LFHCAL



eRD107 FY24 Funding request

Table 4: Total funding request by institution for each R&D activity.

activity	cost in FY24 k\$			total cost in FY24 k\$
	ORNL	FNAL	Yale	
Tile Production R&D	15.0	11.6	5.0	31.6
Tile Char. (Lab)	0	0	19.0	19.0
Sensor Board	23.0	0	0	23.0
Total	38.0	11.6	24.0	73.6

Table 3: Total funding request and breakdown by institution.

institute	cost in FY24 k\$				total cost in FY23 k\$
	eng. and tech.	material	equipment	travel	
ORNL	13.0	20.0	0	5.0	38.0
FNAL	11.6	0	0	0.0	11.6
Yale	0	5.0	16.0	3.0	24.0
Total	24.6	25.0	16.0	8.0	73.6

Table 5: Estimated funding requests for LFHCAL R&D efforts in FY25-26.


Task	Estimated cost in \$ per year	
	FY25	FY26
mechanical engineering	30K	20K
electrical engineering	30K	20K
materials	40K	40K
test beam support	10K	10K
total	110K	90K

- Funding for continuation of started R&D mainly on tile production & characterization
- Largest fraction of funding for equipment & material procurement
- Small travel funds for TB travel & visits at different test sites
- Significant in-kind contribution from universities and laboratories for assembly, simulation and data analysis

Table 6: Funding allocation and approximate completion dates for respective milestones for FY24.

Institute	Item	Cost per item in \$	Number of items	Total cost in \$	To be compl. by
ORNL	Tile Production R&D:				Q2/2024
FNAL	cast material			15K	
FNAL	raw material + dopant			(in kind) 0K	
ORNL/UTK/Yale	injection molder setup + operation	180/h	64h	11.6K	Q4/2023
ORNL	tile assembly		40h	(in kind) 0K	Q1/2024
ORNL	travel			5K	
Yale	Tile Characterization (Lab Bench):				Q3/2024
Yale	scintillator material characterization		100h	(in kind) 0K	Q1/2024
Yale	source measurement unit & led pulser, other material	19K	1	19K	
GSU/Yale/UCR	tile lightyield testing		160h	(in kind) 0K	Q3/2024
Yale	travel			3K	
ORNL	Sensor Board:				Q1/2024
ORNL	electrical engineering	180/h	72h	13K	Q4/2023
ORNL	connectors & cables			5K	Q4/2023
ORNL	sensor board production, assembly		160	5K	Q4/2023
ORNL/UTK	testing		40h	(in kind) 0K	Q1/2024
UTK/Yale/BNL	Reconstruction Optimization:				2025
UTK/Yale/BNL	simulations/digitization/reconstruction/analysis		640h	(in kind) 0K	
Total				73.6K	


Thanks!



LFHCal in Numbers


- Acceptance: $1.2 < \eta < 2.8$
- Interaction length: $6.5\lambda/\lambda_0$
- Inner modules ($R < 1\text{m}$) equipped with machined scintillator tiles & 3mm SiPMs
- Outer modules equipped with injection molded tiles & 1.3mm SiPMs
- 565,760 SiPMs, 60,928 read-out channels
- CD3-A/B procurement: Steel, Tungsten & SiPMs
- Current estimated total cost: $\sim 15.8\text{M}$

parameter	LFHCal
inner x, y	60 cm
outer radius (envelope)	270 cm
η acceptance	$1.2 < \eta < 3.5$
tower information	
x, y	5 cm
z (active depth)	130 cm
z read-out	10 cm
# scintillator plates	65 (0.4 cm each)
# absorber sheets	61 (1.52 cm steel)
	4 (1.52 cm tungsten)
interaction lengths	$6.5 \lambda/\lambda_0$
Sampling fraction f	0.035
# towers	8704
# modules	
8M	1050
4M	76
# read-out channels	$7 \times 8704 = 60,928$




Insert in Numbers

- Acceptance: $2.7 < \eta < 4.4$
- Interaction length: $7.5\lambda/\lambda_0$
- Similar sampling structure as LFHCal
- 10 layers of tungsten, 55 layers of steel
- 360 hexagonal tiles with SiPMs per layer, staggered positions in different layers
- Maximum η coverage with minimum dead area in combination with LFHCal
- CD3-A/B procurement: Steel, Tungsten & SiPMs
- Current estimated total cost: $\sim 1\text{M}$




HGCROC testing



Test setup in ORNL EIC lab:

- We have a KCU105 with the testboard and H2GCROC3
- Firmware/Software done and working
- Testing the feasibility of the ASIC for the EIC:
 - Signal shapes
 - Gain, dynamic range reach
 - TOA/TOT calibration



Internal injection test on all channels (one shown)

Prepared the H2GCROC3 testboard:

- Readout board is compatible with the CAEN commercial unit for ease of use
- 2 H2GROC per board - to test the I2C in series
- Communication board to test the readout and cables used in final detector:
 - Samtec HQDP for 1-10 m length

