




sPHENIX Tracker
2023-08-23, Run 25926 - All EBDCs, BCO 128330850911
0-Field Cosmics Data





sPHENIX commissioning and integration and plan for first science


David Morrison (BNL)
Gunther Roland (MIT)

co-spokespersons

June 2022








April 2023





Some of the many students and postdocs working on sPHENIX ...



... and some of the many technicians, engineers, trades, and others too.

sPHENIX ribbon cutting January 2023

**Asmeret Berhe
DOE Director
Office of Science**

**Vanessa Chan
DOE Director
Office of
Technology
Transitions**




Smooth sailing? Successful sailing.

- PD-2/3 schedule included 14 months of float, early finish in October 2021
- Direct effects of COVID — workforce availability, construction logistics
- Indirect effects of COVID — electronics lead time
- Conflict in Ukraine — necessitated switch from neon to argon for TPC
- Logistics around Run 22
- Beryllium beam pipe
- Complex process readying for DOE's Approval to Operate decision




Beryllium beam pipe



Plan A

Plan B



From installation to commissioning with beam



Received approval to operate on **May 18** (operating gas, HV, LN2/LHe)

SC solenoid cool-down **May 19–25**; ramped to operating current **May 31**

Plan presented in 2022 BUR

Weeks	Designation
0.5	Cool Down from 50 K to 4 K
2.0	Set-up mode 1 (Au+Au at 200 GeV)
0.5	Ramp-up mode 1 (8 h/night for experiments)
11.5	sPHENIX Initial Commission Time
9.0 (13.0)	Au+Au Data taking (Physics)
0.5	Controlled refrigeration turn-off
24.0 (28.0)	Total cryo-weeks

Implicit assumption: all infrastructure is ready

Weeks	Details
2.0	low rate, 6-28 bunches
2.0	low rate, 111 bunches, MBD L1 timing
1.0	low rate, crossing angle checks
1.0	low rate, calorimeter timing
4.0	medium rate, TPC timing, optimization
2.0	full rate, system test, DAQ throughput
12.0	total


May 18 + 12 weeks: August 10

End of RHIC beam: August 1


The success of our commissioning period would not have been possible without the dedicated support by C-AD and their flexibility in accommodating our requests

Into the home stretch: “Approval to Operate”

- Major focus was safety: documentation, procedures, interviewing shift crew, electrical code inspections, signage & labeling, hand rails, walking surfaces, and many other things
- For some of us, unfamiliar review territory — about nine weeks to complete
- Received approval from Brookhaven DOE site office on May 18 — fantastic!



Transition from project to operations



DO: Kin Yip (BNL)
RC: Stefan Bathe (Baruch)
CTF: John Haggerty (BNL),
 Caroline Riedl (UIUC),
 Jin Huang (BNL)



sPHENIX control room

Commissioning report

- Infrastructure — e.g., the SC solenoid
- Ten detectors: MVTX, INTT, TPC, TPOT, EMCal, iHCal, oHCal, MBD, sEPD, ZDC/SMD
- DAQ/Trigger
- Operations
- Online monitoring
- Offline computing — archiving, event assembly, reconstruction, analysis

90 page document on commissioning

1  Report

tag:
version: 0.1
DOI: unspecified
date: August 16, 2023


2 Commissioning Status: August 2023

3 sPHENIX Collaboration

4 Abstract


5 sPHENIX began commissioning with beam on May 18, 2023 with the receipt of approval to
6 operate. This document details the progress made to date bringing the sPHENIX detectors and
7 its associated infrastructure to a state in which physics running can begin.

Commissioning report synopsis






- SC magnet: **complete**
- Min Bias Detector: **complete**
- Outer HCal: **complete**
- Inner HCal: **complete**
- EMCal: **complete**
- TPC outer tracker: **complete**
- ZDC: **complete**
- INTT: triggered mode **complete**, testing streaming mode
- MVTX: successful operation; response to backgrounds underway
- TPC: operating HV achieved, tracks observed; work on stability of operations
- DAQ: all detectors have been read out; work continues on stability and rate
- SMD: some channels still to read out
- sEPD: successful readout; detector and electronics installation completed after August 1 end of run

Superconducting magnet — works perfectly



Very stable operation after faulty QLI ribbon cable replaced

Crossing angle studies: MBD determines $\sigma_{z\text{-vertex}}$



Effect on z-vertex distribution as expected
More severe effect on luminosity than predicted


n.b. fewer collisions outside of useful z_{vertex} range reduces TPC charge dependent calibrations

Global detectors: ZDC, MBD, sEPD




ZDC North-South Correlation

6/13/2023




ZDC-MBD correlation

7/21/2023





sEPD-MBD correlation


8/30/2023




Hadronic Calorimeter



Electromagnetic calorimeter




>99% live channels; growth of SiPM leakage current consistent with expectation




reconstructed di-photon mass — in ADC counts — peak corresponds to π^0

Calibrating the calorimeter energy scale



Simulated Energy Deposit in Scintillators[MeV]



sPHENIX Preliminary Outer HCal - High Gain
Electromagnetic Energy Scale: Mean = 283 ADC/MeV




MAPS vertex detector (MVTX)



Correlation multiplicities in two outermost MVTX layers, across multiple FELIX cards


Primary vertex location: INTT and MBD

July 28, 2023




offset from $z = 0$ was expected

August 18, 2023




Standalone MVTX vertex reconstruction



Three layers of MVTX
used to reconstruct
primary and
secondary vertex





(MVTX) x-y projection




(MVTX) z-r projection



Cosmic data in MVTX and INTT






MVTX, INTT, and TPOT



sPHENIX Experiment at RHIC
Data recorded: 2023-08-11
Run / Event: 25475/9007
Cosmics

sPHENIX Experiment at RHIC
Data recorded: 2023-08-11
Run / Event: 25475/1085
Cosmics

sPHENIX Experiment at RHIC
Data recorded: 2023-08-11
Run / Event: 25475/3147
Cosmics



Helical fit to cosmic tracks in 1.4 T solenoidal magnetic field




sPHENIX Time Projection Chamber

100 Hz ZDC, MBD Prescale: 2, HV: 4.45 kV GEM, 45 kV CM, X-ing Angle: 2 mrad


2023-06-23, Run 10931 - EBDC03 reference frame 85

Au+Au $\sqrt{s_{NN}}=200$ GeV




Initial validation of TPC drift velocity

First TPC data with collisions were used to validate the calculation of the gas drift speed to within 10%




ionization arrives over this time window



Operational challenges with TPC


- Post-installation TPC exhibiting challenges with HV stability not present in extensive pre-installation system tests
- Met with ALICE TPC experts to discuss experience — both TPCs share similar design
- Continuing to step through specific plan of investigation and possible remediation




Operational challenges with MVTX

Beam halo at $r > 2$ cm enough to overwhelm the readout and turn off chips after a few seconds of running


Nine ALPIDE chips of one MVTX stave




One ALPIDE sensor



before collimation



after collimation



time →


blue: normal operation
white: in recovery

Acquired few minutes of $\beta^* = 5m$ data just before RHIC valve box incident


Offline event assembly and reconstruction



- Worked with SDCC to address infrastructure-level stability issues with large disk array (Lustre)
- Have used ATLAS-developed PanDA to successfully run our complex workflow to assemble and reconstruct events for analysis
- Still require collision and corresponding laser data to validate TPC distortion correction



Remaining tasks



- Tremendous progress before/during Run 23 — at the same time, quite a bit still needs attention
- TPC investigations and remediations
- MVTX firmware mods to decrease reset time — possible tungsten beam pipe collar?
- Exercise computing facility with archived data and simulations to further validate and automate processing infrastructure
- Significant cosmic running prior to Run-24 for alignment and to validate tracking


System	Before Run 2024	During Run 2024
Trigger	Firmware and software development of calorimeter triggers	First operation of calorimeter triggers with beam
TPC	<ul style="list-style-type: none"> • FEE firmware completion • tests of zero suppression • completion of MJACK to mitigate SEU • development of digital current • cosmic ray data with and without zero suppression 	<ul style="list-style-type: none"> • Stable operation with HV • collision data with and without zero suppression • testing of digital current and SEU mitigation
DAQ	<ul style="list-style-type: none"> • Tests with zero suppression in calorimeters and TPC • Throughput and livetime tests with multievent buffering • Development of offline event building • Any additional development needed to achieve routine 15 kHz • Improvements in reliability, data integrity, and error handling 	<ul style="list-style-type: none"> • Tuning of zero suppression • Timing of detectors to new triggers • Spin: integrate ZDC, SMD and MBD digital scaler information into GL1
MVTX	<ul style="list-style-type: none"> • Field off cosmic data for tracking development and alignment • Development of mitigation strategies for background and lock-up 	<ul style="list-style-type: none"> • Field off and field on collision data for tracking development and alignment • Tests of mitigation strategies for background and lock-up
INTT	Field off cosmic data for tracking development and alignment	Field off and field on collision data for tracking development and alignment
EMCal HCal	(HCal) tower-by-tower cosmics analysis	Demonstration of design energy resolution and response uniformity

Table 6 in commissioning document




Plan for first sPHENIX science

Pushing toward first science




PC: Perepelitsa (UC)
Pub: Sickles (UIUC)
SB: Rosati (ISU)
S&C: Pinkenburg (BNL)
TG conveners
Calibration: Sakaguchi, C. Roland
Calo Calibration: Hodges, Seidlitz
Tracking: Frawley (FSU)

Coordinating the effort toward first science




- Physics coordination meetings — cuts across topical groups
 - Identifying topics that can be pursued with available Run 23 data
 - Identifying workforce to tackle specific analyses
 - Coordinates with simulation and computing effort — sufficient computing power is available to support needed activities
- Topical group conveners are organizing post-QM “kick-off” meetings for a jet performance paper, $dN/d\eta$, $dE_T/d\eta$, and $\pi^0 v_2$ and other topics

Timeline for first sPHENIX science



- Complicated by premature end to Run-23
 - Lack planned six weeks of physics data (n.b. fewer than the 9 weeks in 2022 BUR)
 - Reduced data available for systematic checks, calibration development
- Recall previous experience ~ six months from first RHIC run to QM'01
- Many performance plots shown at QM'23
- First “standard candle” soft physics ($dN/d\eta$, v_n) — end of CY'23
- Unique RHIC capabilities (e.g., unbiased jets) longer timescale
 - detailed jet performance studies — end of CY'23
 - taking cosmic ray data for alignment and validation of data processing

Ingredients for first sPHENIX science





- event selection and centrality determination
- event plane determination: MBD event plane resolution
- primary and secondary vertex location: INTT and MVTX reconstruction
- π^0 , η : EMCal clustering, energy calibration
- jets: energy calibration, background subtraction, jet finding, data based UE subtraction
- systematically performing calibrations and reconstruction steps needed for first physics
- even with the limited data set: wide range of standard candle measurements that can be performed, and in-roads to be made towards full calorimeter jet physics at RHIC
- this effort needs to be balanced with preparations for Run-24

Au+Au centrality and event plane based on MBD



sPHENIX Internal


MBD - Run 00022982, $|z_{\text{MBD}}| < 30 \text{ cm}$





n.b. STAR beryllium beam pipe isn't upstream/downstream symmetric; removes a useful systematic check on MBD response

Calorimetric jets — EMCal, iHCal, and oHCal combined


sPHENIX
Run/Event: 21615 / 1362
Collisions: Au + Au @ $\sqrt{s_{NN}} = 200 \text{ GeV}$
Peripheral Collision



sPHENIX Preliminary
Au+Au $\sqrt{s_{NN}} = 200 \text{ GeV}$
Run/Event: 21615/1362
Peripheral Collision




Initial tracking performance




Cluster residuals before static and time-dependent corrections in the expected sub-cm (\mathbf{z}) and mm ($\mathbf{r\phi}$) ranges — TPC only

What do we need to progress to Run 24 successfully?




- Continued priority in technical support and trade work — e.g. for detector access that is currently planned
- Electrical engineering support from ATRO — critical for completing firmware mods for TPC and INTT
- Engineering support for MVTX background mitigation plans we may decide to implement (e.g., tungsten beam pipe collar)
- Support for Invenio development (e.g., search on document content) and other tools for collaboration information management

Summary, concerns, prospects



- Tremendous progress readying sPHENIX for physics — lots of excitement throughout collaboration with students/postdocs taking major roles
- Concerned about near-term morale, job prospects of students/postdocs — potential collaboration workforce implications
 - Will have open forum on Friday within collaboration to discuss this; ALD has welcomed a subsequent discussion to be able to share her perspectives and field questions
- There are unfinished commissioning activities — activities that can be done w/o beam are continuing now
- Plan of work leading to Run-24 described in commissioning document
- Standard candle physics soon; detailed studies with data to prepare for


sPHENIX Project Summary Schedule



Critical Path runs through:

- Cal Elect. Preprod. Procure
- Cal. Elect. Fab/Assy
- Cal Elect. Sys. Testing
- EMCal Fab/System Testing
- Early Completion
- Installation, Integrated Test and Commissioning





21

12

19

61

17

41

15

51

13

31

11

11

9

6

7

2



