


Longitudinally segmented Forward HCal (LFHCal) & Insert

Friederike Bock (ORNL)
EIC Project Detector Calorimetry Review
December 6-7, 2022

Electron-Ion Collider

Concept & Assembly



Reminder Charge questions

- ① Are the technical performance requirements complete for all detector systems that employ SiPMs, documented, and understood?
- ② Are the plans for achieving detector performance and **construction sufficiently developed and documented for the present phase of the project?** (I.e., are they commensurate with the initiation of the SiPM procurement?)
- ③ Do the present detector system designs and the resulting SiPM specifications meet the performance requirements with a low risk of cost increases, schedule delays, and technical problems?
- ④ **Are the fabrication and assembly plans for the detector systems consistent with the overall project and detector schedule and sufficiently developed to initiate the SiPM procurement?**
- ⑤ **Are the plans for detector integration in the EIC detector appropriately developed to initiate the SiPM procurement?**
- ⑥ Have previous review recommendations been adequately addressed to initiate the SiPM procurement?
- ⑦ **Have ES&H and QA considerations been adequately incorporated in the SiPM procurement planning?** (This includes a quality assurance plan for receipt of material meeting specifications.)
- ⑧ Is the procurement approach sound and the procurement schedule credible?

The General Idea

Concept:



- CALICE AHCAL inspired W/Fe-Scintillator calorimeter with SiPM on-tile-readout (modification since last review)
- Two main parts:
 - ▶ LFHCal built mostly out of $10 \times 20 \times 140 \text{ cm}^3$ 8M modules
 - ▶ Insert built out of 2 halves surrounding the beam pipe

LFHCal:

- ▶ 4 layers of tungsten + 61 layers of steel interleaved with scintillator material
- ▶ Transverse tower size $5 \times 5 \text{ cm}^2$
- ▶ Multiple consecutive tiles summed to 7 longitudinal segments per tower


Insert:

- ▶ 10 layers of tungsten + 54 layers of steel interleaved with scintillator
- ▶ Hexagonal tiles of 8 cm^2 each read-out individually




General Facts on Read-out LFHCal & insert

Rec





- High granularity needed to try to distinguish shower maxima close to beam pipe
- **LFHCal:**
read out in 7 layers longitudinally (5 or 10 SiPMs summed)
desirable min measurable tower energy 3-5 MeV, max 20-30 GeV in single tower segment
- **insert:**
read out every single tile
desirable min measurable tower energy $\sim 0.1 - 0.5$ MeV/ tile
- SiPMs mounted to flexible PCBs, passive signal transfer to back side of calorimeter using long transfer PCB
- 1 SiPM-HGCROC (up to 70 channels) per 8M module (56 channels) in the back, 320 HGCROCs for insert readout



LFHCal in Numbers


- Acceptance: $1.2 < \eta < 3.5$
- Interaction length: $6.5\lambda/\lambda_0$
- SiPMs not accessible after installation
 - ▶ Inner modules ($R < 1\text{m}$) equipped with machined scintillator tiles & 3mm SiPMs $\rightarrow \sim 11\% = 83200 \text{ tile/ SiPMs}$
 - ▶ Outer modules equipped with injection molded tiles & 1.3mm SiPMs $\rightarrow \sim 89\% = 482560 \text{ tile/ SiPMs}$
- 565,760 SiPMs, 60,928 read-out channels
- CD3-A/B procurement: Steel, Tungsten & SiPMs
- Current estimated total cost: $\sim 15.8\text{M}$

parameter	LFHCal
inner x, y	60 cm
outer radius (envelope)	270 cm
η acceptance	$1.2 < \eta < 3.5$
tower information	
x, y	5 cm
z (active depth)	130 cm
z read-out	10 cm
# scintillator plates	65 (0.4 cm each)
# absorber sheets	61 (1.52 cm steel)
	4 (1.52 cm tungsten)
interaction lengths	$6.5 \lambda/\lambda_0$
Sampling fraction f	0.035
# towers	8704
# modules	
8M	1050
4M	76
# read-out channels	$7 \times 8704 = 60,928$






Insert in Numbers

- Acceptance: $3.5 < \eta < 4.4$
- Interaction length: $7.5\lambda/\lambda_0$
- Similar sampling structure as LFHCaI
- 10 layers of tungsten, 55 layers of steel
- Maximum η coverage with minimum dead area in combination with LFHCaI
- 360 hexagonal tiles with SiPMs per layer, staggered positions in different layers
→ 23400 SiPMs/tiles & read out channels
- Scintillator & SiPM assemblies accessible during end-of-year access, designed to be possible to be annealed every few years or replaced
- CD3-A/B procurement: Steel, Tungsten & SiPMs
- Current estimated total cost: $\sim 1\text{M}$





Construction Procedure

- Construction done in units of modules:
1058× 8M, 76× 4M, right & left side of insert
- Construction & QA steps per unit:
 - ① Assembly of absorber structure without cover-plate
 - ② Assembly of tiles & PCB per layer & testing
 - ③ Installation of tile assemblies in absorber structure
 - ④ Connection of transfer PCB & connectivity tests
 - ⑤ Mounting of cover plate
 - ⑥ Cosmics tests per module



ES&H & QA considerations

- Permanent test setup of 8×8 M-modules included in purchase order, allows for
 - ▶ test beam measurements of final modules during construction and operation phases
 - ▶ final qualification of performance without significant shower leakage
 - ▶ reproduction of possible problems in the lab
- Procurement of SiPMs includes 1% margin for possible production losses
- Foreseen SiPM testing process:
 - ▶ Vendor testing and qualification for V_{op} within 0.1V/ delivery unit
 - ▶ Testing at PCB vendor after flex-PCB assembly (connectivity)
 - ▶ Cosmics tile assembly testing & classification for each module prior & after installation in module (same procedure for insert)



Simulated Performance



Current R&D Programm





Reminder Charge questions

- ① **Are the technical performance requirements complete for all detector systems that employ SiPMs, documented, and understood?**
- ② **Are the plans for achieving detector performance and construction sufficiently developed and documented for the present phase of the project?** (I.e., are they commensurate with the initiation of the SiPM procurement?)
- ③ Do the present detector system designs and the resulting SiPM specifications meet the performance requirements with a low risk of cost increases, schedule delays, and technical problems?
- ④ Are the fabrication and assembly plans for the detector systems consistent with the overall project and detector schedule and sufficiently developed to initiate the SiPM procurement?
- ⑤ **Are the plans for detector integration in the EIC detector appropriately developed to initiate the SiPM procurement?**
- ⑥ Have previous review recommendations been adequately addressed to initiate the SiPM procurement?
- ⑦ Have ES&H and QA considerations been adequately incorporated in the SiPM procurement planning? (This includes a quality assurance plan for receipt of material meeting specifications.)
- ⑧ Is the procurement approach sound and the procurement schedule credible?





Simulated performance




- Implementation of realistic geometry in ePIC software stack
- Single pion response in accordance with expectations & meeting YR requirements
- First version of clusterization algorithm working well at high E
- Integration with insert ongoing
- Ongoing studies to improve clusterization algorithm using ML started during several workshops
- Ongoing development of full fledged software compensation






- ## Yale



Histogram of Breakdown Voltage




LFHCaI Scintillator & SiPM Characterization






- Single photon spectra for every SiPM
- Characterized different SiPM gains as function of V_{ov}
- Started measuring cosmics MIP light yields for different SiPMs types
 - 1.3×1.3 mm $\approx 12 - 14$ p.e. for machined tiles
 - 3×3 mm $\approx 60 - 76$ p.e for machined tiles
- Testing different scintillator materials (EJ-200, BC-408 & Fermilab injection molded)
- Systematic evaluation of impact of machining defects ongoing

Insert Scintillator & SiPM Characterization



- Initially compared LY using Cosmics for $\approx 3 \times 3 \times 0.35 \text{ cm}^3$ CMS machined & injection molded tiles at $V_{ov} = 2V$
 - machined: $\approx 8.3 \text{ p.e.}$
 - injection molded: $\approx 5.6 \text{ p.e.}$
- As expected approx. 30% reduction in LY for injection molded tiles
- Improved wrapping and painting increased LY by up to 30%
- Hexagonal machined tiles $\approx 30\text{-}35\%$ more light yield $\approx 15 \text{ p.e.}$ at $V_{ov} = 2V$
- Irradiation test planned for the fall



SiPM requirements

- Considering 2 different types depending on radiation, ideally relatively high fill factor ($> 40\%$) & reasonably many pixels (15-25 mm pitch),
 - ▶ 1.3.3 mm low radiation ($\sim 90\%$) LFHCal & insert with annealing i.e:
Hamamatsu S13360-1325PE (2668 pixel, fill 47%, PDE $\sim 25\%$)
Hamamatsu S14160-1315 (7284 pixel, fill 49%, PDE $\sim 32\%$)
 - ▶ 3 mm high radiation ($\sim 10\%$) LFHCal i.e:
Hamamatsu S13360-3025PE (14400 pixel, fill 47%, PDE $\sim 25\%$)
Hamamatsu S14160-3015 (39984 pixel, fill 47%, PDE $\sim 25\%$)
 - ▶ Prefer newer generation due to larger number of pixel allowing not to saturate
- Vop Selection:
 - ▶ Groups with same Vop selection $\pm 0.1\text{-}0.2\text{V}$ for LFHCal, grouped according to 8M module (520)
 - ▶ Groups with same Vop selection $\pm 0.05\text{V}$ for insert, grouped according to layer (360)
 - ▶ HGCROC allows individual channel voltage trim for gain adjustment,

Summary Charge Questions

- ① Are the technical performance requirements complete for the forward HCal detector systems that employ SiPMs, documented, and understood?

Yes

- ② Are the plans for achieving detector performance and construction sufficiently developed and documented for the present phase of the project? (I.e., are they commensurate with the initiation of the SiPM procurement?)

Yes

- ③ Do the present detector system designs and the resulting SiPM specifications meet the performance requirements with a low risk of cost increases, schedule delays, and technical problems?

Yes

- ④ Are the fabrication and assembly plans for the detector systems consistent with the overall project and detector schedule and sufficiently developed to initiate the SiPM procurement?


Yes

- ⑤ Are the plans for detector integration in the EIC detector appropriately developed to initiate the SiPM procurement?


Yes

- ⑥ Have previous review recommendations been adequately addressed to initiate the SiPM procurement?


Back-up




LFHCal 8M Scintillator Tile assembly



- Tiles of $\approx 0.4 \times 5 \times 5 \text{ cm}^3$ with dimples individually wrapped in ESR foil assembled in a grid of 4x2 tiles
- 8 tiles are backed by a flexible PCB equipped with 8 SiPMs and LEDs sandwiched with Kapton foil
- Flexible PCB wrapped around side of absorber to connect with long PCB along the side of the module
- Tiles either injection molded or machined out of cast sheets




HGCROC testing



Test setup in ORNL EIC lab:

- We have a KCU105 with the testboard and H2GCROC3
- Firmware/Software done and working
- Testing the feasibility of the ASIC for the EIC:
 - Signal shapes
 - Gain, dynamic range reach
 - TOA/TOT calibration



Internal injection test on all channels (one shown)

Prepared the H2GCROC3 testboard:

- Readout board is compatible with the CAEN commercial unit for ease of use
- 2 H2GROC per board - to test the I2C in series
- Communication board to test the readout and cables used in final detector:
 - Samtec HQDP for 1-10 m length

