

ePIC TOF Structure Thermal Test

08 May 2024

Yu-Tang Wang, Yi Yang
National Cheng Kung University



Test Setup



NI 9213 DAQ

- 16 channels
- Accuracy:
 - High-resolution mode : <0.02 °C
 - High-speed mode : <0.25 °C



Heat source (x 9)

- Ceramic plate (5Ω): ~500°C

Thermocouple (x 16)

- Type E: -250°C ~ 900°C



Environmental chamber

- Inner dimensions: 40 x 50 x 60 cm³
- Temperature: -40 °C ~ 100 °C (± 0.2 °C)
- Humidity: 10% ~ 98% ($\pm 2.5\%$)



Cooling system

- Temperature: 3 °C ~ 32 °C

Test Setup




3D-printed holder



Water out


Water in

Power vs current




● source 2 ● source 3 ● source 5


Cooling water @ 18 °C




Cooling water @ 19 °C



Cooling water @ 23.5 °C



Cooling water @ 26 °C



Do-to-list

- Flow meter will be installed this week
- New acrylic fixture will be ready this week
- Simulation is ongoing (new undergrad is working on it)



CC Water/min.	
5-50	32
10-110	33
20-300	34

