



Science and
Technology
Facilities Council

OB FPC prototyping


WP3 Electrical interfaces

Update on Low TLR OB prototype


- Design completed and reviewed;
- Flexis under production at RPE LTU;
 - Potential delay with payments and T&C agreement due funds approvals within STFC; (proactively acting on it)
- Discussion on distribution:
 - Oxford, summer student (time pressure);
 - LANL;
- Towards a tests plan:
 - Oxford w RAL have setup ready for summer student;
 - Daresbury working of finalisation;
 - LANL;

Recap on the Low TRL OB prototype

Defined design on 18/03



Reviewed design on 16/05




Learning curve on how to exchange info between LUT and STFC (we use different design sw)


Current status/updates

3

- ❖ Preliminary design (based on latest information from Andy, v03) is complete and sent for review this Monday



Schematic cross-section




Base cross-sections for the FPCs (reminder)

4

Cover layer - FDI-A-24 + spacer 25um


Added on top for insulation (folding approach)



Cover Layer 12.5um

Height (H):	77
Height1 (H1):	45
Width (W):	60
Width1 (W1):	70
Separation (S):	130
Thickness (T):	14
Dielectric Constant (Er):	3.4
Impedance Calculated	
Differential Impedance (Z_0):	101.01

Total thickness ~100um



Note: estimating done in
CITS25 software from Polar
Instruments



World Leaders in PCB
Faultfinding and Controlled
Impedance Measurement

Outcome:
difference in impedance
is not too significant (2 Ohm)

Cover Layer 25um

Height (H):	89
Height1 (H1):	45
Width (W):	60
Width1 (W1):	70
Separation (S):	130
Thickness (T):	14
Dielectric Constant (Er):	3.4
Impedance Calculated	
Differential Impedance (Z_0):	99.10

Total thickness ~110um

Notes:

- polyimide film 25um presently at LTU is available,
- polyimide film 12.5um presently at LTU not available yet

Width of traces – 70um

Space between traces – 130um

Pitch of traces – 200um

Main FPC: layers


5




Bridge-FPCs

6

B-FPC Type A



B-FPC Type B






Implemented modification

4

DONE: „Serpentines„ on shorter high speed trace are added

B-FPC Type B
(signal layer)




All resistors and capacitors are 0201
(0.6mm x 0.30mm)

Features of mounting SMD components and connectors



9

For manufacturability increasing SMD components and connectors are mounting on small flexible carriers (flex-mounts) by soldering and after that connecting to board or cable by SpTAB

**Flex-mounts
for SMD component**





SMD components on flex-mounts



Flex-mounts for connectors



Connectors on flex mounts



- Procurement:
 - Quantities:
 - 4 fully assembled (2 DL, 2 OX);
 - 4 M-FPC bare;
 - 16 B-FPC:
 - 8 B-FPC-A bare;
 - 8 B-FPC-B bare;
- Sent agreement to sign, with STFC admin




Bill to:
Marcello Borri
Daresbury Laboratory
Technology Department
Science and Technology Facilities Council
Sci-Tech Daresbury, Daresbury, WA4 4AD
The United Kingdom
Phone: +44 01925 603 085
E-Mail: marcello.borri@stfc.ac.uk

LLC "Research and Production Enterprise "LTU"
bld.3, Novgorodskaya str.,
Kharkiv, Ukraine, 61145
email: info@ltu.ua
www.ltu.ua

QUOTATION nr. ePIC SVT-1
Quotation date: June 10, 2024

Test plan

- Interface board design started;
- Test plan to be finalised at Daresbury (next week);
- Todd at Oxford ready to test (via summer student) and has an initial plan;



Science and
Technology
Facilities Council



Science and
Technology
Facilities Council

Thank you

Facebook: Science and
Technology Facilities Council

Twitter: @STFC_matters

YouTube: Science and
Technology Facilities Council