

Controls System Progress

Lee Flader 24/07/01



@BrookhavenLab

Current Efforts

- Requirements writing
- Slow Controls network planning
 - Integration
 - Example
- Equipment selection

Requirements Writing

- Standardizing requirements for controls performance
 - Control data parameter list
 - Subdetector system descriptions
 - Interlock description
- Specification for EPICS server underway:
 - Initial estimation of data load complete
 - Equipment selection in progress

Common Parameter Requirements

- HV/LV bias
- Leakage current
- ASIC/crystal/board temperature
- Gas & Cooling
 - Flow
 - Pressure
 - Temperature
 - Humidity
 - Dew Point


Requirements Writing – Progress

| Detector Group | Detector | Contact | Survey Response | 1st Draft | 1st Draft Review | 2nd Draft | 2nd Draft Review | CD2 Final Draft |
|----------------|---------------------------|--|-----------------|-------------|------------------|-------------|------------------|-----------------|
| Forward/Back | Far Forward | nathaly.santiesteban@unh.edu; ajentsch@bnl.gov; | Y | Complete | In Progress | Pending | Pending | Pending |
| | Far Backward | simon.gardner@glasgow.ac.uk; kenneth.livingston@glasgow.ac.uk; | Y | Complete | In Progress | Pending | Pending | Pending |
| | Luminosity | Nick.zachariou@york.ac.uk | N | Complete | Complete | In Progress | Pending | Pending |
| Ecal | Forward ECal | gvisser@indiana.edu | Y | In Progress | Pending | Pending | Pending | Pending |
| | Barrel Imaging Ecal (BIC) | sjoosten@anl.gov; zurek@anl.gov; jmetcalfe@anl.gov; | Y | Complete | Pending | Pending | Pending | Pending |
| | Backwards Ecal | munoz@jlab.org | Y | Complete | Complete | In Progress | Pending | Pending |
| Hcal | Forward Hcal | Friederike.Bock@cern.ch; Miguel.arratia@ucr.edu; | N | In Progress | Pending | Pending | Pending | Pending |
| | Barrel Hcal | stefan.bathe@baruch.cuny.edu; mconnors@gsu.edu; | Y | Complete | Pending | Pending | Pending | Pending |
| | Backwards Hcal | Leszek.kosarzewski@gmail.com | Y | In Progress | Pending | Pending | Pending | Pending |
| Polarimetry | Polarimetry | frathmann@bnl.gov | Y | In Progress | Pending | Pending | Pending | Pending |
| PID | TOF | geurts@rice.edu | Y | Complete | Pending | Pending | Pending | Pending |
| | pfRICH | ayk@bnl.gov | Y | In Progress | Pending | Pending | Pending | Pending |
| | dRICH | mcontalb@fe.infn.it | N | In Progress | Pending | Pending | Pending | Pending |
| | hpDIRC | kalicy@cua.edu | N | Complete | In Progress | Pending | Pending | Pending |
| Trackers | Si Trackers | Epsichtermann@lbl.gov; Laura.gonella@cern.ch; | N | Complete | Pending | Pending | Pending | Pending |
| | Gas Trackers | Kagnanvo@jlab.org; maxence.vandenbroucke@cea.fr; | N | Complete | Pending | Pending | Pending | Pending |


Requirements Writing – Expected Load

- Network requirements based on SC survey results
 - DB storage on the order of 10s of TB/year
 - Data rates on the order of 100Mbps – 1Gbps

SC Network Planning – EIC Integration




SC Network Planning – DAQ Integration




SC Network Planning – Rack Integration Plan 1

- Use AB Micro850 PLCs
 - Stored in rack within IR
 - Pros
 - High flexibility
 - Minimizes rack integration efforts
 - Cons
 - High cost
 - Needs EPICS driver development
 - No redundancy support




SC Network Planning – Rack Integration Plan 2

- Use Control/CompactLogix PLC for each detector
 - PLC stored in counting house
 - RIO distributed as needed
- Pros
 - PLCs can share RIO
 - Redundancy supported*
 - Existing EPICS drivers
- Cons
 - Enclosure planning
 - Cabling efforts



SC Network Planning – Subsystem Integration

- Recommend ControlLogix or CompactLogix models for EPICS integration
- ControlLogix supports redundancy
- PLCs reside in DAQ room, RIO reside in the IR




Example Implementation - pfRICH

- Power Supplies (Saverio Minutoli)
 - Weiner LV mainframe and modules
 - CAEN HV mainframe and stackable power supplies
- Gas System (Prashanth Shanmuganathan)
 - Dry nitrogen system
 - Supply & vent side pressure transducers
 - Flow meter
 - Hygrometer*
- Cooling (Dan Cacace)
 - Chillydyne circulator
 - Polyscience chiller
- Detector Operation
 - Light system for calibration

Example Implementation - pfRICH

- Subsystem integration plan
 - CompactLogix PLC & Point IO remote modules interface with power, gas, and cooling
 - Custom hardware is reduced to circuitry needed for front end monitoring & calibration
- Reoccurring need for front end HW across detectors
 - Light system for cal
 - Front end temp



Equipment Selection & Equipment Approval Process

- New effort started in the last weeks for approved equipment selection
- Goals:
 - A systematic means of approving hardware for the project
 - A reference table of approved hardware
 - A common hardware environment:
 - Simplified system integration
 - Smaller knowledge base for troubleshooting
 - Reduced development effort

Equipment Selection & Equipment Approval Process

- What will be evaluated?
 - Power supplies
 - Chillers/circulators
 - Motor controllers
 - PLCs
 - Sensors
 - Protocol gateways
- Who can help?
 - Anyone that is interested

Thank you