

EPIC/ToF – Stave Prototyping activities & construction plan

Sushrut Karmarkar, Andy Jung

November 21st, 2024

My very personal view – all up for discussion!

◊ Stave prototyping activities – happening now!

- ◊ Stave pathfinder institute for prototyping is Purdue + FEA baselining
- ◊ Module thermal FEAs, activities between Santa Cruz, ORNL, and Purdue
- ◊ Thermal testing + limited FEAs at NCKU

◊ Production of staves

- ◊ Parts of raw material via Purdue and production via NCKU, ship back to US

◊ Module assembly

- ◊ Purdue has experience & capacity for wire bonding, limited PED between Purdue & Santa Cruz
- ◊ ORNL has also experience and capacity, I do not know details

◊ Stave system tests

- ◊ Only Stave thermal testing, see above
- ◊ Fully equipped Stave's with mock heaters or somewhat more real heaters
 - ◊ ORNL: details to be confirmed
 - ◊ Purdue can do system integration, we do have chiller for up to -10 C tests or soon (few weeks) also CO2 test setup that can be used as a facility

◊ Stave integration

- ◊ Likely gantry supported
- ◊ My biased view:
 - ◊ CMS pixel experience is with high TC grease for workability, screws and a CF clamp for good contact to stave

◊ TOF assembly

- ◊ Global support tube at Purdue, limited mounting tests at Purdue. Ensure all is OK, then ship to BNL
- ◊ At BNL

Old prototype efforts from R&D 2023/2024

- ◊ Need – the first stave prototype manufactured at Purdue in Summer 2023 warped upon curing.
- ◊ This warpage comes from internal residual stresses from anisotropic coefficient of thermal expansion mismatch between different materials/structures used in the stave.
- ◊ We cannot completely remove this internal stress, but we can minimize it by controlling the cure cycle of the composite.

- ◊ In this talk –
 1. Manufacturing simulation results
 2. Report on raw material procurement – all delivered and available at Purdue CMSC.
 3. Manufacturing plan – Dec 2023 deliverables
 4. Upcoming task list





Nomenclature –
miniSTAVE : 300 mm long
halfSTAVE : 1.35 m long
(half length)
fullSTAVE : full length




Cross-section always is the actual designed cross-section

Motivation of problem in curing everything together at manufacturer recommended cure cycle


- Unsymmetric core with vastly different (anisotropic) CTEs/effective CTE
- Thus, results in warpage at recommended curing temperature of 180°C(350°F)
- Up to 300-micron deflection on each side (600 micron effective) on a 300 mm long miniSTAVE prototype – up to 3.6//7.2// mm for a 2.6 m fullSTAVE



- ⬠ APEX Carbon Flex Core – PMT material data.
- ⬠ Cannot use regular “homogenized” properties since the shape of the honeycomb is not “honeycomb”/hexagonal – need to write out the homogenization math using Mechanics of Structure Genome code - upcoming
- ⬠ Currently modelled explicitly
- ⬠ Adhesive modelling between two laminates NOT implemented. Modelled as continuous.




- ⬠ CFOAM modelled as isotropic homogeneous solid.
- ⬠ This is okay for now
- ⬠ There is huge non-homogeneity in the actual product → need to study the effect of these on thermal performance and see if it is acceptable






CFOAM® 35 HTC TYPICAL PROPERTIES (METRIC)

	Test	Units	CFOAM35 HTC
Nominal Density	ISO 12985-2	cc	0.40-0.50
Compressive Strength	ISO 18515	MPa	1.50-1.80
Compressive Modulus	ISO 18512	MPa	100-400
Tensile Strength	ISO 12986-2	MPa	0.9-1.0
Shear Strength	ISO 12986-2	MPa	1.0-4.0
Coefficient of Thermal Expansion	ISO 14420	ppm/°C	1.9-2.1
Thermal Conductivity	ISO 12987	W/m-K	140-180
Maximum Operational Use Temperature	Environment Dependent	°C	400
Electrical Resistance	ISO 11713	milliohm-cm	3-4
Pore Volume	Microscopy	%	> 70%
Mean Pore Size	Microscopy	Microns	1200




Aitor Amatriain, Corrado Gargiulo, Gonzalo Rubio, Numerical and experimental study of open-cell foams for the characterization of heat exchangers, International Journal of Heat and Mass Transfer, Volume 217,2023,124701,ISSN 0017-9310, <https://doi.org/10.1016/j.ijheatmasstransfer.2023.124701>.




- ◊ Changing cure cycle such that we get the lowest peak strain in the part
- ◊ We achieve the same degree of cure and thus the needed stiffness. Flow behavior of the resin changes (thus wetting/co-curing of the foam and honeycomb core to facesheet)
- ◊ This might affect thermal performance (?) – don't know how.

- ◊ ***Manufacturing 2 miniSTAVE prototypes in the week of Dec 11th, 2023, with two different cure cycles to see which one will give minimum warpage/deformation.***



Study cure cycle for lowest peak strain in composites




1. miniSTAVE (x2) – 1 retained at Purdue, 1 for NCKU – 18th December 2023
2. halfSTAVE (x1) – mid – January 2024
3. Heat Transfer Analysis – miniSTAVE – 20th December 2023
4. Thermal testing of miniSTAVE – late January 2024
5. Structural performance FEA and loading tests/validation – mid February 2024

NOTES –

I missed the radiation materials meeting on 11th December 2023 – will need to get some of these structural and thermal materials radiation tested.

Who do I talk to for this ? Zhenyu Ye ?

Future work – can potentially move to CFRP tube insert instead of SS or titanium – depending upon thermal performance – we have one such tube and we will evaluate the same with a miniSTAVE prototype




Upcoming – Heat Transfer Analysis on miniSTAVE, halfSTAVE, and fullSTAVE

Project


- Model (A4)
 - Geometry Imports
 - Geometry
 - Materials
 - Coordinate Systems
 - Connections
 - Mesh
 - Named Selections
- Steady-State Thermal (A5)
 - Initial Temperature
 - Analysis Settings
 - Temperature - Wall Pipe
 - Convection - Carbon Foam
 - Convection - Honeycomb
 - Convection - Face Sheets
 - Convection - Steel Tube
 - Radiation - Face Sheet
 - Radiation - Honeycomb
 - Radiation - Carbon Foam
 - Radiation - Steel Tube
 - Heat Flux
 - Heat Flux 2
- Solution (A6)
 - Solution Information

Details of "Mesh"


Display	
Display Style	Use Geometry Setting
Defaults	
Physics Preference	Mechanical
Element Order	Program Controlled
<input type="checkbox"/> Element Size	Default (6.7562e-002 m)
Sizing	
Quality	
Inflation	
Advanced	
Statistics	



Validation of the heat transfer analysis with testing and comparison to thermal-IR imaging with mock heaters



Picture from a different test / for representational purpose only!



Mock heaters

End connectors will be temporarily attached