The ePIC Barrel Imaging Calorimeter

Mechanics and Sectors

Sylvester Joosten
Argonne National Laboratory

BIC General Meeting February 14, 2025





News

CD3a Scintillating Fiber procurement in progress

New preliminary design for tracker mechanics and integration

Almost ready for Pb/ScFi test article production at Argonne

CD3a Procurement of Scintillating Fibers




- Open bidding ongoing
- Bidding requires vendors to send sample of 100 fiber canes for testing, (canes are production length, i.e. 4.54m)
- Test results factor in ultimate choice of fiber vendor
- Multiple vendors are participating in the bidding, and all fibers for testing are currently at Argonne
- Next step is to send all fibers to U. Regina for testing
- Procedure to choose fiber vendor based on results will start in 4 weeks
- CD3a included a first portion of our fibers, CD3b will include a next batch
- Still TBD: can we use CD3a fibers for preproduction or do we need a separate fiber order?

BIC Mechanical Design

- New experienced engineer (Vic Guarino) for imaging layer mechanics working towards preliminary design
 - Concept: mount 9-chip AstroPix modules on staves, then slide staves on rails integrated in the CF frames
 - Components made out of extruded aluminum to minimize cost
 - Next step: manufacture first mockups to validate and improve design, due early April 2025
- Working on small contract with Purdue for delamination testing (both for CF-Pb interface and of the Pb/ScFi matrix itself)
- Expecting updated envelopes from EIC engineers soon
 - Likely pain-point on electron-going side where there is very little space between ESB and the DIRC lenses/expansion volumes (see Zisis' talk)



Imaging layer mechanical design (WIP)



Road Towards Test Articles



Sectors:

- Sector test article production setup, including swager, presslet (mini press) almost ready to build first test article (due by April 2025)
- 5500 sq. ft sector production space ready to move in equipment







