

# eRD108: MPGD for ePIC

## FY24 Progress Report & FY25 Proposal

---

EIC Project R&D and DAC Meeting

Aug 29<sup>th</sup> 2024

F. Bossù on behalf of  
eRD108 consortium



# eRD108 Consortium and ePIC MPGD-DCS

**Project ID:** eRD108

**Project Name:** R&D on cylindrical MPGDs towards an EIC detector

Brookhaven National Laboratory (BNL): Craig Woody

Florida Institute of Technology (FIT): Marcus Hohlmann

CEA Saclay: Francesco Bossù, Maxence Vandenbroucke

Temple University (TU): Matt Posik, Bernd Surrow

Jefferson National Accelerator Facility (JLab): Kondo Gnanvo



**Project Members:**

BNL: B. Azmoun, A. Kiselev, M. Purschke, C. Woody

FIT: M. Hohlmann, P. Iapozzuto

CEA Saclay: S. Aune, F. Bossù, A. Francisco, M. Vandenbroucke

TU: M. Posik, B. Surrow

JLab: K. Gnanvo



**Contact Person:** Kondo Gnanvo; [kagnanvo@jlab.org](mailto:kagnanvo@jlab.org)

eRD108



Yale




VANDERBILT  
UNIVERSITY



ePIC MPGD Detector Subsystem Collaboration

# MPGD in ePIC tracking system



MPGDs complement the silicon tracker:

- redundancy hit points
- faster hits for track finding

Three systems:

- **CyMBaL**: Cylindrical Micromegas Barrel Layer at  $R=55\text{cm}$
- **$\mu$ RWELL Barrel Outer Tracker**: planar detectors at the DIRC surface
- **$\mu$ RWELL End Cap Tracker**: disks in the forward and backward regions

eRD108 program about Cylindrical MPGD detectors with 2D readout:


- Development of 2D cylindrical Micromegas detectors: funded in FY24
- Development of a cylindrical  $\mu$ RWELL prototype: completing the FY23 program

## Update on 2D readout R&D and scale 1:1 prototype


CEA Saclay

# CyMBaL

## CyMBaL: Cylindrical Micromegas Barrel Layer



## Design of a module



### Requirements:

- Spatial resolution  $\sim 150\mu\text{m}$
- Time resolution  $\sim 10\text{ns}$
- Light, less than 1% X0
- Hermetic
- Tight space:  $\sim 5\text{cm}$  in R
- Magnetic field:  $\sim 2\text{T}$

- 32 module: 8 modules in  $\phi$  times 4 modules in z
- Overlaps in  $\phi$  and in z for hermeticity
- 1024 readout channels/module
- 32K readout channels

### Module dimensions

Z = 67 cm

R\* $\phi$  = 48 cm

### Active zone dimensions


Z = 59 cm

R\* $\phi$  = 46 cm

# CyMBaL – Technology and planned R&D

## CLAS12 resistive Micromegas

- Material budget  $\sim 0.4\%$
- Working in high radiation environment and in  $B=5T$
- Taking data since 2017
- Fit in tight spaces



## Upgrade for ePIC: 2D readout

## R&D planned activity in FY24


- Finalization of the analysis of the 2023 test beam data on the 2D prototypes
- Complete the tests on resistive patterns and 2D readout with additional prototypes
- Design and production of a large scale prototype with a 2D readout using CLAS12 mechanics
- Mechanical mock-up for a scale 1:1 prototype
- Test performance of a small 2D prototype with a 1mm drift gap with different gas
- Test the use of carbon fiber instead of FR4 to lower even further the material budget

# CyMBaL – Test 2D prototypes


## 12x12 cm2 prototypes to test:

- 2D readout patterns
- Resistive layer motifs
- very-low material budget (0.2% X0)


### *R/O Patterns and resistive motifs*




D1



D2



D4




D3

- Pitch and interstrip variations
- ASACUSA like motifs
- Variation of resistive layer (full, strips, grid)

### *Low material budget*

- Achieved by stretching the flexible PCB on a carbon frame




R/O flexible PCB (Kapton)




Stretched Kapton foil over a Carbon fiber frame bulked with a micromesh




# CyMBaL – 2023 Test Beam analysis



- Data taken in June 2023 at MAMI
- 880 MeV electron beam
- ALPIDE-based reference telescope
- Tested several prototypes
- Important multiple scattering effect
- Geant4 simulations to cross check




~30cm from ref tracker




~78cm from ref tracker



# CyMBaL – 2023 Test Beam analysis



D1



D2

D1:



- pitch variation from 0.5 mm to 1.5 mm
- top layer interstrip 25%

D2:

- 1 mm pitch,
- Interstrip 50%

*Credit: Samy Rafael Plocher*


Resistive layer: full, high resistivity  $\sim 10\text{M}\Omega/\square$



**Amplitude fraction**, 25% low, 50% too high: the sharing of the signal is not uniform, interstrip with values round 30% should work better

**Residues** (uncorrected): D1 provides less than  $200\mu\text{m}$  with 1mm pitch




# CyMBaL – 2023 Test Beam analysis



D3 and D4 : ASACUSA-like patterns

Resistive layer:

- D3: resistive strips of 500 $\mu$ m pitch
- D4: full layer with resistivity  $\sim 500\text{k}\Omega/\square$



*D3 visible drift of the signal max along the resistive strips*


**Amplitude fraction**, better sharing, as both r/o layers are on the same plane

**Residues** (uncorrected): Dominated by multiple scattering

# CyMBaL – Tests in Saclay

- Cosmic rays test bench refurbished
- Silicon telescope (same as in beam test) added to the system
- Mechanical structure to hold up to six prototypes
- Synchronization of MM and ALPIDE DAQs
- Development of software tool for the data taking and analysis optimization
- The DAQ system is now adapted to be portable to a next beam test

*Credit: Dylan Neff*



# CyMBaL – Toward a scale 1:1 prototype


---

## *Main tasks*


- Refurbishing of the production of resistive cylindrical MM tiles
  - Tensioning system
  - Change of the photoresistive material
  - Production of a CLAS12 tile to validate the process
- Design of the readout PCB
  - Choice of the 2D pattern
  - Connector choice

# CyMBaL – Toward a scale 1:1 prototype

## *Refurbishing of the production of resistive cylindrical MM tiles*



Mesh tensioning system: it allows us to reach low tension values



- Bulk of a metallic and a resistive CLAS12 PCB
- Bent in shape


### *Photo-resistive material:*

- Pyralux out of production
- Switched to Vacrel (already used in the past)
- Difference in the film thickness (from 64  $\mu\text{m}$  to 50  $\mu\text{m}$ )
- Difference in composition:
  - Check adherence
  - Adjustments of the development stage
- Tests with 40x40cm<sup>2</sup> detectors ongoing

# CyMBaL – Toward a scale 1:1 prototype

## *Design of readout PCB*

- Choice of the readout pattern depends on the finalization of the tests on the small 2D prototypes. Expected by December.
- Tests of a new small form factor connector:
  - 40 pin Kel connector with flat micro-coaxial cables already procured
  - Transition card Mec8 → Kel connector has been designed
  - Tests will start in September



**Connector and cable validation**



**With Kel connectors on detector**





# CyMBaL – Plans

---

## *Toward the scale 1:1 prototype*

- Finalization of 2D pattern tests: End 2024
- CLAS12 tile production and test: Fall 2024
- Design of the 2D PCB: End 2024
- Design of mechanics for a ePIC prototype: End 2024
- Procurement and production: Apr 2025
- Tests: July 2025

## *Additional tasks in FY24*

- Mitigation studies for large angle tracks:
  - 1-mm gap small prototype to check spatial resolution and efficiency with different gases.
  - Modification of the small prototype to fit a 1-mm gap ongoing
  - Tests: March 2025
- Thin carbon fiber support as replacement of the FR4
  - Suppliers inquired for a 100 $\mu$ m thick foils
  - Design and tests: Mid 2025




The completion of the FY23 and FY24 programs will bring us to readiness for CD3.  
Therefore no funding request for FY25 R&D

## Preparation for JLAB Beam Test

Kondo Gnanvo, Marcus Hohlmann, Pietro Iapozzuto,  
Alexander Kiselev, Huong Nguyen  
BNL, Florida Institute of Technology, JLAB, U. Virginia


# Solutions for problems encountered earlier with Cylindrical $\mu$ RWELL Prototype

- Drift foil (Al-mylar) had developed dents during tests at FNAL (Fig.1)
  - Solution: Mechanical refurbishment of drift foil
    - Added honeycomb on outside of foil (Fig.2)
    - Results show stable drift foil with smooth Al cathode inside (Fig.3)
- We observe large leakage current on one sector under HV & we suspect humidity absorption in the  $\mu$ RWELL kapton or dust particles deposited in the  $\mu$ RWELL holes (Fig. 4)



# $\mu$ RWELL Foil Refurbishment Process

- Clean foil with tacky roller
- Monitor dust in cleanroom & gas box
- Bake foil in oven @50°C for 24 hours
- HV test and measuring leakage currents
- If insufficient, possible high-pressure washing of  $\mu$ RWELL foil per CERN recommendation





# $\mu$ RWELL Frame Preparation Process

---

- 3D-reprinting of frames; no epoxy resin coat applied as resin can flake off
- Gas leak testing and HV test for drift foil with a mock-up foil
- Installing  $\mu$ RWELL foil into assembly
- Gas leak test and HV test on final assembled detector with  $\mu$ RWELL foil



# μRWELL prototype timeline

---

- 8/2024 Re-assembly and preparation of μRWELL detector
- 9/2024 HV and gas leak testing
- 12/2024 Source & cosmics tests at FIT
- 2/2025 Participation in beam test at JLAB  
(requires \$10k in FY25 support for shipping detectors & travel)



# $\mu$ RWELL: DAC Recommendations: August 28 & 29, 2023

---

## Recommendations: Outer Barrel $\mu$ RWELL Layer

- 1) Explore the possibility of employing professional design engineers.

Response: **Seung Joon Lee** (JLab senior engineer) joins the PED effort and is leading the mechanical design of the full scale prototype

- 2) Plan for construction and testing of a full-scale prototype with actual  $\mu$ RWELL foil.

Response: we are projecting a full-scale outer  $\mu$ RWELL to be built starting in a few months

## Recommendations: Endcap $\mu$ RWELL layers

- 2) Explore the possibility of employing professional design engineers.

Response: **Seung Joon Lee** (JLab senior engineer) joins the PED effort and is leading the mechanical design of the full scale prototype

- 2) Accelerate the design and development of a prototype.

Response: We have INFN Roma II (**Dr. Annalisa D'Angelo**) in, and they plan to buy an engineering test article for the disks.

- 3) Plan for earliest possible beam tests of a prototype as this is a new technology employed on a large scale.

Response: INFN Roma II plans to buy an engineering test article for the disks.

---

# Backup

# CyMBaL: DAC Recommendations: August 28 & 29, 2023

---

## Recommendations: **Micromegas Barrel Tracker**

- 1) Resolve issues between DAQ systems for MM prototype and beam telescope. Produce beam test results from MAMI.

Response: As shown in the slides, the reconstruction of the data has been done successfully and the analysis performed.

Unfortunately, the level of multiple scattering prevents us to draw firm conclusions from this test


- 2) Continue with full scale prototyping, focusing on critical issues to prepare for CD2/3.

Response: We have shown the progress toward the scale 1:1 prototype

- 3) Complete thin-gap design studies as soon as possible.

Response: The adaptation of the small prototype for the 1mm gap is ongoing and tests will be completed in the first half of 2025

# PED Engineering Test Article: Design & fabrication of full scale $\mu$ RWELL-BOT module



- ❖ **Technology: thin-gap GEM- $\mu$ RWELL hybrid detector**
- ❖ Design by Radiation Detector & Imaging (RD&I) Group @ JLab
  - Mechanical drawing → JLab engineer (**Seung Joon Lee**)
  - GEM,  $\mu$ RWELL, strip R/O → Input from CERN MPT experts
- ❖ Construction and preliminary tests of the module - 05/2025
- ❖ Test article module expected in beam test @ FNAL - 07/2025

# Plans & timeline for PED Engineering Test Article: $\mu$ RWELL-BOT module

[https://indico.bnl.gov/event/24240/contributions/94802/attachments/56662/97253/20240819\\_uRWELL\\_BOT\\_update.pdf](https://indico.bnl.gov/event/24240/contributions/94802/attachments/56662/97253/20240819_uRWELL_BOT_update.pdf)

- ❖ **Jan 2024 – Dec 2024:** Mechanical drawing of all parts of the detector almost completed
- ❖ **Dec. 2024 – Jan. 2025:** Complete design of GEM foils,  $\mu$ RWELL PCB and U-V capacitive-sharing readout → JLab RD&I – CERN MPT
- ❖ **October 2024 – March 2025:** Set up class 1000 Clean Room and infrastructure for assembly and test of the module @ JLab
- ❖ **End January 2024:** Expected delivery of the GEM foils,  $\mu$ RWELL PCB and U-V capacitive-sharing readout
- ❖ **March 2025 – June 2025:** HV test of the GEM foils,  $\mu$ RWELL PCB and assembly into a detector in clean room
- ❖ **June / July 2025 – :** Characterization of  $\mu$ RWELL-BOT engineering test article in cosmic and in beam test (Fermilab or CERN)