

# **eRD107: Longitudinally separated Forward HCal (LFHCal)**

**April 17, 2025**


**Friederike Bock (ORNL)  
for the eRD107 consortium**

**Participating institutes: ORNL, BNL, FNAL, ISU, GSU, Yale, UCR, UTK, UTA, Valpo, Debrecen**

# The General Idea


## Concept:

- CALICE AHCAL inspired Fe-Scintillator calorimeter with SiPM on-tile-readout (modification since last review)
- Two main parts:
  - ▶ LFHCal built mostly out of  $10 \times 20 \times 132 \text{ cm}^3$  8M modules (modified length to accommodate larger amount of services in barrel)
  - ▶ Insert built out of 2 halves surrounding the beam pipe
- **LFHCal:**
  - ▶ 60 layers of steel interleaved with scintillator material
  - ▶ Transverse tower size  $5 \times 5 \text{ cm}^2$
  - ▶ Multiple consecutive tiles summed to 7 longitudinal segments per tower
- **Insert:**
  - ▶ 60 layers of steel interleaved with scintillator
  - ▶ Hexagonal tiles of  $8 \text{ cm}^2$  each read-out individually








# LFHCal 8M Scintillator Tile assembly




- Tiles of  $\approx 0.4 \times 5 \times 5 \text{ cm}^3$  with dimples individually wrapped in ESR foil assembled in a grid of 4x2 tiles
- 8 tiles are backed by a flexible PCB equipped with 8 SiPMs and LEDs sandwiched with Kapton foil
- Flexible PCB wrapped around side of absorber to connect with long PCB along the side of the module
- Tiles either injection molded or machined out of cast sheets








- High granularity needed to try to distinguish shower maxima close to beam pipe
- **LFHCal:**  
 read out in 7 layers longitudinally (5 or 10 SiPMs summed)  
 desirable min measurable tower energy 3-5 MeV, max 20-30 GeV in single tower segment
- **insert:**  
 read out every single tile  
 desirable min measurable tower energy  $\sim 0.1 - 0.5$  MeV/ tile
- SiPMs mounted to flexible PCBs, passive signal transfer to back side of calorimeter using long transfer PCB
- 1 SiPM-HGCROC (up to 70 channels) per 8M module (56 channels) in the back, 320 HGCROCs for insert readout



# Reminder: Remaining eRD107 Milestones

- ① **Tile production optimization using machining & injection molding**
  - ▶ Evaluation of tolerance compliance for machined tiles
- ② **Test module assembly & beam test**
  - ▶ First prototype of full 8M module
  - ▶ Integration of final read-out
  - ▶ Test beam evaluation of prototype (optionally with ECal in front)



## ① Prototype tile production using machining & injection molding



- Evaluation of tolerance compliance for machined tiles completed

## ② Integration of final read-out

- Third iteration of sensor board produced and operated in TB
- First passive summing test board produced
- First test beam with HGCROC read-out for LFHCal completed reading every single SiPM & analysis ongoing




## ③ Preparations for 2025 TB-campaigns & TB analysis

- Test beam analysis from 2023 & 2024 on-going, aiming at paper combined paper for late summer
- Preparations for large scale  $8 \times 8$  M module test beam CERN at SPS & PS in Oct/Nov ongoing




Largest fraction of TB components and efforts from 2024 & 2025 have been financed by PED,  $\approx 1/20$  for 2024 from remaining R&D funds.



- Yale setup created for fully automated tile dimension scanning using X-Y translation stage, camera & UV light source
- Evaluation of outer dimensions of machined tiles & dimple size
- Large scale evaluation possible without significant human intervention




## Molded tiles



## Machined tiles



Fix Plane



- Measured dimensions molded and machined tiles with calipers (for external size) and automated measurement
  - Molded tiles compliant within measurement uncertainties with specifications
  - Machined tiles with significant variations beyond acceptable limits
  - Variations in particular on thickness beyond expected values
- ⇒ Need to incorporate these variations in design and possible specification modifications for the machined tile production

# Test beam - August 2024

**Dates:** 28<sup>th</sup> Aug-11<sup>th</sup> Sept 2024 **Location:** PS - T09




**Main purpose:** First full module test & H2GCROC tests

## Setup:

- Full 8M module testing 65 layers of absorber & scintillator per layer 8 channels (swapping scintillator geometry either 8M module or insert )
- Readout with multiple CAEN DT5202 64ch CITIROC SiPM readout units (2nd week) and H2GCROCs (1st week)
- Had to be postponed from May to August due to delays in deliveries of components & new H2GCROC firmware and boards tested during the ALICE FoCal TB in May 2024

## Main expected measurements:



- Energy resolution estimates for hadrons and electrons for full length module with both read-out versions
- Assessment of longitudinal leakage
- Longitudinal shower development
- Read-out validation
- Part of campaign with EEEMC in front



$\mu$  for calibrations

4 GeV  $e^-$  for first energy resolution

layer 1-8






## Test Beam data:

- 2023: Data primarily used for scintillator evaluation
- 2024: Two large data sets with HGCROC & CAEN read-out collected with massive support from ePIC collaborators from various institutes






## Test Beam analysis:

- Large participation in test beam analysis from grad students & under-grad students
- Common framework developed and being used for all existing TB campaigns, analysis full done in this
- Current focus on establishing stable calibrations (single cell level) for all channels & runs within each data set
- Aiming at full publication in late summer based off the 2023 & 2024 test beam campaigns

## Pedestal run





## $\mu$ beam 5 GeV



# First Calibrated Event displays from last year



$\mu^-$  beam 5 GeV

LFHCal TB: CERN-PS-T09, 09-2024, CAEN read-out  
 $\mu^-$ -beam,  $E_\mu = 5$  GeV, Run 244,  $V_{up} = 45.0$  V  
 Event 18, muon triggered  
 $E_{tot} = 81.10$  mip eq/tile  
 $E_{miss,cal} = 5.66$  mip eq/tile





$\pi^-$  beam 5 GeV

LFHCal TB: CERN-PS-T09, 09-2024, CAEN read-out  
 $\pi^-$ -beam,  $E_\pi = 5$  GeV, Run 264,  $V_{up} = 45.0$  V  
 Event 10  
 $E_{tot} = 296.14$  mip eq/tile  
 $E_{miss,cal} = 27.29$  mip eq/tile





$e^-$  beam 5 GeV

LFHCal TB: CERN-PS-T09, 09-2024, CAEN read-out  
 $e^-$ -beam,  $E_e = 5$  GeV, Run 258,  $V_{up} = 45.0$  V  
 Event 18  
 $E_{tot} = 352.20$  mip eq/tile  
 $E_{miss,cal} = 21.37$  mip eq/tile




p beam 5 GeV

LFHCal TB: CERN-PS-T09, 09-2024, CAEN read-out  
 $p$ -beam,  $E_p = 5$  GeV, Run 270,  $V_{up} = 45.0$  V  
 Event 94  
 $E_{tot} = 579.33$  mip eq/tile  
 $E_{miss,cal} = 39.72$  mip eq/tile



# First Highlights from last year



# Test Beam Plans 2025

**Requested time:** 1 week each

**Main purpose:** Resulution studies

**Location:** CERN SPS (29th Oct) & PS (17th Nov.)

## Setup:



- Very similar to 2024 setup, with more modules
- 8 full 8M modules (ideally 40x40x132 cm)
- Readout with H2GCROCs
- Same setup in both areas

## Main expected measurements:

- Energy resolution for hadrons and electrons
- Assessment of longitudinal/transversal leakage
- Longitudinal shower development
- Final-Flexible PCB validation & first long PCB validation


## Where we are?:

- 8 Absorber structures produced (last 3 at Nickel-plating right now)
- Flex-PCB design available & SiPMs to be delivered in June
- First design of long board available, will be send for prototype production within the next weeks
- Evaluation board for passive summing created and under test




## Milestones

- ① **Tile production optimization using machining & injection molding**
  - ▶ Evaluation of tolerance compliance for machined tiles
- ② **Test module assembly & beam test**
  - ▶ First prototype of full 8M module
  - ▶ Integration of final read-out
  - ▶ Test beam evaluation of prototype (optionally with ECal in front)




## Executive summary

- ① **Prototype tile production using machining & injection molding**
  - ▶ Evaluation of tolerance compliance for machined tiles completed
- ② **Integration of final read-out**
  - ▶ Third iteration of sensor board produced and operated in TB
  - ▶ First passive summing test board produced
  - ▶ First test beam with HGCROC read-out for LFHCal completed reading every single SiPM & analysis ongoing
- ③ **Preparations for 2025 TB-campaigns & TB analysis**
  - ▶ Test beam analysis from 2023 & 2024 on-going, aiming at paper combined paper for late summer
  - ▶ Preparations for large scale 8 x 8M module test beam CERN at SPS & PS in Oct/Nov ongoing



# Thanks!



## 1 Reconstruction optimization

- Realistic implementation of geometry in ePIC software stack
- ML assisted absorber optimization in full geometry setup

## 2 Prototype tile production using machining & injection molding

- Ongoing machining studies for tile production
- First tile production with injection molding at Fermilab with different tile chemistries

## 3 Tile Characterization


- Light yield studies of machined & injection molded tiles with different dimple sizes, machining techniques and wrappings ongoing
- Position scan of response on-going

## 4 Sensor board development

- Third iteration of sensor board produced in three different processes
- Tests of calibration circuits ongoing


## 5 Preparations for third TB-campaign (Aug 2024) & TB analysis




- Test beam analysis from Sept. & Oct. 2023 on-going
- Currently setting up in PS beam line, TB starting today





- First larger scale injection molding production by Fermilab with 3 different chemistries
- Additional scintillator machining studies on the way
- Produced tiles with different dimple sizes
- Additional production to come in the coming months to equip August test beam modules





- Started measuring cosmics MIP light yields for different SiPMs types
  - $1.3 \times 1.3$  mm
    - $\rightarrow \approx 12 - 14$  p.e. for machined tiles
    - $\rightarrow \approx 11 - 13$  p.e. for injection molded tiles,
  - $3 \times 3$  mm
    - $\rightarrow \approx 60 - 76$  p.e for machined tiles

- Testing different scintillator materials (EJ-200, BC-408 & Fermilab injection molded with different chemistries)
- Systematic evaluation of impact of machining defects ongoing and large scale sample on-going
- Single photon spectra for every SiPM of the TB assemblies vs  $V_{ov}$

# LFHCal: Test beams 2023

## Dates:

- **SPS:** 6<sup>th</sup> – 13<sup>th</sup> Sept.
- **PS:** 11<sup>th</sup> – 18<sup>th</sup> Oct.

## Setup:

- Parasitic to FoCal-H/FoCal-E at SPS and PS
- Setup consists out of maximum 14 layers of 8M tile assemblies



**Sept:** w/o absorber layers

**Oct:** w/ absorber layers (4 tungsten, 10 steel)




- Read-out: CAEN DT5202 64ch CITIROC SiPM readout unit or H2GCROC

## Main expected measurements:

- Light yields per tile
- Shower profile measurements with different absorbers
- Cross talk estimates of different tiles
- Use it as testing setup for SiPM-H2GCROC
- If placed behind FoCal-H, measure part of leakage



## October campaign



## September campaign - Hodoscope setup


- Full  $V_{ov}$  scan  $e^-/h$
- Gain-scan
- Position scan
- Possibly leakage measurement of FoCal-H

## October campaign - mini-LFHCal



- Full  $V_{ov}$  & gain scan  $e^-/\pi^-$
- Position scan
- Scan with additional W-plates upfront ( $e^-$ )
- $e^-$  shower development (1-5 GeV)
- $\pi^-$  shower development (5,10,15 GeV)

## Additional W-plate scan

Channel6  $e^-$ , 4 GeV, 4 VoV








## MIP response for scintillators



## $e^-$ Energy scan

Channel3  $e^-$ , 3W Layers, 4 VoV





- H2GCROC read-out ready just in time for last 1.5 days of data taking (Oct.)
- Self-triggered data obtained
- Unfortunately externally triggered setup couldn't be operated due to beam stop of PS during last night
- New prototype board on time for delivery for testing significantly ahead of TB