




## nHCal "mini Project Review"

Physics requirements: Daniel Brandenburg

**Technical realization: Caroline Riedl**


Planning: Leszek Kosarzewski

Caroline Riedl (UIUC)

March 25, 2025

- Timeline I
- Project design
  - Purposes and requirements
  - Parameters
  - Materials and vendors
- Performance evaluation
- Timeline II








- The nHCal is surrounded by an outer collar, backed by a flux return plate and has an oculus ring placed in front.
- The flux return is decoupled from the nHCal ☞ need to use non-magnetic steel as absorber.

backward endcap

forward endcap





| calendar year          | Q1 2025              | Q2 2025 | Q3 2025 | Q4 2025 | Q1 2026 | Q2 2026 | Q3 2026                                            | Q4 2026 | Q1 2027 | Q2 2027 | Q3 2027 | Q4 2027 | Q1 2028 | Q2 2028 | Q3 2028 | Q4 2028 | Q1 2029 | Q2 2029 | Q3 2029 | Q4 2029 | Q1 2030    | Q2 2030 | Q3 2030 | Q4 2030 |
|------------------------|----------------------|---------|---------|---------|---------|---------|----------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|------------|---------|---------|---------|
| simulations            |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         | 2025-03-19 |         |         |         |
| finalize design        |                      |         | 70%     |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| tile testing           |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| full chain test        |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| prototype construction |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| beam test              |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| test beam availability | no test beam at FNAL |         |         |         |         |         | long shutdown at CERN / no test beam in North Area |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| procurement            |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| construction           |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| shipping to BNL        |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| assembly at BNL        |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |
| milestones             |                      |         |         |         |         |         |                                                    |         |         |         |         |         |         |         |         |         |         |         |         |         |            |         |         |         |



"want to do this physics"  $\Rightarrow$  "need this performance"

- **Tail catcher calorimeter**

- **Low  $x$  ( $10^{-3} - 10^{-2}$ ) and  $Q^2$ , high  $y$**

- Diffractive-VM decay product reconstruction

- Diffractive dijet reconstruction

- Veto for jets with neutral energy component

- Help with help in scattered-electron ID (together with backward EMCal)

- Hadron-beam background veto for dRICH (together with LFHCAL)

put screenshot from Daniel's talk here instead




- Good  $\mu/\pi$  separation of tracks with MIP signal





- Good spatial resolution to distinguish neutral/charged hadrons



- High efficiency for low-energy neutron detection ( $>90\%$  detection efficiency for 2 GeV neutrons; track-cluster matching)




- Good timing resolution





**nHCal** similar but not identical to **LFHCal** design. Both are sampling calorimeters with alternating layers



|                                  | nHCal                                               | LFHCal                                                |
|----------------------------------|-----------------------------------------------------|-------------------------------------------------------|
| <b>material</b>                  | same                                                | Fe / SciTiles                                         |
| <b>interaction length</b>        | 2.4                                                 | 6.0                                                   |
| <b>depth along beam axis</b>     | 45cm                                                | 132cm                                                 |
| <b>number of physical layers</b> | 10                                                  | 60                                                    |
| <b>thickness of layers</b>       | 40mm / 4mm                                          | 16mm / 4mm                                            |
| <b>tile size</b>                 | 10cm x 10cm                                         | 5cm x 5cm                                             |
| <b>module size</b>               | 10cm x 20cm x 45cm (8M),<br>10cm x 10cm x 45cm (4M) | 10cm x 20cm x 140cm (8M),<br>10cm x 10cm x 140cm (4M) |
| <b>number of modules</b>         | same                                                | 1050 (8M), 76 (4M)                                    |
| <b>tiles per layer</b>           |                                                     |                                                       |
| <b>number of ROC</b>             |                                                     |                                                       |

|                           | Possible candidate(s)                                    | decided | ordered or<br>acquired for<br>prototype | ordered or<br>acquired for<br>project<br>detector | remarks                                                                                                                                                                                                                                   |
|---------------------------|----------------------------------------------------------|---------|-----------------------------------------|---------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Tiles</b>              | Eljen EJ-200, or injection molding (FNAL)                | no      | yes                                     | no                                                | Considered choices: 5cm x 5cm, 10cm x 10cm<br><a href="https://eljentechnology.com/products/plastic-scintillators/ej-200-ej-204-ej-208-ej-212">https://eljentechnology.com/products/plastic-scintillators/ej-200-ej-204-ej-208-ej-212</a> |
| <b>SiPMs</b>              | S14160-1315PS                                            | yes     | no                                      | no                                                | <a href="https://www.hamamatsu.com/eu/en/product/optical-sensors/mppc/mppc_mppc-array/S14160-1315PS.html">https://www.hamamatsu.com/eu/en/product/optical-sensors/mppc/mppc_mppc-array/S14160-1315PS.html</a>                             |
| <b>Light collection</b>   | SiPM-on-tile or WLS with SiPM                            | no      | no                                      | no                                                | LFHCal uses SiPM-on-tile design                                                                                                                                                                                                           |
| <b>Front-End Readout</b>  | HGCROCv3                                                 | yes     | no                                      | no                                                | 78 channels. Same as for LFHCal. nHCal: placed in front of modules (LFHCal: back)                                                                                                                                                         |
| <b>Absorber structure</b> | Leading Edge Metals & Alloys; Electron Beam Welding, LLC | no      | no                                      | no                                                | Absorber: non-magnetic steel; electron beam welding in vacuum                                                                                                                                                                             |




- Standalone tile testing using cosmic rays and radioactive source.
  - Purpose of the tests: evaluate performance of different tile configurations and sizes
  - Tiles of different sizes (5x5, 10x10) and thickness (4, 8, 16mm) were ordered by Project.
- Looking into what the best approaches are, cost- and physics-wise, which includes exploring different techniques
- Exploring the necessity to build a prototype and test beam opportunities
- Instead, set up full-chain test?
- A detailed plan will be made including required resources (FTE and \$) and a time sequence.

- Goal of beam tests: verify simulations
  - ▶ Measure position resolution, e/h ratio, sampling fraction.
- For a nHCal-dedicated test beam, we need to build a prototype and find hadron test-beam time (currently difficult)
- Can we inform the final design decision from only stand-alone tile testing, full-chain tests, and LFHCal test beams?
  - ▶ LFHCal and nHCal parameters not identical
  - ▶ (Continue to) support LFHCal team in their future test beam campaigns



# nHCal timeline - returning to the bigger picture




extra slides

extra slides

extra slides




Plans for CD-2 and CD-3 originally aligned with conclusion of RHIC.



Critical Path is Accelerator Systems

Science operations start in roughly a decade

# EIC Project-Critical Decisions and Plans




- **CD-3A, Long-Lead Procurement, approved March 2024. Excellent use of IRA funding.**
- **CD-3B, Long-Lead Procurement, approval planned for March 2025 (ESAAB)**



# LFHCAL: The General Idea




## Concept:

- CALICE AHCAL inspired W/Fe-Scintillator calorimeter with SiPM on-tile-readout
- Three construction units:
  - ▶ 8M modules  $10 \times 20 \times 140 \text{ cm}^3$
  - ▶ 4M modules out of  $10 \times 10 \times 140 \text{ cm}^3$
  - ▶ Insert modules built out of 2 halves surrounding the beam pipe
- **8M & 4M modules :**
  - ▶ 4 layers of tungsten + 61 layers of steel interleaved with scintillator material
  - ▶ Transverse tower size  $5 \times 5 \text{ cm}^2$
  - ▶ Multiple consecutive tiles summed to 7 longitudinal segments per tower
- **Insert modules:**
  - ▶ 10 layers of tungsten + 54 layers of steel interleaved with scintillator
  - ▶ Hexagonal tiles of  $8 \text{ cm}^2$  each read-out individually






- The nHCal will also 8M and 4M modules
- No “insert modules” since radiation damage is less of a worry in the backward electron-going direction





# Endcap Interfaces


## Forward Endcap (FE) 11'x6'x25', 200ton



## Description

- HCal, EMCAL and Lepton are end cap detectors
- Seismic restraints attach the end caps to the central barrel
- Anchor bolts tie down the end caps when the central barrel isn't available
- Hydraulic rams push the end caps on Hilman rollers
- Hydraulic jacks lift the detector for alignment
- Flux return minimize the fringe field and balance the magnetic forces

## Backward Endcap (BE) 11'x4'x25', 125ton



Electron-Ion Collider


Collaboration Meeting, January 20-24, 2025

R. Sharma

26



# Integration Model in Experimental Hall



Electron-Ion Collider



Collaboration Meeting, January 20-24, 2025

R. Sharma

9

<https://agenda.infn.it/event/43344/contributions/252099>





|                    |                        |      |
|--------------------|------------------------|------|
| MAGNET & BEAM PIPE | FLUX RETURN & CARRIAGE | HCAL |
| EMCAL              | RICH                   | DIRC |
| MPGD               | AC LGAD                | SVT  |


COLOR CODE

- Communication with Project in October 2024:
  - ▶ Module size is 45 cm x 20 cm x 10 cm; for details see posted drawing package.
  - ▶ Maximum length of the module can be 70 cm in z but then maintenance close to the oculus will be difficult
  - ▶ Electronics sits towards the IP
  - ▶ The segmentation inside the module is free to vary as long as it fits in the 45 cm x 20 cm x 10 cm
- See also <https://indico.bnl.gov/event/25021/>



- For better energy resolution - make nHCal deeper (up to  $\sim 70$  cm)?
- Add charge veto to help isolate neutral showers
- Add in addition SMD with high position resolution?

## Additional charged veto and SMD layer



- 1 Investigate if adding extra scintillator layer as a charged veto helps isolate neutral showers
- 2 This extra layer needs to be thicker eg. 2 cm to leave enough signal
- 3 Can have better granularity than standard tiles
- 1 Revisit option of adding an SMD layer with high position resolution
- 2 Initially no plans to reuse STAR EEMC SMDs, because of too low light yield
  - [https://wiki.bnl.gov/athena/images/6/60/ATHENA\\_bnHCal\\_Notes\\_v1.pdf](https://wiki.bnl.gov/athena/images/6/60/ATHENA_bnHCal_Notes_v1.pdf)
- 3 Similar idea to KLM
- 4 Another option to use smaller tiles


- 1 Can we extend from 45 cm in z to eg. 70 cm?
  - Limited by oculus and room for electronics
  - Increases cost - estimate?
  - Improves energy resolution - quantify?
  - Other benefits?

- Difficulty to get hadron beam test time
  - ▶ No test beam at FNAL in 2025, and 2026 unclear (transformer problems for the main injector)
  - ▶ CERN LHC long shutdown mid-2026++
- Considered possibilities:
  - ▶ **FNAL 2026** - jointly with EMCal barrel? Initial planning with Argonne group in 2024 about collaboration in 2025
  - ▶ **CERN spring 2026** - jointly with ATLAS/CMS ZDC? (co-led by UIUC)
    - Not in parallel (ZDC is an HCal too and has 5.5 interaction lengths → parasitically behind the setup is not an option), but potentially serially in time. Synergies in sharing person power, DAQ, trigger scintillators, readout cables, tables... UIUC/ZDC plans to request beam time for spring 2026 (call not open yet). If jointly with nHCal, request one additional consecutive week.
  - ▶ **CERN fall 2025** - jointly with IfHCal?
    - IfHCal TB time for PS scheduled Nov 19-26. Again, issue with parallel HCal beam time - won't be possible at the same time
  - ▶ **Parasitic at RHIC fall 2025?**
    - There is a temporary shutdown in summer (no beam from July 1 - August 18, 2025 to avoid heat/humidity-related inefficiencies) and this downtime could be used to prepare the setup. Would require communication with sPHENIX asap.

See also <https://cernbox.cern.ch/external/public/wRuLiYuAwqgS5xx/InternationalTBplan-worldwide.xlsx>




# Test beam for ePIC barrel EMCal in June 2024 at FNAL




protons 120 GeV



electrons / pions  
2-32 GeV  
fractions vary  
depending on E  
(~15% pions at lowest)



~3-4 feet



~1.5m

~1m

MWPC

silicons


EMCal  
(BabyBCAL setup)

nHCal  
prototype  
here?

MWPC




# Proposal for an ePIC nHCal beam test at FNAL




(August 2024 - Caroline Riedl in communication with Sylvester Joosten, Maria Zurek, Manoj Jadhav, Henry Klest)

- Space:  $\sim 120\text{cm}$  in  $z$ ;  $\sim 30\text{cm}$  in  $y$ ;  $\sim 30\text{cm}$  in  $x$ , which likely implies that we will sit downstream of the 2nd MWPC. This is the preferred scenario. (see supporting drawing on the next page)
  - ▶ The nHCal is only 3-4 hadronic interaction lengths deep, which means the hadronic showers will not be fully contained. We would therefore would like to place a tail catcher downstream of the primary prototype to measure the energy leakage.
  - ▶ In this scenario, the distance between EMCal and HCal prototypes corresponds to the actual distance between the two calorimeters in the backward endcap.
- If " $120\text{cm}$  in  $z$ " is not possible, we can also accommodate only  $\sim 60\text{cm}$  in  $z$  and sit directly downstream of the EMCal.
- There will be RO cables and possibly other connections extending further in  $x$  and/or  $y$ .
- Tested detector: 2 ePIC nHCal prototypes (primary with 9 towers, tail catcher with 1 tower) - scintillator-absorber sandwich
- Depending on the existing setup at FNAL, we will need to bring a platform that allows moving our setup in  $x$  and  $y$  to allow the beam to enter at different locations
- SiPM cooling?







- Front geometry limit:  $-4.03 < \eta < -1.18$
- Back geometry limit:  $-4.14 < \eta < -1.27$
- Clusters:  $-3.95 < \eta < -1.25$
- MC particles showering in nHCal(with hits):  $-4.16 < \eta < -1.16$



- After successful beam test? Full chain test sufficient?
- When will the material be ordered? (prerequisites?) Need FDR → CD2/3
- When will the production site be prepared?
- Preparation of FDR: draft of Money + FTEs have to be 90% final, lists in P6