



LFHCAL Testbeams 2025

- One week of CERN SPS: Oct 29th-Nov 5th
- One week of CERN PS: Nov 19th-26th
- 40cm x 40cm x 132cm prototype
 - 8x "8M" module stacked into square configuration
 - Approaching hadron shower containment...
- HGCROC readout with longitudinal summing
 - Very close to ePIC baseline







LFHCAL Testbeams 2025




Mechanics

- 5 absorber modules at ORNL
- 3 sent to Nickel plating
 - 1 plated
 - 1 damaged in transit (and fixed)
- Braces for mechanics/grounding available at ORNL









Scintillators + Flex PCBs

- FNAL will produce ~4000 new scintillator tiles
 - Will required new mold (for 4x production speed) ~4wks
 - ~1wk production time
 - Waiting on PED money
- Need to order more ESR foil (have foil for 2000 tiles available)
- Sensors will arrive at BNL in June (according to Hamamatsu)
- New flex PCB layout is ready for production but not yet submitted
- Assembly of flex PCBs tbd:
 - Previously assembled in Hungary
 - tariffs? Assembly in US?



Electronics: Long Board + Summing Board

- First Long board design prepared for production
 - Not yet submitted, still discussing crosstalk measurements with previous boards
 - Specs close to ePIC: simplification of board end connectors
- Summing board
 - Sums 5/10 longitudinal segment sensors into single readout channel
 - Passive summing test board available (with switchable configuration)
 - SiPM test boards produced and available at ORNL under test
 - Pre-produce 3 boards in June, retest
 - Full production of 10 summing boards in August





Electronics: HGCROC + triggers

- HGCROC boards exist, FPGA boards exist
- Same overall scale as 2024 beam time due to summing
- Active work on firmware, software, calibration routines
 - lots of experience from EEEMC + BIC beam times with HGCROC
- ORNL building our own set of plastic scintillator trigger fingers with SiPM readout
 - Thanks to



LFHCAL Testbeams 2025

