





# Recent beamtest activity

## Insert/ZDC

Miguel Arratia, UC Riverside  
Calo Meeting, 05/07/2025



# 2024

- Test in STAR Hall @ RHIC ,  
200 GeV pp collisions




Status: **Analysis completed.**

[\[2501.08586\]](#) First-Ever Deployment of a  
SiPM-on-Tile Calorimeter in a Collider: A Parasitic  
Test with 200 GeV  $pp$  Collisions at RHIC

- Test SiPM irradiation @ UC  
Davis Cyclotron.

Status: **Analysis completed**


[\[2503.14622\]](#) Measurement of SiPM Dark Currents  
and Annealing Recovery for Fluences Expected in  
ePIC Calorimeters at the Electron-Ion Collider




# 1) 2025 RHIC STAR

- RHIC test part II, 200 GeV AuAu run.  
Status: Ready to go, waiting for beam.

## 200 GeV pp collisions



## 200 GeV AA collisions



## 2) 2025 JLab test


- Generation-3 prototype testing.
- At JLab Hall-D positron 4 GeV  
Status: Beam test completed as per last week. Analysis ongoing.



### 3) 2025 parasitic test BNL/NASA

-

- At BNL NASA 1-6 GeV  
deposited energy with protons,  
and light-ion beams  
Status: Installation ongoing.




# 3rd generation prototype for test at JLab




- Design for ZDC SiPM boards complete.
- All assembly process (including laser cutting, SiPM soldering with reflow oven, tile affixing), final, with cost-effective solutions.
- 375 channels, 15 layers,  $\sim 16 \times 0$  for 4 GeV positron test.

# Test of generation-3 prototype at



First installation Feb 6  
Data taking April 23-30



375 channels, >98% live & calibrated

# Gen-3 prototype critical step to full scale





Design for ZDC is modular.  
Prototype at JLab is ~6% of full ZDC size, ~10% at BNL/NASA.

SiPMs boards designed by UCR are final.  
Connectors, custom cables, etc.

Established “final” protocols for SiPM-on-tile units assembly, including laser-cut ESR, wrapping, QA etc.


Established “final” protocols for SiPM board soldering, affixing tiles, testing, transport.

## Scaling to the full ZDC




ZDC Prototype  
ZDC Prototype  
Event #174

0 ns





Real  
data!



# Calibration


Channel-by-channel calibration with MIPs insitu, and  
channel-by-channel high-gain/low-gain cross-calibration




Analysis going well (this is our 3rd time performing test of prototypes)

Expect to quantify:

- EM energy response
- Test staggered-layer design to improve angle reconstruction.
- 4D shower shape






# Transport from JLab to BNL




Successful transport experience  
May 2-3 2025

## Assembling prototype at BNL/NASA facility



- Detector size was increased to 575 channels (~10% ZDC and ~10% Insert)--> **Proof we are shovel ready.**
- Parasitic, beam dump experiment with 2.5 GeV proton beams scheduled for 5/21
- Further parasitic tests in heavy-ion beams, to sample up to 6 GeV deposited energy



# DAQ system used in BNL/NASA



# Cosmic rays

DAQ tested with  
external trigger  
scintillator.


Works as expected



# Summary

2023

Jefferson Lab



2024

CROCKER NUCLEAR LABORATORY  
CYCLOTRON SERVICES




2024-2025

Brookhaven  
National Laboratory




2025

Jefferson Lab



2025

Brookhaven  
National Laboratory



# Conclusions

2025 is going to be busy with 3 beam tests (parasitic RHIC in STAR Hall, parasitic Hall-D JLab & parasitic BNL/NASA proton and light-ion)

Main point of tests is to validate “final” modular design with significant % of full-scale ZDC/Insert to show (e.g. NSF) that we are “shovel ready”. In addition, an important goal is development and consolidation of assembly and QA protocols and transport.

We welcome anyone interested in collaborate, as we’ve just done with JLab test (L. Preet U Regina).