EIC-LAS: Discussion on workforce

SVT working meeting, 9-11 Jully 2025



João de Melo - BNL jmelo@bnl.gov




MOSAIX


MOSAIX (ER2) - Sensor Dimensions

- ■MOSAIX is a full feature prototype of the sensor for ALICE ITS3
- ☐ Wafer scale sensor design using the stitching technique
- □ Process: TPSCo 65 nm CMOS Imaging Sensors(customized)
- MOSAIX design leading to production sensor (ER3)

Alice/ITS3



MOSAIX (ER2) - Top Integration Diagram





MOSAIX to EIC-LAS

EIC-LAS: Reducing from 12 to 5-6 RSUs

□EIC-LAS (SVT OB & Discs):

- Powering applied only from the LEC.
- Expected similar IR drop @RSU-5 ?






MOSAIX to EIC-LAS: LEC Modifications


□ Reduce LEC to one channel

- Bypass Serializer LDOs
 - > Study on the performance before and after removing LDOs.
 - ➤ Dedicated decap cells, star routing (supply), and functional adjustments (no LDO controls).
- ➤ Data Encoding and Router (serialization of the data to a single channel)
 - ➤ Challenge to adapt/change
 - > Slow control needs to be modified



Preliminary Resources

MOSAIX Tape-out (expected)



Preliminary Resources and Tasks

- ➤ EIC-LAS Sensor Development (~7 months)
 - □1 Technical Lead that also supports R&D / Design
 - □1 Digital engineer for Top / Integration
 - □Reduce the number of RSUs
 - 1 Digital engineer (half period) to reduce RSUs and to validate the signal/data integrity (of each RSU).
 - □ Reduce LEC to one channel
 - 2 Digital engineers plus 0.5 mixed signal engineer. SC control needs to be modified as well as the serialization of the data to a single channel.
 - Bypass Serializer LDOs
 - 1 Analog engineer plus 0.5 mixed signal engineer. Study on the performance before and after removing LDOs. Dedicated decap cells, star routing (supply), and functional adjustments (no LDO controls).
 - ☐ Final checks and tape-out
 - All team. Functionality, filling, final DRC checks, and submission.

Summary of Key Points

- ➤ ER2 submission imminent (aiming for the 2nd week of Jully)
 - □ER3 (production) submission scheduled ~1 year after ER2 submission
- ➤ EIC-LAS Sensor Development (~7 months)
 - □ Reduce LEC to one channel
 - □Bypass Serializer LDOs
 - ☐ Final integrity checks and tape-out
- ➤ Importance of Agreement for Access to the MOSAIX Database
 - □Full access to all technical details is still pending
 - □Work on EIC-LAS cannot begin until database access is available
 - □Accurate estimates of the effort and timeline for EIC-LAS modifications depend on complete technical information

MOSAIX to EIC-LAS Timing Improvement!?

MOSAIX to EIC-LAS: Timing Improvement


□Pixel Array Readout

- Serial transmission of tile packet to LEC
 - > Tile periphery builds and transmits one data packet for each framing interval (2-10 μs)
 - ➤ Global SYNC signal aligns in time the integration intervals across all the tiles

@ 40MHz (25ns) for a 2µs interval, capable of 80 hits per Tile

For **EIC-LAS**, less hits per Tile?





Alice/ITS3