
The ePIC Barrel Imaging Calorimeter

### **Mechanics and Sectors**



Sylvester Joosten
Argonne National Laboratory

BIC General Meeting July 25, 2025





### **Sectors Update**



#### Lead/Swaging

- We tuned the swager to work reliably with GlueX surplus lead and are using it for first test articles
- Some irregularities (minor thickness variation pattern) in swaged lead seems not problematic and likely already present for GlueX
- Ordered lead from vendor; but arrived 20% too thick, with crushed edges and thickness irregularities. We've returned shipment and are negotiating possible specs
  - Vendor used German supplier in the past for GlueX but not anymore due to costs/tarrifs
  - Most lead manufacturers not capable of making 0.5mm sheets examining options
  - Enough GlueX lead to keep building test articles for now.

#### SFIL Test Articles

- o Constructed first 0.5m SFIL test article (SFIL1), came out fairly well but learned some lessons
  - Machining at Argonne using Bridgeport mill
  - Still investigating options for machining longer test articles (onsite vs offsite)
- Constructed SFIL2 test article, addressed most issues in SFIL1.
  - Investigating minor angle between top and bottom plate
  - Validating CAD drawings of lay-ups versus actual lay-up profiles
- Next steps: focused on destructive test articles and final debugging of setup; then we will build SFIL3 with GlueX fibers due early August.

#### Looking forward

Preparing production space for long test article construction in fall



## **Tracker Mechanics and Integration**





#### Test Articles

- Received 20x 2m test articles (extruded aluminum); tolerances and mechanical fit working well
- Initial measurements looking good; finalizing micrometer/flatness/squareness measurements
- Still need to design scalable way to fix modules in place

#### Next Steps

 Super-stave design and integration in CF frame in development, expect first drawings by PDR





## **CF Work and Destructive Testing and FEA**



### Destructive Testing (Mode 1 & 2)

- We're fabricating flat delamination test articles this week
- Purdue will cut and prep the samples for mode 1 (peel) and mode 2 (shear) testing.
- Interfaces under test: lead—CF and lead—SciFi—lead.
- We've received CFRP sheets from Purdue and selected Kapton/flash tape as separation layers
- Testing is scheduled for early August in Purdue
- These results are a required input for our FEA of sectors and full system due for PDR

#### Composite Frame Test Articles

- We're prototyping two 0.5 m CFRP drawer designs:
  - A single-piece frame, and
  - A four-piece segmented frame.
- Purdue is fabricating both designs using aerospace-grade prepreg CF
- We're developing integration methods of CF frame with the Pb/SciFi matrix
- We're developing external fixtures for alignment and assessing press force impact (current system operates <15 psi).</li>
- We aim to deliver at least one physical 0.5 m frame for the PDR. Full-length (3 m) test articles will follow in the fall.

### Integration

- Destructive test results will feed directly into frame selection, layup strategy, and FEA validation.
- Integration design with the AstroPix tray ongoing

# **Destructive Testing Drawings**



