Backward Ecal / EEEMCal

Triple I Engineering Meeting Update (28/07/2025)

Julien Bettane









Prototype External structure – FSW



- ☐ Prototype to check the efficiency of the cooling
- ☐ Test the Friction Stir Welding (FSW) technology
- ☐ Good watertightness and good for the pressure
- Machining finished
- ☐ Metrology checking required because of the deformation
- ☐ Receiving this week










Prototype External structure – Welding (back up)



- ☐ Aluminum welding tests in progress
- ☐ Machining tests of the shape in our mechanical workshop in order to practice
- Ready to machine the steps of the FSW prototype received



Machining of the steps
Metrology testing of the shape < 0,025 mm




Additional welding test to improve the quality (tightness test OK)




Prototype Internal structure – Copper tubes



- ☐ Prototype with copper tubes
- **☐** Machining and assembly in progress
- □ Design stays the same even if the flange is reduced → Not possible to add crystals
- ☐ Clearance = 11 mm









Fabrication of the External structure






- ☐ External structure in one block at the beginning
- ☐ External structure in two parts at the end (after machining)
 - Better for the Eddy current
 - Better for the contact with crystals on the top (cooling)
- ☐ Good for the deflection & the stress
- ☐ Good for the tolerances and the positioning of the crystals
- ☐ Current discussion with Company





Design & Cooling for the FEB









Design & Cooling for the FEB









≈ 500 (Adapter + FEB)



Based on the optimum for the Asics \rightarrow 1 lpGBT for 3 EICROC (OMEGA, IN2P3)







Solution Clearance OK – On structure

Clearance KO – Adjustment required



