

# ESRF Operations and Machine Upgrade

BNL, April 26-28 2017

**Pantaleo Raimondi**

*On behalf of the Accelerator Project Phase II Team*



The European Synchrotron




The Accelerator Upgrade Phase II aims to:

- Substantially decrease the Store Ring Equilibrium Horizontal Emittance
- Increase the source brilliance
- Increase its coherent fraction

*In the context of the R&D on “Ultimate Storage Ring”, the ESRF has developed a solution, based on the following requirements and constraints:*

- Reduce the horizontal equilibrium emittance from 4 nm to less than 140 pm
- Maintain the existing ID straights beamlines
- Maintain the existing bending magnet beamlines
- Preserve the time structure operation and a multibunch current of 200 mA
- Keep the present injector complex
- Reuse, as much as possible, existing hardware
- Minimize the energy lost in synchrotron radiation
- Minimize operation costs, particularly wall-plug power
- Limit the downtime for installation and commissioning to less than 18 months.

**Maintain standard User-Mode Operations until  
the day of shut-down for installation**




## Machine Statistics for 2014-2017 at the ESRF

During 2016, ESRF has delivered 5485 hours of beamtime to its users, out of the 5537 planned

	2014	2015	2016	2017
Availability (%)	99.11	98.53	99.06	<b>97.93</b>
Mean Time Between Failures (hrs)	105.5	93.6	93.8	<b>60.50</b>
Mean duration of a failure (hrs)	0.94	1.37	0.88	<b>0.87</b>


(Until March 2017)

# LOW EMITTANCE RINGS TREND



# BRILLIANCE AND COHERENCE INCREASE


## Brilliance



Hor. Emittance [nm]	4	0.135
Vert. Emittance [pm]	4	5
Energy spread [%]	0.1	0.09
$\beta_x[\text{m}]/\beta_z[\text{m}]$	37/3	6.9/2.6


Source performances will improve by a factor 50 to 100

## 18mm Undulator spectrum




Undulator  
:  
CPMU18,  
K=1.68  
L=2m


## Coherence



# ESRF Phase II Upgrade at the Bone



Present ESRF Arc Layout:  $E_x=4\text{nm}$



New Low Emittance Layout:  $E_x=0.135\text{nm}$

The 844m Accelerator ring consists of:

- 32 identical Arcs 21.2m long
- 32 straight sections 5.2m long equipped with undulators and RF


Each Arc is composed by a well defined sequence of Magnets (dipoles, quadrupoles etc), Vacuum Components (vacuum vessel, vacuum pumps etc), Diagnostic (Beam Position Monitors etc) etc.

All the Arcs will be replaced by a completely new Layout

# THE EVOLUTION TO MULTI-BEND LATTICE

## Double-Bend Achromat (DBA)



- Many 3<sup>rd</sup> gen. SR sources
- Local dispersion bump (originally closed) for chromaticity correction



# THE EVOLUTION TO MULTI-BEND LATTICE

## Double-Bend Achromat (DBA)

- Many 3<sup>rd</sup> gen. SR sources
- Local dispersion bump (originally closed) for chromaticity correction



## Multi-Bend Achromat (MBA)



- MAX IV and other USRs
- No dispersion bump, its value is a trade-off between emittance and sextupoles (DA)

# THE HYBRID MULTI-BEND (HMB) LATTICE

## ESRF existing (DBA) cell

- $E_x = 4 \text{ nm}\cdot\text{rad}$
- tunes (36.44, 13.39)
- nat. chromaticity (-130, -58)

**- Multi-bend for lower emittance**  
**- Dispersion bump for efficient chromaticity correction => "weak" sextupoles (<0.6kT/m)**  
**- Fewer sextupoles than in DBA**  
**- Longer and weaker dipoles => less SR**  
**- No need of "large" dispersion on the inner dipoles => small  $H_x$  and  $E_x$**





## Proposed HMB cell

- $E_x = 140 \text{ pm}\cdot\text{rad}$
- tunes (76.21, 27.34)
- nat. chromaticity (-99, -82)

# LIFETIME OF S28B

s28b bpm0208nominal LOW EMIT RING INJ @S3. 512 turns WP 021 034 s28b bpm0208nominal 10  
 DA on en :-12.4 mm En. Acc. :-6.0 % T.L.:45.1h I.E.:NaN% I.E. RF:NaN% I.E. rb:100.0%  
 error average 10 seeds DA on en:-10.2+/-0.5 mm En. Acc. :-6.0+/-0.0 % T.L.:23.0+/-1.3 h  
 I.E.:NaN+/-NaN % I.E. RF:NaN+/-NaN % I.E. rb:97.9+/-1.1 %



**S28A**  
**DA -8.1mm@S3**  
**TLT ~ 13h.**

**S28B**  
**DA -10mm@S3**  
**TLT ~ 21h**


$e_y=5\mu\text{m}$	ESRF	Upgrade
Multibunch	64 h	21 h
16 bunch	6 h	2.1 h
4 bunch	4 h	1.4 h

# Technical challenge: Magnets System

## Mechanical design final drawing phase


- Large positioning pins for opening repeatability
- Tight tolerances on pole profiles
- Prototypes delivered in the period September 2014-Spring 2015

Quadrupole  
Around  $52 \text{ Tm}^{-1}$




Octupoles

Sextupoles  
Length 200mm  
Gradient:  $3500 \text{ Tm}^{-2}$




Gael Le Bec




## High gradient quadrupoles

- Gradient:  $90 \text{ T/m}$
- **Bore radius:  $12.5 \text{ mm}$**
- Length:  $390/490 \text{ mm}$
- Power:  $1-2 \text{ kW}$




Permanent magnet ( $\text{Sm}_2\text{Co}_{17}$ ) dipoles  
longitudinal gradient  $0.16 - 0.65 \text{ T}$ , magnetic gap  $25 \text{ mm}$   
 $1.8 \text{ meters long, 5 modules}$




Combined Dipole-Quadrupoles  
 $0.54 \text{ T} / 34 \text{ Tm}^{-1}$  &  $0.43 \text{ T} / 34 \text{ Tm}^{-1}$

## Pole shape optimization

*Imposed 11mm stay clear from pole to pole for all magnets for optimal synchrotron radiation handling*




Low gradient pole profile



High gradient pole profile


11mm stay clear



Vacuum chamber and magnets sections


## High Gradient

- 91 T/m gradient, 388 – 484 mm length
- 12.7 mm bore radius, 11 mm vertical gap
- 1.4 – 1.6 kW power consumption



## Moderate Gradient



- Up to 58 T/m gradient, 162– 295 mm length
- 16.4 mm bore radius, 11 mm vertical gap
- 0.7 – 1.0 kW power consumption




# DIPOLE WITH LONGITUDINAL GRADIENT

## Specifications

- 0.17 – 0.67 T field
- 5 modules of 357 mm each
- Larger gap for the low field module
- Allows the installation of an absorber






Measured field integral homogeneity  
(one module)



Longitudinal field distribution

# DIPOLE QUADRUPOLES



DQ1 pole shape

DQ1 gradient homogeneity:

**Integration of trajectory along an arc**

DQ1: 1.028 m, 0.57 T, 37.1 T/m


$\Delta G/G < 1\%$  (GFR radius 7 mm)

DQs are machined in 7 solid iron plates

**Poles curved longitudinally for maximum stay clear and good field region**


## Specifications

- 48 kT/m<sup>3</sup> nominal strength (70 kT/m<sup>3</sup> maximum)
- 90 mm length
- 4 Water cooled coils at the return-field yoke
- Allows for the required stay-clear for Synchrotron Radiation fans



# EBS MASTER PLAN (2015-2020)

## Master Plan and Major Milestones



# PROGRESS STATUS: DESIGN

- **Design of all the components nearly completed:**
  - **Magnets** ~95% (Kickers and PM-septa in progress)
  - **Vacuum System** ~95% (One-of-a-kind chambers in injection section in progress)
  - **Absorbers** ~100%
  - **Girders** ~100%
  - **Supports** ~100%
  - **Diagnostics** ~80% (Collimators, Special chambers in progress)
  - **Power Supplies** ~90% (Sizing optimization and hot-swap implementation in progress)
- **All elements have been fully integrated and are consistent with the overall specifications and requirements**

- All contracts for serial production magnets in place
- All contracts for vacuum chambers in place
- Girder contracts in place
- Infrastructure adaptations critical contracts in place
- All large scale procurement in place by December-2016


**Delivery of serial components has started will last about 2 years**

# ESRF EBS (2015-2022): MAGNETS PROCUREMENT

All contracts in place, magnets in fabrication  
FAT for HG-Quads, Sextupoles and correctors last week  
All FAT should be completed by December  
More than 1000 Magnets to be procured by the end of 2018



66 octupoles



398 moderate gradient quadrupoles



130 high gradient quadrupoles




196 sextupoles




100 correctors

# IMPLEMENTATION IN CHARTREUSE HALL




PM Dipoles are being assembled by ESRF staff  
More than 650 Magnets Modules for a total of about 130 5-Module dipoles

PM assembly tool



Dipole assembly area

# ESRF EBS (2015-2022): VACUUM CHAMBERS PROCUREMENT





All contracts in place, chambers in fabrication  
FAT for aluminium chambers in November  
All FAT should be completed by December  
More than 450 Vacuum Chambers to be procured by the end of 2018


# FAMILY 3: LOW PROFILE STAINLESS STEEL CHAMBERS

Material : 316 LN

Curved Chambers



BPM Block





Requested shape tolerance: 0.3mm!

EB Welding

Thick ante-chamber acting as stiffener


1,5mm sheet





Deformation at the Beam area 0.125mm

Joel Pasquaud

# BELLOW RF FINGERS: ESRF DESIGN PATENTED



Bellow assembly




Part pushing blade to contact

**Contract in place**

RF Finger

Blade contact

- Smooth transitions between profiles
- No change of the profile inside the RF fingers





Courtesy of P Brumund,  
L Eybert, L Goirand

# PRODUCTION – VACUUM CHAMBERS


(STAINLESS STEEL)

Stainless steel chambers: 2 contracts FMB (D)  
CH14: 1 contract PINK (D)

CH4 high profile pre series



CH12 high profile pre series



Pre-series still in progress

CH1 high profile pre series

CH7 low profile pre series in progress



CH3 & 11 high profile pre series




*Courtesy of P Van Vaerenbergh, J Pasquaud, L Goirand*

# PRODUCTION – VACUUM CHAMBERS & OTHERS

Aluminium Vacuum chambers


pre-series: still in progress



January 2017  
Factory acceptance for;

- Photon absorbers


# ESRF EBS (2015-2022): ABSORBERS PROCUREMENT




**Family Teeth** (up to  $110 \text{ W/mm}^2$ )

**Family Frontal** (up to  $50 \text{ W/mm}^2$ )


**All contracts in place**  
**400 Absorbers in fabrication**



Crotch 1



ABS CH9-1-29



ABS CH4-1-1



ABS CH5-1-1





ABS CH13-1-13

**No weld, no braze**


*D. Coulon, Y. Dabin, Th. Ducoing,  
E. Gagliardini, Ph. Marion, F. Thomas*

# ABSORBERS WITH TEETH OPTIMIZED TO REDUCE THERMAL STRESSES

Teeth distribute the heat over a larger area





Teeth geometry optimized to reduce thermal stresses




A: temperature is max Stress is min

B: temperature is min Stress is max








*D. Coulon, Y. Dabin, Th. Ducoing, E. Gagliardini, Ph. Marion, F. Thomas*

Stress criteria < Yield strength




80% of the losses are relocated on the scrapers for 4% lifetime reduction:



No scrapers

Two scrapers in DR\_37 of cells 13 and 24

# COLLIMATOR FOR CH.#12 IN CELLS 13 AND 24







# CURRENT TRANSFORMER & STRIPLINES


all in Ch.#12

1. H stripline
2. V stripline
3. Current transformer

all detailed designs ready  
CFTs by December 2016




# PRODUCTION - SUPPORTS



All supports in  
Production phase

Vacuum Chambers supports  
KURSTERS & BOSCH (NL)



Dipole supports KINKELE (D)


Magnets supports CASTELLINI (IT)



*Courtesy of L EYBERT*

# BEAM LOSS MONITORS : COMPACT, CHEAP, PERFORMING


BLD with its Alu housing  
190x25x25mm



connectors  
sma & RJ-25

compact BLD is an in-house design  
extensively tested & optimized  
for ESRF usage  
160 units in procurement  
costs: <550 € per unit

BLM is the full control & signal acquisition  
for 4 BLDs → 40 units in procurement



# 1000 LARGE POWER SUPPLIES AND 1000 SMALL POWER SUPPLIES

Type	Name	quantity per cell	NOMINAL FIELD VALUES			Electrical design PS				nom maxWatt				
			Length [m]	dB/dx [T/m]	lattice	Power [kW]	Voltage [V]	Current [A]	OVdesign factor	Watts lmax	Watts Pnom	Watts Pmax	Watts cell	maxWatt P total cell
Quadrupole, mod. gradient	QF1	2	0.349	53.7		1.06	12.1	87.5	1.2	102	1167	1576	2334	3152
Quadrupole, mod. gradient	QD2	2	0.266	51.5		0.86	9.8	87.5	1.2	106	966	1418	1932	2836
Quadrupole, mod. gradient	QD3	2	0.216	46.5		0.74	8.4	87.5	1.2	117	843	1519	1687	3037
Quadrupole, mod. gradient	QF4	4	0.216	51.5		0.74	8.4	87.5	1.2	106	843	1238	3373	4952
Quadrupole, mod. gradient	QD5	2	0.212	52.5		0.86	9.8	87.5	1.2	104	966	1364	1932	2729
<b>Total</b>		<b>12</b>											<b>11257</b>	<b>16705</b>
Quadrupole, high gradient	QF6	2	0.36	95.2		1.42	15.7	90.4	1.1	99	1535	1857	3070	3714
Quadrupole, high gradient	QF8	2	0.48	96.2		1.66	18.6	89	1.1	98	1767	2139	3535	4277
<b>Total</b>		<b>4</b>											<b>6605</b>	<b>7992</b>
Dipole-Quadrupole, high field	DQ1	2	1.11	37.54	33.9	1.59	15.75	100.7	1.2	121	1729	2490	3458	4980
Dipole-Quadrupole, mod field	DQ2	1	0.77	37.04	33.7	1.38	17.0	81.0	1.2	97	1469	2116	1469	2116
<b>Total</b>														
Sextupole, long	SF	2				1.01	11.7	86	1.1	95	1111	1344	2222	2689
<b>Total</b>		<b>6</b>											<b>6666</b>	<b>8066</b>
Octupole	OF1-2	2	0.1			0.30	3.2	94	1.2	113	426	613	852	1226
<b>Total</b>		<b>2</b>											<b>852</b>	<b>1226</b>

**Contracts in place by December 2016**

**27** Total PS power for **one cell** for main electromagnets **30.3** **41.1**  
KW KVA

	magnet	coils	type
corrector AC+DC (5 independent coils)	3	5	AC+DC
Sextupole, short correctors	6	6	DC

Total number of coils/cell **51**


About 1000 DC-DC low voltage converters: the average channel power is around 1kW and a maximum of 2.3kW.

The stability requested will be 15ppm with a MTBF of more than 400 000 hours.

The integration in 32 cabinets will be designed with the Computer Services for redundancy and **HOT-Swappability**


Girders 1 and 4

**130 girders, 10-12t each**



**All contracts in place, girders in fabrication**

Girders 2 and 3



**All girders will be fully assembled before starting the shutdown for installation**

# PRODUCTION - GIRDERS



← Pre-series girders delivered

Series girder, 2 contracts  
production 8 every 5 weeks (total 129+1 spare)




**NORTEMECANICA (SP) 65**

**AVS (SP) 65**




*Courtesy of T Brochard,  
F Cianciosi*


# GIRDERS ASSEMBLY




# SEQUENCE OF MAGNET INSTALLATION




# SEQUENCE OF VACUUM ASSEMBLY



# STATUS - VACUUM ASSEMBLY – GIRDER 1



# OVERVIEW OF THE INFRASTRUCTURE IN THE TUNNEL (AS OF 22-09-2016)



**“Standard cells”**  
Design in progress

**“Specific cells”**  
C5 – C7 – C25 (RF)

**“Specific cells”**  
C13 - C24 (Collimator)

**Injection zone TL2**

**3D layout in progress (MEG)**

3D - Girders

3D - Front end


3 D - Straight section

**And then drawings :**

For the piping

For the cable trays

# GENERAL OVERVIEW OF BUILDINGS (AS OF MAC4)



# ESRF01 – ESRF02 A/B – WORKS IN PROGRESS




## Main steps since the last MAC (4):

- Metallic structure
- Facade
- Overhead crane
- Ground preparation - Asphalt
- Concrete slab
- Facilities

# DISMANTLING – INSTALLATION – PLANNING OVERVIEW

[NO LEVELING] - 5 Entry points to install the new girders



# CONCLUSION

- Engineering Design virtually completed
- Procurement in full swing
- Delivery of all pre-series components almost completed (4 vacuum chambers still missing)
- Serial production for many components (magnets, vacuum components, supports, absorbers, girders etc...) proceeding well
- Many installation activities (cabling, buildings etc) are being anticipated
- **Schedule now heavily linked to external manufacturers!**
- Logistic activities proceeding very well

**Many thanks to all the ESRF staff for the great enthusiasm, support and achievements...**

MANY THANKS FOR YOUR ATTENTION

