

MPGD Updates on Outer μ RWELL-BOT Test Article

Xinzhan Bai, Kondo Gnanvo, Seungjoon Lee, Brian Kross, Sourav Tarafdar,
Andrew Lumanog, Evan Emerson, Caleb Graham, Drew Weisenberger, Eric
Christy

JLab EIC Weekly Meeting


October 24th, 2025

Electron-Ion Collider




μ RWELL –BOT : ePIC MPGD Barrel Outer Tracker

μ RWELL-BOT layout



Module design



- **24 module: 12 modules in ϕ \times 2 modules in z**
- No overlaps in ϕ and in $z \sim 10\%$ dead area
- 7,168 readout channels / module
- **86K readout channels**
- $R_{\min} = 72.5$ cm; $R_{\max} = 75$ cm

Module dimensions

$Z = 180$ cm

$R \times \phi = 36$ cm

Active zone dimensions

$Z = 170$ cm

$R \times \phi = 33$ cm


Expected performance

- Spatial resolution: < 100 (250) μm in Z ($r\phi$)
- Time resolution $\sim 10\text{ns}$
- Efficiency $\geq 95\%$
- Material budget $\sim 2\% X_0$

<https://eic.jlab.org/Geometry/Detector/Detector-20240515102931.html>



Integration in ePIC

Installation & Maintenance



Both MPGD modules must be inserted and removed from the east side for maintenance and servicing


μ RWELL-BOT: Service Requirement



Type	Size (OD,mm)	Model	Qty/Module
Data cable (optical)	3	OM3/OM4	14
High Voltage	3.2	HTC-50-1-1 (CEH50)	4
Low Voltage	5	Alpha Wire 3464C	14
Gas	5	PTFE	2
Cooling	6	Copper/Stainless steel tubing	2
Env. Sensor (temp, humid)	1	--	3
Ground			1

- The volume and diameter of each service line are subject to change as the FEB design progresses.
- The cooling requirement has not yet been finalized.
- The current cooling approach utilizes water cooling with a heatsink.
- Three subsystems—BOT, ECT, and CyMBaL—will collaborate on the cooling system design.

μ RWELL –BOT : Module Structure



Thin-gap GEM- μ RWELL: Performance Studies in Test Beam



Test beam campaigns @ FNAL (2023) and @ JLab (2025) for performance study and optimization of thin-gap GEM- μ RWELL prototypes

FNAL test beam (06/2023): Position resolution vs. track angle

- ❖ 3 protos: 0.5 & 1 mm thin-gap GEM- μ RWELL, 3-mm std μ RWELL
- ❖ 4 HV scans for efficiency study with Ar:CO₂ (80:20) gas mixture
- ❖ Track angle scan (0 – 45°) for position resolution comparison studies

JLab Hall D test beam (06/2025): - Efficiency vs. gas mixtures

- ❖ 2 protos: 1-mm and 1.5-mm thin-gap GEM- μ RWELLs
- ❖ HV scan for efficiency study various Ar-based mixtures
- ❖ Argon gas mixture: (Ar/CO₂ & Ar/CO₂/Iso)



Electron-Ion Collider




Preparation for the third campaign to study performance in 1.5T field in the GOLIATH magnet

JLab EIC Weekly Meeting, October 24th, 2025

in Spring 2026 at the CERN SPS H4 line

Thin-Gap GEM- μ RWELL: Performance Studies in Test Beam

- Efficiency : 95%
- Thin-Gap leads to significant position resolution improvements without degrading efficiency




Engineering Test Article – Foils & Frames


μ RWELL / CapaSh readout PCB: Front view



μ RWELL / CapaSh readout PCB: back view



GEM foil



Support frames



Engineering Test Article – Assembly Workflow


Workflow for the Assembly of the Test Article

Components:

- Detector Frame
- GEM Foil
- μ RWELL Foil


Includes cleanroom activity and non-cleanroom activity

Highly customized instruments – tailored to detector size and shape




Two Labs : Cleanroom and EEL126 (RD&I Group MPGD Lab) Layout

EEL-121 Cleanroom Layout




Both labs are packed with instruments

RD&I Group MPGD Lab (EEL-126)






Cleanroom Instruments – HV Nitrogen Box

- GEM Foil High Voltage Test (GEM Foil HV Cleaning)
- Includes two steps:
 - Raw GEM foil
 - Framed GEM foil (stretched and glued to detector frame)




Cleanroom Instruments – GEM Foil Stretcher

- Stretch GEM Foil
- Glue detector frame to the foil after stretching



Cleanroom Instruments – μ RWELL Assembly Stand

- For final detector chamber assembly (μ RWELL assembly)
- Advised by CERN : class-10 cleanroom (hard to get at JLab)
- A customized flow hood (placed inside the cleanroom)
 - Keep a laminar flow over the μ RWELL board surface during assembly
 - Volume-adjustable HEPA Filters




Flow Hood with **Andrew Lumanog** standing inside

RD&I Group MPGD Lab Instruments – Sanding Stand

- Detector frame grids – 0.4 mm thick spacers to support GEM foil from sagging
- Inside the detector volume
- Sanding to reach a smooth surface and varnishing to seal the spacers
- Sanding stand design suggested by JLab industrial hygienist

Constructed using 1 inch wide Aluminum T-Slots




RD&I Group MPGD Lab Instruments – Ultrasonic Bath

- Ultrasonic bath to clean the frame
- Fill with de-ionized water
- Purchased a large volume ultrasonic bath
- Pending installation in EEL-126




RD&I Group MPGD Lab Instruments – Fume Hood

- Apply a thin film of Varnish to seal the spacers after sanding and ultrasonic bath cleaning
- Varnish work requires a Fume Hood
- Pending installation in EEL-126





Cleanroom Instruments – Frame Drying Stand

- Dry the frames after cleaning in ultrasonic bath
- Process needs ~24 hours in cleanroom



Detector Assembly – Honeycomb Supporting Board


- Nomex honeycomb core material (Axiom)
- Light rigid material
- Material come in as a whole piece
- Cut into correct size



Honeycomb board structure

Honeycomb Board Assembly – Honeycomb Preparation

- Glued with 125 micrometer thick G10 skin – vacuum bagging process



Honeycomb Board Assembly – Status

- Frame Preparation (sanding, honeycomb preparation) completed
- Vacuum bagging pending safety review
 - Safety requirement
 - Review expected to be completed this Friday

REPRINTED

Jefferson Lab

JLab-PTW-8649

PERMIT TO WORK

PERMIT DETAILS

Permit Request No:	JLab-PR-8649	Permit Prepared By:	Xinzhan Bai
Work Group:	RD&I	Issue Date:	09/18/2025 16:53
Area:	Bldg 90 - Experimental Equipment Lab (EEL) Shops/Labs	Expected Expiry Date:	01/10/2026 16:00
Task Number:		Organisation:	DETIMG
Project Title:		Outage:	
Account Code:			
Has Simple LOTOs:	No		
Notes:			
Special Requirements:			

PLANT & WORK

Title:	EIC tracking detector frame preparation
Primary Plant Item:	126 - EXPERIMENTAL EQUIPMENT LAB (EEL) - 126
Work Scope	
Job Description:	Detector frame preparation for EIC EPIC outer barrel tracking detectors.
Tools & Equipment:	Sandpaper and HEPA vacuum
Equipment Number	Description
126	126 - EXPERIMENTAL EQUIPMENT LAB (EEL) - 126

CONTROL CERTIFICATES

Certificate#	Description	State	Issue Date

ATTACHED DOCUMENTS

Name	Doc Type	Attached Date

APPROVALS

I confirm that the control measures specified on this permit and the Task Hazard Analysis (and the references attached) are sufficient and that I have reviewed the work as specified on this permit and authorize it to proceed.

PTW Issuer Sign: Andrew Weisenberger Date: 09/9/2025 14:34

This Permit applies only for the occasion specified. No person may leave the site with this JLab-PTW-8649 in his or her possession.

Thursday, October 23, 2025 9:37

Printed By: Xinzhan Bai (757-269-5006)

Page 1 of 3

DRAFT

Jefferson Lab

JLab-PTW-8924

PERMIT TO WORK

PERMIT DETAILS

Permit Request No:	JLab-PR-8924	Permit Prepared By:	Xinzhan Bai
Work Group:	RD&I	Expected Issue Date:	10/14/2025 08:00
Area:	Bldg 90 - Experimental Equipment Lab (EEL) Shops/Labs	Expected Expiry Date:	02/14/2026 16:00
Task Number:		Organisation:	DETIMG
Project Title:	EIC Outer Barrel Tracker Detector Frame Preparation	Outage:	
Account Code:			
Has Simple LOTOs:	No		
Notes:			
Special Requirements:			

PLANT & WORK

Title:	EIC outer Barrel Tracker Honeycomb Board Preparation
Primary Plant Item:	108 - EXPERIMENTAL EQUIPMENT LAB (EEL) - 108
Work Scope	
Job Description:	Assembly the top support honeycomb board for the EIC tracker detector
Tools & Equipment:	vacuum pump
Equipment Number	Description
108	108 - EXPERIMENTAL EQUIPMENT LAB (EEL) - 108

CONTROL CERTIFICATES

Certificate#	Description	State	Issue Date

ATTACHED DOCUMENTS

Name	Doc Type	Attached Date

APPROVALS

I confirm that precautions specified on this permit (and the references attached) are sufficient and that I have reviewed the work as specified on this permit and authorize it to proceed

ESH SME Industrial Sign: *** NOT APPROVED *** Date:

Hygiene

I confirm that the control measures specified on this permit and the Task Hazard Analysis (and the references attached) are sufficient and that I have reviewed the work as specified on this permit and authorize it to proceed .

PTW Issuer Sign: *** NOT APPROVED *** Date:

Thursday, October 23, 2025 9:38

Printed By: Xinzhan Bai (757-269-5006)


Page 1 of 4

RD&I MPGD Lab Installation Status

- Detector frame preparation in EEL-126 (RD&I Group MPGD Lab)
 - Sanding
 - Varnishing – Flow hood
 - Cleaning – Ultrasonic bath
- EEL-126 Installation (JLab Facility)
 - Ultrasonic bath
 - Fume hood
- Delay to be expected (Government shutdown)

Engineering Test Article – Timeline

- Detector frames (RESARM), GEM Foil, μ RWELL (CERN) Received
- Major instruments delivered, installation in progress
 - Infrastructure ready for construction – **November**
 - Detector ready for benchmarking – **December (before Christmas)**
- Preliminary cosmic test – **early January**
- Planned beam test at CERN – **spring 2026**
- **Contingent on Lab operation schedule (government shutdown)**



Summary

- All major instruments, detector frames, detector foils on-hand
- Cleanroom preparation complete
 - All major instruments in place
- EEL-126 MPGD Lab installation – (JLab Facility is taking charge of)
 - Fume Hood installation
 - Ultrasonic bath installation
- Detector fabrication to begin upon EEL-126 installation completion

Backup Slides

Honeycomb Board Assembly – Vacuum Gluing

- Vacuum bagging process – performed on a Granite table – ensure flatness
- Process under safety review by JLab industrial Hygienist

