

# Hall D Beam Test

March Commissioning Beam Test Preparation

# Logistics

See email with subject: *Hall D Parasitic Beam Test – Registration, Training, and Logistics (on what we know now)*

- Please proceed with registration and required training

Asana:

<https://app.asana.com/1/1206466510795502/project/1209235715111537/list/1209236993954172>


Mattermost:

<https://chat.epic-eic.org/main/channels/bic-beamtest>

# Training

- GEN034: Security Awareness
- CST001: Cyber Security Awareness
- SAF100: ES&H Orientation
- SAF103: Oxygen Deficiency Hazards
- SAF801C: Radiation Worker Initial Training (online)
- SAF801P: Radiation Worker Practicum (one-time, **in person**)
- SAF801T: Radiation Worker Exam (proctored, **in person**)
- SAF801KD: General Access RWP
- SAF113: Hall D Safety Awareness (includes walkthrough, in person) - **Will organize it for everyone (Rad Worker Training and Dozimeter needed)**
- ESC001: Basic Electrical Safety Training (on teams, **only selected days - Thu, March 19, 9-11 AM**)

# EIC prototypes beam-tests in Hall-D 2026 ( new )



Start March 30 - End Aug 30

Switch from Low to high energy configuration

Feb 27, 2026.

Week	date	Energy	Left arm (tracking )	Right arm ( CAL)
W1	March 30	Low		HALL-D HICAL
W2	April 8	Low		HALL-D HICAL
W3	April 15	Low	BIC	HALL-D HICAL
W4	April 22	Low	BIC	HALL-D HICAL
W5	April 29	Low	BIC	HALL-D HICAL
W6	May 6	Low	MPGD	MOLLER
W7	May 13	Low	MPGD	MOLLER
W8	May 20	Low	Short week / SWITCH TO HIGH ENERGY	
W9	May 27	Low	SWITCH TO HIGH ENERGY	SWITCH TO HIGH ENERGY
W10	June 3	Low	Short week/ SWITCH TO HIGH ENERGY	
W11	June 10	High	HALL-D TRD	HALL-D TAG-M
W12	June 17	High	HALL-D TRD	HALL-D TAG-M
W13	June 24	High	HALL-D TRD	HALL-D TAG-M
W14	July 1	High		CRYTOR
W15	July 8	High		CRYTOR
W16	July 15	High		CRYTOR
W17	July 22	High	LUMI	HALL-D HICAL
W18	July 29	High	LUMI	EEECAL
W19	Aug 5	High	BIC	EEECAL
W20	Aug 12	High	BIC	EEECAL
W21	Aug 19	High	SVT/MPGD	EEECAL
W22	Aug 26-Aug 30	High	SVT/MPGD	

# Logistics

- Our current plan (ANL folks) assumes that we arrive on **March 22/23** for installation.
- Magnet installation is invasive, all halls will go into shutdown
- From the info we have currently, the magnet installation will start Monday (e.g., April 13, and take a week). So this would mean, beam available on April 17.

Please indicate your availability here:

<https://docs.google.com/spreadsheets/d/1SGdw8OcbCEeJBJPANbpdIGxSmSlmJjd7WrSDrztxn0Y/edit?usp=sharing> In “Presence Overview” tab.


I will add a new table with availability for April 15 - May 6

- We will need people to help us cover the actual running time!

SFILs  
SciFi intermediate  
layers

Baby BCAL

beam



# News after visit in JLab



# Baby BCAL



# News after visit in JLab

- Team arrival March 22/23, setup starts in EEL
- Move to Hall D once access window opens
- Baby BCAL shipping underway, storage plan depends on hall availability
- Cable routing and length under review
- Andrew Lumanog will serve as equipment POC/custodian
- ePASS and guarding plans look on track
- Limited RadCon clearance expected for select electronics
- Important logistics: EEL access, hpDIRC restrictions, escorted student hall entry, notify Scot ([spiegel@jlab.org](mailto:spiegel@jlab.org)) before hall access

# Logistics

Our cubicle:

**GlueX cubicles are F306 (CEBAF building)**

**ANL cubicles (4 spots) F340 (CEBAF building)**

**Room for daily meeting: TBD (1 PM)**

# Backup


SFILs  
SciFi intermediate  
layers

Baby BCAL


beam

Trigger Paddles

- To be calibrated
- Split into GlueX DAQ



# Main Components - Signal Routing




AS - Analog Signal  
DS - Digital Signal

# Signal Routing

## Trigger and Clock

AS - Analog Signal



# Plan

High level goal:

Commission for the first time the readout with HGCROC.

Prepare for running in August at 3-6 GeV with full HGCROC readout to determine energy resolution and timing response within optimal for running and full BIC dynamic range.

Synchronize AstroPix and SciFi/Pb readout for shower imaging event by event.

# Plan

- 2 days running with ADC only settings (about 0-80 MIP range). We will lose some of the smallest signals, but no TOT in the beginning.
- 6 hours of running ADC only settings for 1-6 GeV setting (for the Aug preparation). Here we would lose most of the small signal, that's why only 6 hours.
- 2 days running ADC+TOT for 1-6 GeV settings
- 2 days running ADC+TOT for 0-10 GeV settings (for the BIC high-precision running) rest time 0-50 GeV settings (hadron side of BIC)

# Detector Requirements for BIC



<https://eic.jlab.org/Requirements/>

Identify scattered electrons and measure their energy, in high  $Q^2$  events, also decay electrons, e.g. from vector or heavy flavor meson decays, and to measure DVCS photons and decay photons (G-DET-ECAL-BAR.16.10.05)

- **Electron ID up to 50 GeV** and down to 1 GeV and below (F-DET-ECAL-BAR.16.10.05)
  - Energy resolution  $< 10\%/\sqrt{E} + (2-3)\%$  (P-DET-ECAL-BAR.16.10.05)
  - High power for  **$e/\pi$  separation down to 1 GeV/c** (P-DET-ECAL-BAR.26.10.05)
- **Photon measurements up to 10 GeV** (F-DET-ECAL-BAR.26.10.05)
- **$\gamma/\pi^0$  separation up to 10 GeV** (F-DET-ECAL-BAR.36.10.05)
  - Distinguishing two showers with opening angle down to 30 mrad (P-DET-ECAL-BAR.36.10.05)

**Assist with muon identification** (G-DET-ECAL-BAR.36.10.05)

Sufficient dynamic range to **detect MIP** signals in all layers (P-DET-ECAL-BAR.56.10.05)



# Stimulations

**Check max and mean energy deposit for the following cases:**

- Extremes: 19 GeV electron at  $\eta = -1.7$ , 50 GeV electron at  $\eta = 1.4$
- From the EIC detector requirements: 10 GeV photon in whole  $\eta$  range

Simulations translate energy loss to nphe using the measurements with GlueX BCAL SciFi/Pb matrix, known attenuation behavior, corrections for single-clad kuraray fiber, optical connection and light-guide efficiency


Charge is simply calculated using the expected gain at nominal operational voltage (2.7V for the S14 SiPM Matrix):  $Q = G \cdot N_{pe} \cdot e$  (G - gain =  $2.5 \cdot 10^6$ )

# What is the lowest signal measurement required? (fC)

10-11 phe

MIP peak MPVs vs SciFi/Pb layer  
for  $\eta = 0$  (worst case scenario)

**0.004 - 0.0044 nC**



# What is the highest signal measurement required? (fC)

See Maria's presentation from June 24, 2025: <https://indico.bnl.gov/event/27551/>

10 GeV  $\gamma$  45-135 deg: mean < 0.07 nC, max < 1.1 nC

10 GeV  $\gamma$  < 45 deg: mean < 0.14 nC, max < 2.4 nC

10 GeV  $\gamma$  > 135 deg: mean < 0.14 nC, max < 2.4 nC


19 GeV electron at  $\eta = -1.7$ : mean < 0.30 nC, max < 4 nC

50 GeV electron at  $\eta = 1.4$ : mean < 0.60 nC, max < 8 nC

# Electrical Diagrams


Power supply channel and electrical outlets count

# Baby BCAL with GlueX Wedges



AS - Analog Signal  
DS - Digital Signal

# Baby BCAL with BIC Wedges



AS - Analog Signal  
DS - Digital Signal

# Total Count - Baby BCAL

## Outlets:

- 2 outlets for CAEN DT5743 WF Digitizers (Remote-controlled power strip)
- 1 outlet for DAQ Computer (Remote-controlled power strip)
- 1 outlet for the chiller (I expect this will need to be in the wall outlet)
- 2 slots in MPOD crate for power supply modules or we can bring our own crate if no space in the existing one. (platform, limited by the power cable lengths - they are borrowed from GlueX)

**Question to Andrew:** What needs to be the wall outlet and what the power strip?

**Power line count:** (see the diagram on previous page)


GlueX Wedges

- 8 x 75V (MPOD ISEG)
- 4 x 5V (MPOD Wiener)

BIC Wedges

- 2 x 40.7V (MPOD ISEG)
- 2 x 5V (MPOD Wiener)
- 2 x -5V (MPOD Wiener)

# SFILs - week 1






# Total Count - SFILs

## Outlets:

- 2 outlets/slots in power strip for 2 fans (cooling)
- 2 slots for KCU FPGA (remote controlled strip)
- 1 slot in MPOD crate for LV power supply modules or we can bring our own crate if no space in the existing one. (upstairs)
- 2 outlets for R&S Power Supplies NGA142
- 2 outlets for R&S Power Supplies HMP4040

## Power line count: (see the diagram on previous page, max from 2 setups is taken)

- 8 x 5V (MPOD, 8 ch LV module) - HGCROC boards
- 8 x +5V (R&S HMP4040, 4 ch power supply) - Summing boards
- 8 x -5V (R&S HMP4040, 4 ch power supply) - Summing boards
- 8 x <43V (R&S NGA142, 2 ch power supply) - bias



# Total Count - AstroPix


## Outlets:

- 1 outlet for WF Generator (Remote-controlled power strip)
- Same MPOD LV Module as for Baby BCAL

## Power line count: (see the diagram on previous page)

- 1 x 5.3V (MPOD Wiener)

# Trigger Paddle - Full Electrical



# Total Count - Trigger

## Crates/Outlets:

- 1 Slot for the NIM Crate (NIM logic for trigger and HV supply for paddles - HV Supply Bertan Model 365)

## Power line count: (see the diagram on previous page)

- 4 x HV 1250V (<0.1mA)

# Summary of outlets, crates, etc

## Crates/ Slots in Crates:

- Slots for 3 MPOD Modules (1 x ISEG 100 V power supply, 2 x Wiener 16 V power supplies) - close to the setup (platform). We can bring our own crate if needed.
- 1 Slot for the NIM Crate (NIM logic for trigger and HV supply for trigger paddles - HV Supply Bertan Model 365). We can bring our NIM crate or use the available one. Preferably upstairs.

## Remote controlled power strip slots:

- 2 outlets for CAEN DT5743 WF Digitizers
- 1 outlet for DAQ Computer
- 2 slots for KCU FPGA
- 1 outlet for WF Generator (Do we want it in remote controlled ones?)

## Outlets/power strip slots:

- 1 for the chiller (cooling)
- 2 for fans (cooling)
- 2 outlets for R&S Power Supplies NGA142
- 2 outlets for R&S Power Supplies HMP4040

