

sPHENIX Director's Review

Robert Pisani
Physics Associate, BNL

August 2-4, 2017

BNL

TPC Support Systems Scope




From the WBS Definitions

- **1.2.7 TPC Support Systems** TECHNICAL SCOPE: CONTAINS ALL TASKS WHICH ARE REQUIRED TO PROVIDE NECESSARY SUPPORT SYSTEMS FOR THE TPC: LASER, GAS, COOLING SYSTEM. WORK STATEMENT: PROVIDE ALL PARTS TO SUPPORT TPC OPERATION.
 - **1.2.7.1 TPC Laser System** TECHNICAL SCOPE: THIS ITEM CONTAINS ALL TASKS WHICH ARE REQUIRED TO IDENTITY COMPONENTS FOR THE TPC LASER CALIBRATION SYSTEM AND PROCURE AND CONSTRUCT THE ELEMENTS OF THE SYSTEM. WORK STATEMENT: PROVIDE ALL PARTS TO PRODUCE THE LASER CALIBRATION SYSTEM AND ASSEMBLE/INSTALL ALL PARTS.
 - **1.2.7.2 TPC Gas System** TECHNICAL SCOPE: THIS ITEM CONTAINS ALL TASKS WHICH ARE REQUIRED TO IDENTITY COMPONENTS FOR THE TPC GAS SYSTEM AND PROCURE AND CONSTRUCT THE ELEMENTS OF THE SYSTEM. WORK STATEMENT: PROVIDE ALL PARTS TO PRODUCE THE GAS SYSTEM AND ASSEMBLE/INSTALL ALL PARTS.
 - **1.2.7.3 TPC Cooling System** TECHNICAL SCOPE: THIS ITEM CONTAINS ALL TASKS WHICH ARE REQUIRED TO IDENTITY COMPONENTS FOR THE TPC GAS SYSTEM AND PROCURE AND CONSTRUCT THE ELEMENTS OF THE SYSTEM. WORK STATEMENT: PROVIDE ALL PARTS TO PRODUCE THE GAS SYSTEM AND ASSEMBLE/INSTALL ALL PARTS.


sPHENIX Detector Relativistic Heavy Ion Collider BASIS of ESTIMATE (BoE)			
L2 Project Name	L2 WBS Number	L3 Project Name (Control Account)	L3 WBS Number
Time Projection Chamber	1.2	TPC Support Services	1.2.7
Work Package Name	WBS Number	Basis of Estimate Link	
TPC Laser System	1.2.7.1	Laser-Summary	
TPC Gas System	1.2.7.2	Gas-Summary	
TPC Cooling System	1.2.7.3	Cooling-Summary	

Laser System Technical Design Drivers

- **A Laser System(1.2.7.1)**- Lasers can be used to produce ionization in the TPC volume that provides both a source of signals and a calibration. This includes pattern applied to the central membrane (STAR) as well as direct laser transmission through the gas (STAR and ALICE). In the case of STAR and ALICE, the lasers going through the gas are directed via fibers and mirror bundles to criss-cross planes at several Z locations. The fiber bundles take radial space that both STAR and ALICE can afford. Due to the small size, sPHENIX cannot afford to have a bundle running along Z. Therefore we shall use two solutions to laser calibration. First, we will shine diffuse laser light onto the patterned central membrane. Second, we will allow for angled trajectories of laser light emanating from between the modules traveling at various angles through the gas. While not ideal it is a better solution than losing radial space.



Place Holder



cathode with
alumina dots

Cooling System Technical Design Drivers

- A Cooling System(1.2.7.3)- Cooling system need to be designed to remove 12kWatts of heat from the TPC Fee's which are located on the end caps of the TPC inside the SPhenix magnet. System to be operated below atmospheric pressure to prevent coolant leaks.

Segment system along the 12 sectors and remove 500 watts from each


300 Fee Cards per End Cap:
Inner: 5/Module
Middle: 8/Module
Outer: 12/Module

Take heat out with chillers



Chilled water sent to TPC

Cooling system must be thermally coupled to the Fee Board

FEE estimated max ~20 watts per board




Heat Source



The Gas System Design Drivers

TPC Gas System Requirements

- Neon based gas mixture
- 6 turnover a day
- 4000 liter volume
- Slight overpressure above atmosphere
- Compensate for changes in barometric pressure
- High purity system
- Recirculation required (\$)
- Remote monitoring
- Alarming



• A Gas System (1.2.7.2)--- High purity re-circulations system for a Ne based operating gas. System need to be operated at constant atmospheric pressure (0.5" w.c.) while turning over the gas volume (4000 liters) six times over 24hrs.

Subsystem Collaborators

Stony Brook University



Faculty



Postdocs



Grad Students



Electrical Engineer
(retired)


AGS experiments Tracking, PHENIX Tracking,
PHENIX HBD, ILC TPC, generic TPC R&D

A steady stream of undergrads





Brookhaven National Laboratory

AGS Tracking, PHENIX Tracking,
LEGS TPC, generic TPC R&D



T2K Gas

Small TPC w/ Chevrons




Some Key Personnel:


- Paul Giannotti – Principal Electrical Engineer (BNL)+20 Monitoring and alarms system experience.
- Don Lynch-- Chief Engineer (BNL)15 yrs thermal engineering experience, 20 yrs mechanical experience with BNL
- Robert Pisani—Physic Associate (BNL) 20+ years of gas systems and 10+ cooling systems experience.
- Carter Biggs --Sr Tech 20+ experience with technical support gas and cooling systems
- Dr. Leonid Kotchenda Sr Scientist (PNPI_20+ experience with gas system
- Dr. Peter Kravtsov Sr Scientist (PNIP)20+ experience with Gas systems
- Tom Hemmick Sr Scientist (SUNY SB) 20+ years gas detector experience
- Bob Azmoun Physics Associate +15 yrs experience gas detectors
- Sean Stoll Physics Associates +25 yr experience detectors and lasers.

PNPI

Phenix and Star gas system, (HBD,TOF,MuID, MuTR, TPC, ...



Cryogenic and Superconductive Techniques Laboratory
High Energy Physics Division of PNIP



Schedule Milestones

• Gas system


- Design Winter 2019
- Safety & Design Review Feb 2020
- Procurement of parts Spring 2020
- Assembly of system Summer 2020
- System Complete August 2020

• Cooling System

- Design Winter 2019
- Safety & Design Review January 2020
- Procurement of parts Winter/Spring 2020
- Assembly of system Spring 2020
- System Complete July 2020

• Laser system

- Design Fall 2019
- Safety & Design Review November 2019
- Procurement Assembly of system Winter 2019/2020
- Assembly of system Spring 2020
- System Complete June 2020



The Gantt chart illustrates the project schedule from 2/4/20 to 8/10/20. The project is divided into four main phases: Design, Construction, Commissioning, and Handover. The Design phase is a single long bar. The Construction phase is divided into four sub-phases, each represented by a bar. The Commissioning phase is a single bar. The Handover phase is a single bar. The chart shows a step-down pattern of activities over time.


Estimated Labor

			hours	cost	hours
Acquire final quotes	Engineer	60	100%	60	
Place orders	engineer	40	100%	40	
Verify parts	Tech	80	100%	80	
Design Gas system	Engineer	120	100%	120	
Design interlocks	engineer	40	100%	40	
Design interior manifolding (on endcap)	engineer/designer	20	200%	40	
Assemble Electronics Rack	Engineer/Tech	80	200%	160	
Install Flowmeters	Tech	8	100%	8	
Install Filters	Tech	8	100%	8	
Install Scrubbers	Tech	16	100%	16	
Install Analyzers	Tech	8	100%	8	
Instrument control Racks	tech	24	100%	24	
Hookup electronics	Engineer/Tech	80	200%	160	
Instrument gas rack	engineer/tech	120	150%	180	
Run Lines to IR	tech	80	200%	160	
Test lines to IR	Tech	16	100%	16	
Plumb gas rack	Tech	80	100%	80	
Test Gas racks for leaks	Tech/Engineer	16	200%	32	
Assemble IR manifolds	tech	80	100%	80	
Test IR Manifolds	tech	8	100%	8	
Plumb IR Manifolds	Tech	20	200%	40	
Install detector plumbing(Manifold to Detector)	tech	40	200%	80	
Test gas rack	Engineer/Tech	40	200%	80	
Install Monitoring instrumentation in IR	Engineer/Tech	60	200%	120	
				0	
Comission system	engineer/tech	80	200%	160	

Basis of Estimate and Resource-Loaded Schedule

Cooling System

256	1.2.7.3	TPC Cooling System	212 days	Fri 8/30/19	Wed 7/8/20	
257	1.2.7.3.1	Design TPC Cooling System	80 days	Fri 8/30/19	Fri 12/27/19	279
258	1.2.7.3.2	TPC Cooling System Safety Review	0 days	Mon 1/6/20	Mon 1/6/20	257FS+5 days
259	1.2.7.3.3	TPC Cooling System Design Review	0 days	Mon 1/13/20	Mon 1/13/20	258FS+5 days
260	1.2.7.3.4	Procure TPC Cooling Sys tem equipment(pumps,heat	60 days	Tue 1/14/20	Wed 4/8/20	259
261	1.2.7.3.5	Install TPC Cooling System pumps	3 days	Thu 4/9/20	Mon 4/13/20	260
262	1.2.7.3.6	Install TPC Cooling System heat exchanger	3 days	Tue 4/14/20	Thu 4/16/20	261
263	1.2.7.3.7	Install TPC Cooling System PH control	3 days	Fri 4/17/20	Tue 4/21/20	262
264	1.2.7.3.8	Install TPC Cooling System end cap manifolds	10 days	Wed 4/22/20	Tue 5/5/20	263
265	1.2.7.3.9	Install TPC Cooling System tanks	3 days	Wed 5/6/20	Fri 5/8/20	264
266	1.2.7.3.10	Install TPC Cooling System plumbing	30 days	Mon 5/11/20	Mon 6/22/20	265
267	1.2.7.3.11	Set up TPC Cooling System computer controls	5 days	Tue 6/23/20	Mon 6/29/20	266
268	1.2.7.3.12	Set up and Test TPC Cooling System interlocks	5 days	Tue 6/30/20	Wed 7/8/20	267
269	1.2.7.3.13	TPC Cooling System Complete	0 days	Wed 7/8/20	Wed 7/8/20	268



The cost before contingency is \$138k and after contingency is \$165k


Manufacturer quotes are either assessed as 20% or 25% contingency based upon past experience with long term price stability. All other items carry 40% contingency.

Components and Hardware	Equipment		File Name	
	Equipment	File Name	Equipment	File Name
	equipment(pumps,heat exchanger, PH control, manifolds, tanks...)			
	Chillers watt 10C(3)	Thermo Scientific Merlin	\$29,100	TPCMerlin
	Deionizing filters (2)	McMaster	\$1,644	TPCFilter_Switch
	Particle filters (2)	McMaster	\$720	TPCFilter_Switch
	Valving for Chiller Switchover	McMaster	\$610	TPCFilter_Switch
	SS Manifolds (8) 6 port	McMaster	\$1,110	TPCmanifold
	Hardware (panel, brackets, mnts)	McMaster	\$1,500	estimate
	Flowmeter 24(SS) water	Dwyer	\$1,230	TPCDwyer
	Compression fittings SS (various)	Swagelok	\$3,550	TPC_Compression
	Bypass/filtering Valving at detector	McMaster	\$1,550	TPCvalving
	Pressure gauges (16)	Dwyer	\$450	TPCGauge
	Manifold valving (24)	Swagelok	\$1,575	TPCMetering
	FlexHose to Manifolds 8	Bannor Industries	\$1,600	Estimate from past
	1 1/4" thin walled SS Lines	McMaster	\$1,200	TPCtubing
	1" SS Thin walled Lines	McMaster	\$1,250	TPCtubing
	5/16" SS Coil (0.250 ID Min)	McMaster	\$1,200	TPCtubcoil
	SS Pipe fittings	McMaster	\$1,000	experience
	1 1/4" Braided lines (316 SS)	McMaster	\$1,000	tpchse
	Poly lines to detector (Various)	MSC	\$924	TPCpolyhose
	House Water Manifolding (brass)	McMaster	\$1,097	TPCwater
	Pressure Transmitters (8 min)	Dwyer	\$1,625	TPCpressureTran
	Transmitting Flowmeters (SS 1") (8)	McMaster	\$2,050	TPCFlowTran
	RTDs (8)	Omega	\$550	TPCrtcd
	RTD transmitter+local read (7)	Omega	\$2,986	TPCrtcd
	Electronic hardware	various	\$1,750	estimate
	House water Monitor (pressure)	Various	\$1,200	Web Quote
	Pressure Relief Valves 1" (2) SS	McMaster	\$882	TPCrelief
			\$63,353	

Estimated Labor	Equipment		File Name	
	Equipment	File Name	Equipment	File Name
	Design Cooling system	Engineer/tech	120	200%
	Layout Pipe loops and locations	Designer/engineer	80	125%
	Design Manifolds	Engineer/tech	80	100%
	Design Cold Plate	Engineer/tech	80	150%
	Design Cold Plate manifolding	engineer/designer	80	150%
	Get final Quotes	Engineer/tech	80	200%
	Place Orders	Engineer/tech	40	100%
	Verify parts	Engineer/tech	80	200%
	Test cold plates (600)	Tech	1200	100%
	Build Filter system/test	Tech	40	200%
	Build Manifolds/test	Tech	40	200%
	Install Chillers	Tech	80	200%
	Install Supply/Return Lines	tech	40	200%
	Install Manifolds	tech	80	200%
	Instrument Monitoring	engineer/tech	80	150%
	Test Chillers	engineer	20	100%
	Test Loop to Manifolds w	engineer	40	100%
	Test Interlocks	engineer	20	100%
	Install lines to detector	tech	120	200%
	Commission Cooling system	engineer/tech	40	200%
	Install interior manifold	tech	160	200%
	Install Cold Plates to electronics	tech	1200	100%
	Make final connections	tech/engineer	512	150%
	Test completed manifold (interior)	tech	150	100%
	Set up testing system	engineer/tech	80	100%
	Safety and Safety System			
	Design Safety interlocks	Engineer	80	200%
	Design Monitoring system	Engineer	80	200%
	Instrument interlocks to system	engineer/tech	120	150%
	Commission system	engineer/tech	80	200%

Basis of Estimate and Resource-Loaded Schedule

Laser System



The full cost of the laser system is \$144k before contingency and \$186k after contingency.

Manufacturer quotes are either assessed as 20% or 25% contingency based upon past experience with long term price stability. All other items carry 40% contingency.

Components and Hardware




WBS	Description	Item	Vendor	Total	Status	Basis of Estimate	Contingency	Item Contingency	Wt Contingency	Total	Contingency	Total w/ Contingency	Grand Total	Grand Total w/ Contingency
1.2.7.1	TPC Laser System												\$144,177	\$186,412
1.2.7.1.2	Procure TPC laser(s)	Laser	Newport	\$77,177	Pending	Manufacturer Quote	0.2	\$15,435.40	0.2	\$77,177	\$15,435	\$92,612		
1.2.7.1.3	Procure TPC optics with mirrors			\$50,000	Pending	Experience	0.4	\$20,000	0.4	\$50,000	\$20,000	\$70,000		
1.2.7.1.4	Procure TPC mirror bundles with supports													
1.2.7.1.6	Design													

Place Holder

The Gas System Status

TPC Gas System



- Based on PHENIX HBD gas system designs
- Ne mixture (Ne/CF₄/iC₄H₁₀; 95:3:2)
- Flowrate ~1m³/hr
- 1-2mBar (~0.5" w.c.) above atmosphere to +/- 1/8" w.c.
- Closed loop recirculation
- Analyzers to monitor mixture and impurities
- In line purifiers
- High purity system-all stainless
- PC Controlled
- Fully alarmed




The Cooling System Status

TPC Gas System

- Based on the PHENIX VTX/FVTX cooling system
- Negative Pressure Loop
- Modified for flow rate and load, and segmentation
- Water based coolant
- Closed loop
- Purifier loops built in
- Monitored and alarmed
- 24 channel system divided North and South
- Redundancy built into the system.
- Total heat removed 12kWatt



The Laser System Status



Place Holder

Summary

Gas System

- PHENIX hosted many high purity gas systems (HBD detector, RPC, TOF, DC, PC, RICH, MuTr, MuId). The TPC detector's needs are rather similar to the HBD ultra high purity system (even less stringent) and so we feel it is conservative to use the HBD system as a cost basis.
- The system will be designed with all stainless plumbing for highest purity and ample contamination monitoring. It is very similar to the PHENIX HBD system, whose purity and flow rates are beyond the needs of the TPC.
- We have highly experienced people collaborating on this. Many with 15 to 20+ years experience.
- The gas system cost is \$109k before contingency and \$135k after contingency. (From BOE & RLS)

Cooling System

- Our heat load is dominated by the SAMPA chips on the FEE and is thereby well understood, allowing for reasonable accuracy on the cost estimation. The heat load is significant enough that liquid cooling is required since gas cooling will be insufficient.
- The cost basis uses is extrapolated using similar systems found in the PHENIX VTX/FVTX Cooling System
- We have a skilled set of people collaborating on this with 10 to 15 years experiences.
- The cost before contingency is \$138k and after contingency is \$165k.

Laser System

- We will base the calibration system on the STAR and Alice laser calibration systems
- The full cost of the laser system is \$144k before contingency and \$186k after contingency.
- We have a skilled set of people collaboration and department with 10 to 15 years experiences.

Back Up