

sPHENIX Director's Review Infrastructure

Level II Manager: Paul Giannotti

August 2-4, 2017

BNL

1.9: Infrastructure (Paul Giannotti)

1.9.1: Infrastructure Project Management and Oversight (Paul Giannotti)

1.9.2: Detector Mechanical Systems (Jim Mills)

- 1.9.2.1: Cradle Carriage Work Package
- 1.9.2.2 : Internal Detector Structural Support Work Package
- 1.9.2.3 : End Caps/ Pole Tips Work Package
- 1.9.2.4 : Cradle Carriage Bridge, Mid Platforms And Access Work Package

***See Backup for Key
Personnel and WBS
dictionary information)***


1.9.3: Detector Support Systems (Paul Giannotti)

- 1.9.3.1: Line Electric Power Distribution Work Package
- 1.9.3.2: Detector Support Services Systems Components Work Package
- 1.9.3.3 : Detector Electronics Racks And Rack Generic Support Systems Work Package
- 1.9.3.4: Detector Gas And Cooling Services Systems
- 1.9.3.5: Detector Safety Subsystems Work Package
- 1.9.3.6: Gas Mixing House & Gas Pad Components Work Package
- 1.9.3.7: Rack Room Modifications Work Package
- 1.9.3.8: Control Room Work Package

1.9.4: Facility Support Systems (Brian Streckenbach)

- 1.9.4.1 : Magnet Cryo, Electrical & Control Structural Support In IR Work Package
- 1.9.4.2 : Beampipe/Vacuum Work Package
- 1.9.4.3 : IR HVAC Work Package
- 1.9.4.4 : IR Electronics Cooling Water Distribution System Work Package
- 1.9.3.5: IR/AH Safety Subsystems Components Work Package
- 1.9.3.6: Assembly Hall Modifications work Package

System Scope for: 1.9.2 Detector Mechanical Systems (Jim Mills)



1.9.3 Detector Support Systems

1.9.4 Facility Support Systems

System Description for:



1.9.3 (P. Giannotti)


1.9.4 (B. Streckenbach)

- 1.9.3.1 Electric Power
- 1.9.3.2 Support Services (cable trays etc.)
- 1.9.3.3 Electronics Racks
- 1.9.3.4 Detector Gas & Cooling
- 1.9.3.5 Safety Systems
- 1.9.3.6 Gas Mixing House & Gas Storage Pad
- 1.9.3.7 Rack Room Modifications
- 1.9.3.8 Control Room computers/furniture

- 1.9.4.1 Magnet Cryo & Structural Supports
- 1.9.4.2 Beampipe/Vacuum
- 1.9.4.3 IR HVAC
- 1.9.4.4 IR Electronics Cooling Water
- 1.9.4.5 IR/AH Safety Systems
- 1.9.4.6 Assembly Hall Modifications

See Backup for Details on these work packages)

Note: Assembly and Installation of these Infrastructure items is not in the scope of this WBS effort but rather in the scope of WBS 1.10 (Installation and Integration)



Infrastructure Design Drivers:

All work packages

- Safety
- Subsystem design requirements
- Cost
- Maintainability, Reliability, Accessibility
- Future upgrades/expansion

WBS 1.9.2 (Cradle, etc)

- SC Magnet (Dimensions, chimney extension)
- Outer HCal (Dimensions, weight)
- Existing shield wall opening
- Existing rail system

WBS 1.9.3 (Detector support systems)

- Available infrastructure (repurposed from PHENIX)
- Minimize footprints in detector active areas
- Maintainability

WBS 1.9.4 (Facility support systems)

- Maximize repurposing from PHENIX
- Minimize impact on detectors

Schedule Drivers/Cost Drivers

Schedule Drivers

- Design of Detector Support Cradle, Base, and Bridge
- Fabrication time and availability for installation of Detector Cradle and Base (First article for detector construction)
- Cryo. Piping Supports and Building Modifications (elevated work)
- Modify existing AC Power Distribution System
- Modify existing Safety Interlock System
- Modify existing IR HVAC units (controls only)

Cost Drivers

- Cradle carriage
- Labor
- Repurposed Infrastructure Modifications
- (Cryo is part of Magnet subsystem) (1.8)

Cost summaries from BoE's 1.9.2, 1.9.3 and 1.9.4

1.9.2.1	Cradle Carriage Work Package	\$888,358.00
1.9.2.2	Internal Detector Structural Support Work Package	\$273,890.00
1.9.2.3	End Caps/ Pole Tips Work Package	\$250,200.00
1.9.2.4	Cradle Carriage Bridge, Mid Platforms and Access Work Package	\$77,200.00
Total Procurements Cost [2017 dollars, no overhead or contingency added] for the WBS #1.9.2: Detector Mechanical Systems Control Account		\$1,489,648.00

Note: Cost savings due to use of existing facility & repurposed equipment = \$millions

Resource Summary for Integration Documentation, Technical Coordination, Installation, Tooling, Fixtures and Subsystem Installation in FTE's by Resource Category

Administrators	Scientists	Engineers	Designers	Technicians	Trades	Students
0.0	0.2	5.1	3.3	3.0	0.0	0.0


WBS #	Work Package Description	Material Cost for this Work Package
1.9.4.1	magnet Cryo, electrical & Control Structural Support in IR	\$50,000.00
1.9.4.2	Beampipe/Vacuum Work Package	\$50,000.00
1.9.4.3	IR HVAC Work Package	\$35,000.00
1.9.4.4	IR Electronics Cooling Water Components Work Package	\$65,000.00
1.9.4.5	Assembly Hall Modifications	\$32,000.00
1.9.4.6		\$10,000.00
Total Unburdened Material Cost for CA # 1.9.4 =		\$242,000.00

WBS #	Work Package Description	Material Cost for this Work Package
1.9.3.1	Line Electric Power Distribution Work Package	\$50,000.00
1.9.3.2	Detector Support Services Systems Components Work Package	\$32,000.00
1.9.3.3	Detector Electronics Racks and Rack generic support systems	\$32,000.00
1.9.3.4	Detector Gas and Cooling Services Systems	\$107,000.00
1.9.3.5	Detector Safety Subsystems Work Package	\$12,000.00
1.9.3.6	Gas Mixing House & Gas Pad Components Work Package	\$10,000.00
1.9.3.7	Rack Room Modifications Work Package	\$20,000.00
1.9.3.8	Control Room Work Package	\$50,000.00
Total Unburdened Material Cost for CA # 1.9.3 =		\$313,000.00

BoE's for Infrastructure packages can be found in [here](#)

Infrastructure Staffing

FTE Profile by Category




FTE Profile by Fiscal Year

WBS Level	Org Sort	Group	FY 17	FY 18	FY 19	FY 20	FY 21	FY 22
1.9	BNL	Purchased Services	0.00	0.00	0.00	0.02	0.00	0.00
		Scientific	0.19	0.02	0.02	0.00	0.00	0.00
		Technical	1.64	0.57	2.34	1.70	0.00	0.00
		Professional	1.73	0.84	1.05	1.58	0.19	0.00
	BNL Sum		3.56	1.43	3.41	3.30	0.19	0.00
Grand Total			3.56	1.43	3.41	3.30	0.19	0.00

Cost Profile: Infrastructure

Baseline Scenario - 1.9 Infrastructure
AY k\$'s - with Extraordinary Construction Overhead Application



Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application

Resource	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021	FY 2022	Total
Labor	692	301	701	733	50	0	2,477
Non-Labor - Materials	90	0	884	1,445	0	0	2,419
Baseline Total	782	301	1,585	2,178	50	0	4,896
Contingency (30%)	235	90	476	653	15	0	1,469
MIE Total	1017	391	2061	2831	65	0	6365


Resource	Baseline	Contingency	Total
Labor	2,477	743	3,220
Non-Labor	2,419	726	3,145
1.9 Infrastructure	4,896	1,469	6,365


Basis of Estimate: Contingency

Infrastructure

SUBSYSTEM	PERCENT OF ESTIMATES	CONTINGENCY
Engineering estimate	77	0.40
Quotes	9	0.25
Similar Experience	14	0.25
Average contingency		0.37

Quality of estimates






11

sPHENIX Infrastructure Status & Highlights

- Removal & Repurposing effort is clearing IR equipment making water piping and cable trays available for rework.
- Repurposed equipment being cataloged and stored for future use (electronics racks, heat exchangers etc.
- Cradle Carriage design has started.
- Acquiring quotes for limited amount of new electric power distribution, cooling water and safety system components (modification to existing systems only).
- Design effort Cooling water, magnet cryogenics & cooling water piping has started.

Backup



IR Power and signal trays



- Existing configuration uses heavy duty 6" wide steel galvanized tray.
- Blue and Green show upper and lower tiers.
- Upper tier is signal, lower tier is power.

Assembly Hall

Typical track services detail




Current routing of IR services

Through Sill Only (other services run via backyard and North & South Tunnels)

- 30 total 4" diameter PVC pipes (Sill Tubes)
- 377 sq. inches of available space




cooling water piping



Fed from Building 1008B (backyard)

- Electronics Cooling Water Piping remains
- Magnet Cooling Water Piping to be removed
- Cryogenic piping for magnet

Racks, rack generic requirements



Water Cooled Heat Exchangers

- Power Requirements

1. One 30A 208V AC Feeder Breaker


- Rack Safety Interlocks

1. Smoke Detection
2. Over Temp. Detection
3. Water Leak Detection




AC Line Electric Power Distribution

AC line electrical power distribution utilizes existing power distribution
Magnet power effort is being handled by super conducting magnet group



- Plan to use existing existing 4 HVAC units infrastructure
- We have done well with a periodic maintenance schedule, which has increased the systems overall reliability
- 4 condensers located outdoors on IR roof




Safety System Sample Logic

Existing Infrastructure Changes

- Trip Logic to Remain Relay Based
- PHENIX Control Room upgrade for ODH sensors and monitoring
- CAD PASS system upgrade due to use of He in IR

Emergency Shutdown Inputs



Installation L2/CAM/Key Personnel



Key Personnel:

Paul Giannotti *Principal Engineer and ES&H Coordinator, Electrical Engineer, Physics Department, BNL*

Relevant Experience

Designer of PHENIX Control Room indication and alarm system, emergency shutdown safety system, and electrical power distribution. Operations and ES&H support for all PHENIX runs 2000-2016.

Rob Pisani, Sr. Scientific Associate for sPHENIX

Relevant Experience

25 years particle detector support experience. SSC EmCal Prototype R&D(1993 Built/test), R&D PHENIX Rich Prototype, PHENIX HBD prototype, Phenix TEC detector, PHENIX Gas System Coordinator (multiple systems), PHENIX VTX/FVTX Cooling System, Deputy Manager of PHENIX Removal & Repurposing.

Steve Boose, *Electronics Engineer for sPHENIX*

Relevant Experience

25 years. Software / hardware design at BNL in support of the NASA SeaWiFS, DOE Ocean Margins Program and the PHENIX experiment at RHIC. 4 years Software / hardware design and technical support for the scientific laser industry. 10 years Electronics troubleshooting and repair in high vacuum, information systems and audio.

Rich Ruggiero, *Sr. Design Engineer for sPHENIX*

Relevant Experience

2012 - Present as sPHENIX Sr. Design Engineer. Responsible for all sPHENIX integration coordination and conceptual design. 1997-Present PHENIX Design Engineer responsible for all integration and cable routing, survey/installation, work access and detector upgrades. 1986 – 1997 BNL Designer for D0 Central Calorimeter, D0 EMCal and Coarse Hadronic sectors, Oasis proposal (predecessor to PHENIX), and various NSLS, AGS and ATLAS design projects.

Brian Streckenbach, *CAD liaison Engineer to sPHENIX*

James Mills, P.E., *Project Engineer for sPHENIX, Senior Project Engineer, Collider-Accelerator Department, BNL*


Relevant Experience

Over 37 years of Engineering and Project Management experience at Brookhaven National Laboratory. 8 years as Manager of the Modernization Project Office (2006-2014) with overall responsibility for the successful completion of a portfolio of projects in excess of \$15 million annually; 6 years as Project Engineer for conventional construction in support of facility operations at Brookhaven (2000-2006); managing projects up to \$6 million in total scope. 4 years of experience as Head of the Facility and Experimental Support Group, RHIC Project (1996-2000). Responsible for approximately \$13 million dollars of conventional construction in support of experiments at RHIC. 6 years as Project Engineer for the STAR Magnet (1990-1996), providing engineering analysis and design of the 0.5 tesla solenoidal magnet. 10 years as Project Engineer, experimental support for High Energy Physics experiments at Brookhaven National Laboratory's Alternating Gradient Synchrotron (1980-1990).

Installation Interfaces

Interface Control documents(ICD's) define and quantify the interfaces between any 2 subsystems. Interfaces include mechanical, electrical, optical, cooling, gas media, etc. For the Installation and Integration effort there are 9 such documents currently conceived. For purposes of the installation efforts, these generally refer to interfaces between the subsystems components and the tooling, fixtures, procedures and equipment required to accomplish the installation and alignment of these components..

1.1 Project Management	1.2 TPC	1.3 EMCal	1.4 HCal	1.5 Calorimeter Electronics	1.6 DAQ/ Trigger	1.7 Min Bias	1.8 SC Magnet	1.9 Infrastructure	1.10 Integration & Installation	1.11 INTT	1.12 MVTX	
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1.1 Project Management
	N/A	N/A	N/A	N/A	sP.SE-ICD-004	N/A	N/A	sP.SE-ICD-004	sP.SE-ICD-016	N/A	N/A	1.2 TPC
		N/A	sP.SE-ICD-001	sP.SE-ICD-002	sP.SE-ICD-005	N/A	N/A	sP.SE-ICD-005	sP.SE-ICD-017	N/A	N/A	1.3 EMCal
			N/A	sP.SE-ICD-003	sP.SE-ICD-006	N/A	N/A	sP.SE-ICD-006	sP.SE-ICD-018	N/A	N/A	1.4 HCal
				N/A	sP.SE-ICD-007	N/A	N/A	sP.SE-ICD-007	sP.SE-ICD-019	N/A	N/A	1.5 Calorimeter Electronics
					N/A	sP.SE-ICD-008	N/A	sP.SE-ICD-008	sP.SE-ICD-020	SE-ICD-024	sP.SE-ICD-027	1.6 DAQ/ Trigger
						N/A	N/A	sP.SE-ICD-009	sP.SE-ICD-021	N/A	N/A	1.7 Min Bias
							N/A	sP.SE-ICD-010	sP.SE-ICD-022	N/A	N/A	1.8 SC Magnet
								N/A	sP.SE-ICD-023	sP.SE-ICD-025	sP.SE-ICD-026	1.9 Infrastructure
									N/A	SE-ICD-026	sP.SE-ICD-029	1.10 Integration & Installation
										N/A	sP.SE-ICD-030	1.11 INTT
											N/A	1.12 MVTX



WBS sPHENIX MIE Project Elements	
1.1	Project Management
1.2	Time Projection Chamber
1.3	MAPS Telescope
1.4	Electromagnetic Calorimeter
1.5	Hadron Calorimeter
1.6	Calorimeter Electronics
1.7	DAQ-Trigger
1.8	Minimum Bias Trigger Detector
WBS Infrastructure & Facility Upgrade	
1.9	SC-Magnet
1.11	Installation-Integration
WBS Parallel Activities	
1.12	Intermediate Silicon Strip Tracker
1.13	Monolithic Active Pixel Sensors

The mechanical mounting, electrical, optical, cooling and gas connections that are made between adjacent detector subsystems and between detector subsystems and infrastructure/ structural support components are defined in the ICD's that are shared by each pairing of those subsystems.

WBS Dictionary entries for the 4 control accounts that comprise the Infrastructure Subsystem

Technical Scope:

WBS 1.9.1 is the Control Account for Project Management costs associated with Infrastructure Management.

Work Statement:

This Control Account encompasses the efforts of the Infrastructure level 2 manager to manage this subsystem in accordance with the BNL and DOE requirements, including collecting and analyzing management performance data for this subsystem, reporting the data as appropriate and generally assuring that this subsystem meets cost and schedule estimates, and if the subsystem management performance strays from the baseline, implementing appropriate actions to restore performance to the baseline."

Technical Scope:

WBS 1.9.2 is the Control Account for all scientific, engineering and technical staff efforts to plan and supervise all aspects of the design, fabrication and assembly of the sPHENIX infrastructure components associated with sPHENIX facility Cradle Carriage and structural support:

1. Cradle Carriage
2. Internal detector structural supports. (includes the structural support mounting and positional alignment features for the Inner HCal/EMCal, superconducting solenoid, TPC, INTT, MVTX and Min Bias detector subsystems)
3. Flux return end caps/pole tips and related mounting components
4. Upper (bridge), intermediate and lower carriage work platforms and access (stairs) on the cradle carriage

Work Statement:

The assembly of the cradle carriage and actual installation of these components and equipment will take place at the sPHENIX experiment complex at building 1008 (in the assembly hall) and is covered in the sPHENIX 1.10.2 control account. There are 4 work packages included in this control account where the actual work is defined for these items. Each work package has its own separate Basis of Estimate (BoE) document elsewhere in this workbook. These documents can be accessed from the Navigation page in this workbook. (see link below).

*WBS dictionary entries for
installation work packages
can be found in [here](#)*

WBS Dictionary entries for the 4 control accounts that comprise the Infrastructure Subsystem

Technical Scope:

WBS 1.9.3 is the Control Account for all scientific, engineering and technical staff efforts to plan and supervise all aspects of the design, fabrication and assembly of the sPHENIX infrastructure components associated with sPHENIX facility support systems, safety systems and non-IR infrastructure including the following work packages:

1. Line Electric Power Distribution
2. Detector Support Services Systems Components
3. Detector Electronics Racks and Rack generic support systems
4. Detector Gas and Cooling Services Systems
5. Detector Safety Subsystems
6. Gas Mixing House & Gas Pad Components
7. Rack Room Modifications
8. Control Room and Offices Modifications

Work Statement:

The actual installation of these components and equipment will take place at the sPHENIX experiment complex at building 1008 and is covered in the sPHENIX 1.10.2 control account. There are 8 work packages included in this control account. Each work package has its own separate Basis of Estimate (BoE) document elsewhere in this workbook. These documents can be accessed from the Navigation page in this workbook. (see link below).

*WBS dictionary entries for
installation work packages
can be found in [here](#)*

WBS Dictionary entries for the 4 control accounts that comprise the Infrastructure Subsystem

Technical Scope:

WBS 1.9.4 is the Control Account for all scientific, engineering and technical staff efforts to plan and supervise all aspects of the design, fabrication and assembly of the sPHENIX infrastructure components associated with sPHENIX facility support systems, safety systems and non-IR infrastructure including the following work packages:

1. Magnet Cryo, Electrical & Control Structural Support in IR
2. Beampipe/Vacuum
3. IR HVAC
4. IR Electronics Cooling Water Distribution System
5. IR/AH Safety Subsystems Components
6. Assembly Hall Modifications

Work Statement:

The actual installation of these components and equipment will take place at the sPHENIX experiment complex at building 1008 and is covered in the sPHENIX 1.10.2 control account. There are 6 work packages included in this control account. Each work package has its own separate Basis of Estimate (BoE) document elsewhere in this workbook. These documents can be accessed from the Navigation page in this workbook. (see link below). "

*WBS dictionary entries for
installation work packages
can be found in [here](#)*

Technical Scope:

WBS 1.9.4 is the Control Account for all scientific, engineering and technical staff efforts to plan and supervise all aspects of the design, fabrication and assembly of the sPHENIX infrastructure components associated with sPHENIX facility support systems, safety systems and non-IR infrastructure including the following work packages:

1. Magnet Cryo, Electrical & Control Structural Support in IR
2. Beampipe/Vacuum
3. IR HVAC
4. IR Electronics Cooling Water Distribution System
5. IR/AH Safety Subsystems Components
6. Assembly Hall Modifications

Work Statement:

The actual installation of these components and equipment will take place at the sPHENIX experiment complex at building 1008 and is covered in the sPHENIX 1.10.2 control account. There are 6 work packages included in this control account. Each work package has its own separate Basis of Estimate (BoE) document elsewhere in this workbook. These documents can be accessed from the Navigation page in this workbook. (see link below). "