

sPHENIX Director's Review Project Overview

Edward O'Brien


August 2-4, 2017

BNL

What is sPHENIX ?

- sPHENIX is a major upgrade to the PHENIX detector. It is a large-acceptance, high-rate detector for Heavy Ion physics that repurposes **>\$20M** in existing PHENIX equipment, infrastructure and support facilities
- The detector is optimized to measure jet and heavy quark physics by incorporating a Tracker, full EM and Hadronic calorimeter coverage at $|\eta| < 1.1$, and a **1.5 T solenoidal magnetic field.**
- It will utilize much of the infrastructure already existing in the PHENIX detector complex and the **BaBar SC-magnet.** The Min Bias Trigger Detector is the reused **PHENIX Beam Beam Counter with upgraded electronics.**
- **A bottom-up resource-loaded project plan has sPHENIX assembled, commissioned and ready to take data in January 2023 based on the DOE-ONP guidance for the Critical Decision from earlier this year.**

sPHENIX Conceptual Design



Not part of this review →

- Uniform fiducial acceptance $-1 < \eta < 1$ and $0 < \phi < 2\pi$
- Superconducting solenoid enabling high resolution tracking
- Hadronic calorimeter doubling as flux return
- Compact electromagnetic calorimeter to allowing fine segmentation at a small radius
- Solid state photodetectors that work in a magnetic field, have low cost, do not require high voltage
- Common readout electronics in the calorimeters
- High rate 15 kHz in AA allows for large unbiased MB data sample
- Utilization of existing PHENIX exp Infrastructure
- Compact TPC 250 mm hit res & continuous readout
- 4 Intermediate silicon strip tracking layers (Japanese funds)
- 3 layer – 2π MAPS-based vertex det (DOE-Upgrade)

Most Detector components are at an advanced state of R&D

The Three Parts of sPHENIX

MIE Cost range is \$29-35M

Upgrade Support is ~\$20M

Infrastructure/Facility Upgrade ~\$20M

DOE funded & Managed

BNL Funded & Managed

BNL Funded & Managed


- A. sPHENIX MIE Upgrade** covering the detector (Project Management, TPC, EMCal, HCal, Calorimeter Electronics, DAQ/Trigger, Min Bias Detector). Dominated by M&S costs. The MIE carries labor for Project Management and ~\$1M in paid University labor for building things.
- B. Upgrade Support** is 100% BNL labor that supports the sPHENIX MIE upgrade. Primarily the Phys Dept PHENIX/sPHENIX technical support group augmented by CAD, Magnet Div and Instrumentation Div.
- C. Infrastructure and Facility Upgrade** of the 1008 complex . Combination of M&S and Labor. Purpose is the upgrade of 1008 to modern standards. Enables cryo operations in 1008 and provides a facility optimized for the operation of a modern detector.

sPHENIX MIE Scope

- A Time Projection Chamber (TPC), Electromagnetic Calorimeter (EMCal), Hadronic Calorimeter (HCal), all covering 2π in azimuth and a fiducial pseudo-rapidity coverage of $-1 \leq \eta \leq 1$.
- Readout electronics to fully instrument the TPC, EMCal and HCal.
- A Data Acquisition system with the capability to readout the TPC, EMCal and HCal with an event rate and data logging rate commensurate with the sPHENIX physics goals.
- A DAQ/Trigger system that can provide minimum bias and energy cluster triggers at a rate necessary to carry out the sPHENIX physics program in AA, pA and pp at RHIC.
- A Minimum Bias Trigger Detector
- Project Management to carry the Project Scope through to a successful completion.

WBS of sPHENIX MIE & Support Effort

MIE



WBS sPHENIX MIE Project Elements

- | | |
|-----|-------------------------------|
| 1.1 | Project Management |
| 1.2 | Time Projection Chamber |
| 1.3 | Electromagnetic Calorimeter |
| 1.4 | Hadron Calorimeter |
| 1.5 | Calorimeter Electronics |
| 1.6 | DAQ-Trigger |
| 1.7 | Minimum Bias Trigger Detector |

Support Activities managed by the sPHENIX Project team

WBS Infrastructure & Facility Upgrade

- | | |
|------|--------------------------|
| 1.8 | SC-Magnet |
| 1.9 | Infrastructure |
| 1.10 | Installation-Integration |

Parallel Activities funded from other sources

WBS Parallel Activities

- | | |
|------|------------------------------------|
| 1.11 | Intermediate Silicon Strip Tracker |
| 1.12 | Monolithic Active Pixel Sensors |

sPHENIX Schedule

CD-0 Mission Need Approved	Sep 2016
BNL Director's pre CD-1 Review	Sep 2017
OPA-CD-1/CD-3a Review	Spring 2018
CD-1/CD-3a authorization (?)	Dec 2018
Fabrication (orders) of long lead time components begins	Dec 2018
All Preproduction R&D and Design complete	Spring 2019
OPA- CD-2/CD-3b review	Spring 2019
CD-2/CD-3b authorization (?)	Aug 2019
All fabrication (orders) begin	Aug 2019
sPHENIX installation begins in 1008 Facility	Apr 2021
MIE deliverables complete	Dec 2021
sPHENIX Installed, cabled, ready to commission	Jul 2022
Commissioning complete	Sep 2022
First RHIC beam for sPHENIX	Jan 2023
CD-4 Approval	Jan 2024

The MIE has 25 months of float between completion of deliverables and CD-4


The Resource-loaded Schedule contains 6 months of float to Jan 2023 first beam @ RHIC

CD-1 Documents Available to the Committee


- 1. Project Team Organization**
- 2. WBS (WBS Dictionary)**
- 3. Basis of Estimate documents**
- 4. Contingency Risk/Analysis**
- 5. Project Schedule**
- 6. Critical Milestones**
- 7. Proposed Funding Profile**
- 8. Proposed Labor Profile**
- 9. Preliminary Hazard Analysis Report**
- 10. NEPA form**
- 11. Integrated Safety Management Plan**
- 12. Conceptual Design/Conceptual Design Report-**
- 13. Acquisition Strategy**
- 14. Preliminary Project Execution Plan**
- 15. Preliminary Risk Assessment and Risk Registry**
- 16. Security Vulnerability Assessments (Equipment protection & cyber security)**
- 17. Alternate Analysis**

Project Organization

<https://docdb.sphenix.bnl.gov/0001/000104/001/sPHENIX-Bios.docx.pdf>




Project Organization




Infrastructure & Facility

MIE



L2 and CAM Structure of MIE



L2 Managers & Control Account Managers

L2 Managers:

1.1 Project Management	Irina Sourikova(BNL-Project Controls)
1.2 TPC	Tom Hemmick (SBU)
1.3 EMCal	Craig Woody (BNL)
1.4 HCal	John Lajoie (ISU)
1.5 Calorimeter Electronics	Eric Mannel (BNL)
1.6 DAQ/Trigger	Martin Purschke (BNL)
1.7 Min Bias Trigger Detector	Mickey Chiu (BNL)

Control Account Managers

Project Managmt	Irina Sourikova (BNL)
TPC Detector	Klaus Dehmelt (SBU)
GEM r1	Sasha Milov (WIS)
GEM r2	Vicki Greene (Vandblt)
GEM r3	Victor Riabov (PNPI)
TPC FEE	Takao Sakaguchi (BNL)
TPC DAM	Jin Huang (BNL)
EMC Blocks	Anne Sickles (UIUC)
EMC Module/Sector	Sean Stoll (BNL)

Inner HCal	John Lajoie (ISU)
Outer HCal	Anatoli Gordeev (BNL)
CalE SiPMs	Christine Aidala (UM)
CalE Preamps	Steve Boose (BNL)
CalE Digitizer	CY Chi (Columbia)
DAQ	Ed Desmond (BNL)
Trigger	J. Nagle(UColorado)
Timing Sys	TBD (If necessary)
MB Trig Det	Mickey Chiu (BNL)

Resource-Loaded Schedule Status

We are finishing a bottom-up revision to the Resource-loaded schedule

- 6 month effort of ~40 - 50 people.
- 1800+ activities over 11 WBS L2 categories. All in MS-Project
- The MIE Activities were integrated with the Magnet, Infrastructure, Installation/integration.
- Merged the INTT with the rest of the project files
- Consultant migrating the files to P6 in process. No review yet by L2's or CAMs. Ready for primetime early Sept

RLS and BOE Procedure:

- **BOE of Cost and Duration based on Vendor bids or quotes, catalog prices, engineering estimates or previous experience**
- **L2s/CAMs Bottom-up contingency based on uncertainty(risk) table**
- **Use BNL Labor bands, BNL Extraordinary OH rates, university rates where applicable.**
- **Non-BNL labor availability estimates came from collaborating institutions**
- **No RFP's on MIE. 1 RFP in SC-Magnet (cryo bypass)**
- **The CERN GEM order involves only vendor that doesn't take payment in \$.**
 - **No significant foreign exchange issues.**
- **Labor resources not available from BNL Phys Dept will come from CAD, Mag Div, Instrumentation Div, or collaborating Institutions**

sPHENIX BOE Contingency Guidelines









Materials Bottom-Up Contingency
Uniformly Graded Approach to Risk Across All Subsystems

There is a similar table for Labor contingency estimates

Code	Type of Estimate	Contingency %	Description
M1	Existing Purchase order	0%	Items have been completed or obligated. (Note: Contact Change Orders are considered a Risk and should not be included)
M2	Procurement for LOE/Oversight work	0%-20%	M&S items such as travel, software purchases and upgrades, computers, etc. estimated to support LOE efforts and other work activities.
M3	Advanced	10%-25%	Items for which there is a catalog price or recent vendor quote based on a completed or nearly completed design or an existing design with little or no modifications and for which the costs are documented.
M4	Preliminary	25%-40%	Items that can be readily estimated from a reasonably detailed but not completed design; items adapted from existing designs but with moderate modifications, which have documented costs from past projects. A recent vendor survey (e.g., budgetary quote, vendor RFI response) based on a preliminary design belongs here.
M5	Conceptual	40%-60%	Items with a documented conceptual level of design; items adapted from existing designs but with extensive modifications, which have documented costs from past projects.
M6	Pre-conceptual - Common work	60%-80%	Items that do not have a documented conceptual design, but do have documented costs from past projects. Use of this estimate type indicates little confidence in the estimate. Its use should be minimized when completing the final estimate.
M7	Pre-conceptual - Uncommon work	80%-100%	Items that do not have a documented conceptual design, and have no documented costs from past projects. Its use should be minimized when completing the final estimate.
M8	Beyond state of the art	> 100%	Items that do not have a documented conceptual design, and have no documented costs from past projects. Technical requirements are beyond the state of the art.


Basis of Estimate

Calorimeter Electronics Net contingency 30%



sPHENIX Critical Path Calculated in P6

sPHENIX MS-Project and P6 give the same critical path



Major Project Milestones for L2 Subsystems

WBS	Project Milestone of LEVEL-2 subsystems	Scheduled Dates
1.2.1	TPC available for installation	11/2020
1.2.2	Quad GEM Module Readiness review	6/2019
1.2.2/3/4	Quad GEM Module Production complete	6/2020
1.2.5	TPC FEE Production Readiness review	5/2019
1.2.5	TPC FEE Production complete	7/2020
1.2.6	TPC DAM Production Readiness review	6/2019
1.2.6	TPC DAM Production complete	9/2020
1.3.2	Block Production Readiness review	1/2020
1.3.3	Module and Sector Production Readiness review	8/2019
1.3.4	EMCal sectors complete, available for installation	11/2021
1.4.2	Procurement of IHCAL mechanical structure complete	4/2021
1.4.2	Procurement of IHCAL scintillating tiles complete	10/2020
1.4.2	Last sector IHCAL available for installation	6/2021
1.4.3	Procurement of OHCAL scintillating tiles complete	3/2020
1.4.3	First sector OHCAL available for installation	9/2020
1.4.3	Last sector OHCAL available for installation	4/2021
1.5.1	Optical Sensor Procurement Complete	9/2020
1.5.2	EMCAL Fee Production Complete	2/2021
1.5.2	HCAL Fee Production Complete	10/2020
1.5.3	Calorimeter Digitizer Production start	8/2019
1.5.3	Calorimeter Digitizer Production Complete	10/2020
1.6	DAQ Ready for Operation	10/2021
1.7.3	Receive Digitizers for Min Bias Det	4/2020
1.7.4	Min Bias Det available for installation	12/2020

The MIE Part of sPHENIX


CD-0 Cost range is \$29-35M

DOE Funded & Managed

- The full MIE scope exceeds the cost range by ~3.5 M AY\$ (contingency included)
- All documents including the RLS, BOEs, labor profiles etc. assume the full scope
- We have two de-scope scenarios that fall within the budget range but the detailed science impact has yet to be evaluated by the collaboration.
- The intention is to build the full scope by reducing costs through scrubbing and value engineering, while also pursuing additional funds from International and other sources. Barring that we would implement a de-scope scenarios
- The sPHENIX Project, collaboration and BNL will devise a plan to fit within CD-0 cost range well in advance of the OPA review.

sPHENIX Cost Estimate – Full Scope

Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application




Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application

WBS	SYSTEM	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021	FY 2022	Total
1.1	Project Management	280	320	320	320	305	305	1,850
1.2	TPC	323	31	1,575	675	0	0	2,604
1.3	EMCal	161	96	5665	396	380	0	6,698
1.4	HCal	15	129	2,752	8,777	313	0	11,986
1.5	Calorimeter Electronics	52	351	4,051	767	0	0	5,221
1.6	DAQ & Trigger	19	32	114	1,035	0	0	1,200
1.7	Min Bias Trigger Det	63	0	19	54	0	0	136
Baseline Total		913	959	14,496	12,024	998	305	29,695
MIE Contingency		274	288	4,349	3,607	299	92	8,909
MIE Total		1187	1247	18845	15631	1297	397	38604

WBS	SYSTEM	Baseline	Contingency	Total
1.1	Project Management	1,850	555	2,405
1.2	TPC	2,604	781	3,385
1.3	EMCal	6,698	2009	8,707
1.4	HCal	11,986	3596	15,582
1.5	Calorimeter Electronics	5,221	1566	6,787
1.6	DAQ & Trigger	1,200	360	1,560
1.7	Min Bias Trigger Det	136	41	177
MIE Totals		29,695	8909	38,604

sPHENIX Descope Scenario -1, 50% EMCal

Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application




Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application

WBS	SYSTEM	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021	FY 2022	Total
1.1	Project Management	280	320	320	320	305	305	1,850
1.2	TPC	323	31	1,575	675	0	0	2,604
1.3	EMCal	161	96	2832.5	198	190	0	3,478
1.4	HCal	15	129	2,752	8,777	313	0	11,986
1.5	Calorimeter Electronics	52	351	2,431	460	0	0	3,294
1.6	DAQ & Trigger	19	32	114	1,035	0	0	1,200
1.7	Min Bias Trigger Det	63	0	19	54	0	0	136
Baseline Total		913	959	10,043	11,519	808	305	24,547
MIE Contingency		274	288	3,013	3,456	242	92	7,364
MIE Total		1187	1247	13056	14975	1050	397	31911

WBS	SYSTEM	Baseline	Contingency	Total
1.1	Project Management	1,850	555	2,405
1.2	TPC	2,604	781	3,385
1.3	EMCal	3,478	1043	4,521
1.4	HCal	11,986	3596	15,582
1.5	Calorimeter Electronics	3,294	988	4,282
1.6	DAQ & Trigger	1,200	360	1,560
1.7	Min Bias Trigger Det	136	41	177
MIE Totals		24,547	7364	31,911

sPHENIX Descope Scenario -2, No IHCal, 85% EMCal

Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application



Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application

WBS	SYSTEM	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021	FY 2022	Total
1.1	Project Management	280	320	320	320	305	305	1,850
1.2	TPC	323	31	1,575	675	0	0	2,604
1.3	EMCal	161	96	4,815	337	323	0	5,732
1.4	HCal	15	129	2,752	5,427	313	0	8,636
1.5	Calorimeter Electronics	52	351	3,160	598	0	0	4,161
1.6	DAQ & Trigger	19	32	114	1,035	0	0	1,200
1.7	Min Bias Trigger Det	63	0	19	54	0	0	136
Baseline Total		913	959	12,755	8,446	941	305	24,319
MIE Contingency		274	288	3,827	2,534	282	92	7,296
MIE Total		1,187	1,247	16,582	10,980	1,223	397	31,615

WBS	SYSTEM	Baseline	Contingency	Total
1.1	Project Management	1,850	555	2,405
1.2	TPC	2,604	781	3,385
1.3	EMCal	5,732	1,720	7,451
1.4	HCal	8,636	2,591	11,227
1.5	Calorimeter Electronics	4,161	1,248	5,409
1.6	DAQ & Trigger	1,200	360	1,560
1.7	Min Bias Trigger Det	136	41	177
MIE Totals		24,319	7,296	31,615

Impacts of the De-scope Scenarios

- Building $\frac{1}{2}$ the EMCal will reduce our acceptance for Upsilon's by almost a factor of four. In addition we lose γ +jet statistics, direct γ statistics and our ability to look at jets over a full range of R values due to the restrictions on the acceptance. The other physics capabilities of the detector are preserved.
- Building No IHCAL will reduce our e/h separation due to leakage out the back of the EMCal which in turn creates a bigger combinatorics background for the Upsilon through hadron misidentification as an electron.
- The collaboration has agreed to study the physics impact of these issues in detail and recommend a de-scope option. In the mean time institutions involved with the EMCal (UIUC+UM) and IHCAL (ISU&WSU) are investigating the possibility of an NSF MRI proposal or proposals to fund components of these subsystems. Initial talks with Garcia-Solis and Opper of NSF were promising but incipient.
- International funding is being pursued with IHEP-Protvino as a possible contributor to the IHCAL. Other endeavors such as Saclay contributing to the TPC would free up funds that could be directed to restore parts of our de-scoped subsystems. Recent discussions with new potential Chinese collaborators for work on the EMCal also show the promise of resulting in an in-kind contribution to sPHENIX.

Long Lead-Time Items for Letter or Authorization or CD-3a

Two options for Long Lead procurements: Letter of Authorization from the Project Management Executive (J. Gillo), or CD-3a authorization.

SiPMs for EMCal and HCal	\$1.0M
Outer HCal Steel	\$5.3M
Scintillating Tiles for HCal	\$1.8M
Scintillating Fibers for EMCal (1/2 order)	\$0.7M

Each items has a long production time, long queue time or both. All are for detectors on or near the critical path.

Procure of those long-lead “items” through authorization from the PME in advance of CD-2 would be carried out via a tailoring strategy (Letter of Authorization)


Justification:

1. Reduce overall project risk
2. Materials will be needed regardless of . . .
3. Contract option already in placed to be executed with excellent price
4. Reduce project schedule
5. Reduce overall cost to project (estimated to be . . .)

Labor Supporting for sPHENIX MIE



WBS 1.1 through 1.7



No FTE contingency shown in plots or spreadsheet

FTE Profile


WBS Level	Group	FY 17	FY 18	FY 19	FY 20	FY 21	FY 22
BNL	Purchased Services	0.00	0.00	0.18	0.48	0.12	0.00
	Scientific	2.65	3.65	2.40	4.02	2.79	0.32
	Technical	4.70	2.15	2.40	10.79	5.47	0.11
	Professional	6.10	6.03	4.38	8.73	6.23	0.55
	Administrative	0.40	0.59	0.59	0.59	0.57	0.09
BNL Sum		13.84	12.41	9.96	24.61	15.18	1.08
Non-BNL	Scientific	2.24	1.12	1.21	3.68	0.20	0.00
	Student	1.96	3.29	6.05	36.16	19.43	0.27
	Technical	1.80	1.28	0.56	6.01	3.42	0.00
	Professional	0.15	0.23	0.46	0.71	0.10	0.00
	Postdoc	0.00	0.00	0.82	1.46	1.61	0.00
Non-BNL Sum		6.15	5.93	9.10	48.01	24.75	0.27
Grand Total		20.00	18.34	19.06	72.63	39.94	1.34

- The student contribution is commensurate with past student contributions from the same institutions on similar detector projects
- We will secure the non-BNL labor contributions with Memoranda of Agreement between Institutions.

Labor Supporting MIE+Infra/Facility Upgrade +INTT

WBS 1.1 – 1.11

FTE Profile by Category



FTE Profile by Fiscal Year

WBS Level	Group	FY 17	FY 18	FY 19	FY 20	FY 21	FY 22
BNL	Purchased Services	0.05	0.22	0.26	1.04	0.37	1.47
	Scientific	3.29	4.39	3.03	4.64	3.21	1.94
	Technical	8.35	4.59	5.28	14.71	6.93	5.58
	Professional	11.64	9.12	6.62	12.75	7.20	1.94
	Administrative	0.40	0.59	0.59	0.59	0.57	0.09
BNL Sum		23.73	18.90	15.78	33.73	18.29	11.02
Non-BNL	Scientific	2.31	1.13	1.21	3.68	0.20	0.00
	Student	1.96	3.29	6.05	36.16	19.43	6.27
	Technical	1.80	1.28	0.56	6.01	3.42	0.00
	Professional	0.15	0.23	0.46	0.71	0.10	0.00
	Postdoc	0.00	0.00	0.82	1.46	1.61	0.00
Non-BNL Sum		6.23	5.94	9.10	48.01	24.75	6.27
Grand Total		29.95	24.84	24.88	81.75	43.04	17.29

No FTE contingency shown in plots or spreadsheet

Proposed Key Performance Parameters

Installation is NOT part of the MIE and not a deliverable. Beam collisions are not needed to satisfy the KPP's.

Preliminary KPP's listed in the PPEP. They are under Discussion with DOE-ONP

System	Demonstration or Measurement	Preliminary KPP's
Time Projection Chamber	Preinstall Bench Test	$\geq 90\%$ live chns based on laser, pulser, cosmics
Time Projection Chamber	Preinstall Bench Test	Ion Back Flow $\leq 2\%$ per QuadGEM Module
Time Projection Chamber	Preinstall Test w/ cosmics	$\geq 90\%$ single hit efficiency / mip track
Time Projection Chbr FEE	Preinstall Bench Test	Cross talk $\leq 2\%$ ea chn
EM Calorimeter	Preinstall Bench Test	$\geq 90\%$ live channels based on LED, cosmics
Hadronic Calorimeter	Preinstall Bench Test	$\geq 90\%$ live chns based on LED, cosmics
EM Calorimeter	Preinstall Bench Test	Ea sector with an absolute energy pre-calibration to a precision of $\leq 35\%$ RMS
Hadronic Calorimeter	Preinstall Bench Test	Ea sector with an absolute energy pre-calibration to a precision of $\leq 20\%$ RMS
Min Bias Trigger Detector	Preinstall Bench Test	$\geq 90\%$ live channels based on laser. 120 ps/ch timing resolution w/ Bench Test
DAQ/Trigger	Event rate	10 kHz with random pulser
DAQ/Trigger	Data Logging rate	10 GBit/s with pulser

Oversight and Project Meetings

Oversight

- Biweekly sPHENIX meeting with DOE BHSO
- Monthly sPHENIX meeting with DOE-ONP
- Monthly PHENIX R&R(decommissioning) meeting with DOE-ONP
- Biweekly meeting with BNL ALD's Project Management Group
- 8 internal BNL reviews of the subsystems
- 2 BNL Director's reviews with external committees.

Project Meetings

- Weekly Management meeting
- Weekly simulations meeting
- Biweekly meetings for each MIE subsystems
- Biweekly meetings for SC-magnet
- Biweekly sPHENIX engineering meeting
- Biweekly Tracking meeting
- Biweekly L2 Managers meeting

In addition there is a biweekly General Meeting for the whole collaboration at which the Project reports and a biannual Collaboration meeting.

We've held 900 sPHENIX meetings over the last 3 years. It is a very active collaboration.

Summary


- sPHENIX is a major upgrade to the PHENIX experiment that will utilize >\$20M in existing equipment. The sPHENIX scientific collaboration is a new organization that was formed 1.5 years ago.
- The sPHENIX Project team is established and has been working together for 3 years.
 - **The Project Organization including L2's and CAMs is established.**
- We have releases or advanced draft of the documents required for CD-1 including a CDR(300 pages, 200 figures) and a preliminary PEP.
 - **They are available on the review web site.**
- There is a newly revised Resource-loaded schedule with a bottom-up cost and contingency estimate.
 - **We are migrating the RLS schedule in MS-Project to P6. The L2 Managers and CAMs have yet to review the new P6 implementation.**
 - **Bottom-up cost estimate exceeds BNL guidance. We've established two "straw man" technical de-scope scenarios that fit within budget guidance. We are working with the collaboration and BNL to assess the physics impact of those scenarios.**
- Project schedule exists that has the MIE Project complete by Dec 2021. The fully installed and commissioned detector in ready for RHIC collisions Jan 2023 with 8 months float.
 - **The FY18 President's Budget required DOE to delay sPHENIX 1 year**
 - **The Project team will pursue an aggressive R&D and conceptual design effort during the next 12-15 months prior to the CD-1 start.**

Back Up

sPHENIX Upgrade Support Labor



Technical Upgrade Support Labor Cost
AY k\$'s - with Extraordinary Construction Overhead Application



Baseline Scenario
AY k\$'s - with Extraordinary Construction Overhead Application

WBS	SYSTEM	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021	FY 2022	Total
1.1	Project Management	481	716	761	802	820	139	3,719
1.2	TPC	894	252	287	1,162	29		2,624
1.3	EMCal	375	505	7	985	1489	46	3,407
1.4	HCal	367	259	392	813	316		2,147
1.5	Calorimeter Electronics	235	152	217	576	32		1,212
1.6	DAQ & Trigger	170	231	123	704	351		1,579
1.7	Min Bias Trigger Det	58	25	3	38	5		129
Baseline Total		2,580	2,140	1,790	5,080	3,042	185	14,817
MIE Contingency		774	642	537	1,524	913	56	4,445
MIE Total		3354	2782	2327	6604	3955	241	19262


WBS	SYSTEM	Baseline	Contingency	Total
1.1	Project Management	3,719	1116	4,835
1.2	TPC	2,624	787	3,411
1.3	EMCal	3,407	1022	4,429
1.4	HCal	2,147	644	2,791
1.5	Calorimeter Electronics	1,212	364	1,576
1.6	DAQ & Trigger	1,579	474	2,053
1.7	Min Bias Trigger Det	129	39	168
MIE Totals		14,817	4445	19,262

**30% Labor contingency included
In budget**

Funding Split M&S and Labor

Capital Project Scope


sPHENIX - Major Item of Equipment (MIE)




38.6 AY M\$ w/Contingency
32 AY M\$ w/ Contingency after descope

RHIC Operations Scope

Upgrade Support



Infrastructure & Facility Upgrade



Risk Matrix

Table 3: Impact Assessment Matrix for Project-Level Global Risks

Impact Risk Area	Low	Moderate	High
Cost:	≤ \$250K	≤ \$500K	> \$500K
Schedule:	Delays Level 2 milestone or Project critical path by ≤ 3 months	Delays Level 2 milestone or Project critical path by ≤ 6 months	Delays Level 2 milestone or Project critical path by > 6 months
Scope/Technical:	Negligible, if any, degradation.	Significant technical/scope degradation.	Baseline scope or performance requirements will not be achieved.

Uniformly Applied Graded Approach to Risk Across All Subsystems

Table 6: Risk Classification Matrix

Probability	Impact		
	Low	Moderate	High
High (probability > 75%)	Moderate	High	High
Moderate (25% < probability < 75%)	Low	Moderate	High
Low (probability < 25%)	Low	Low	Moderate

sPHENIX BOE Contingency Guidelines

Labor Bottom-Up Contingency - Uniformly Graded Approach to Risk Across All Subsystems

	Type of Estimate	Contingency %	Description
L1	Actual	0%	Actual costs incurred on activities completed to date.
L2	Level of Effort Tasks	0%-20%	Support type activities that must be done to support other work activities or the entire project effort, where estimated effort is based on the duration of the activities it is supporting.
L3	Advanced	10%-25%	Based on experience with documented identical or nearly identical work. Development of activities, resource requirements, and schedule constraints are highly mature. Technical requirements are very straightforward to achieve.
L4	Preliminary	25%-40%	Based on direct experience with similar work. Development of activities, resource requirements, and schedule constraints are defined as preliminary (beyond conceptual) design level. Technical requirements are achievable and with some precedent.
L5	Conceptual	40%-60%	Based on expert judgment using some experience as a reference. Development of activities, resource requirements, and schedule constraints are defined at a conceptual level. Technical requirements are moderately challenging.
L6	Pre-conceptual	60%-80%	Based on expert judgment without similar experience. Development of activities, resource requirements, and schedule constraints are defined at a pre-conceptual level. Technical requirements are moderately challenging.
L7	Rough Estimate	80%-100%	Based on expert judgment without similar experience. Development of activities, resource requirements, and schedule constraints is largely incomplete. Technical requirements are challenging.
L8	Beyond state of the art	> 100%	No experience available for reference. Activities, resource requirements, and schedule constraints are completely undeveloped. Technical requirements are beyond state of the art.

1.2 TPC: Mechanical design is advanced. In 1st round of prototyping but we're building on ALICE, STAR and EIC R&D work. Full scale prototype with limited readout, ready fall 2017.

Two electronics boards needed FEE and DAM. Both based on existing boards.

1st prototype FEE produced & being tested in BNL Instrumentation. Similar to both ALICE & STAR boards.

DAM will be ATLAS FELIX board w/ new firmware. Testing in BNL Instrumentation has started with FELIX 1.5

1.3 EMCal: 2nd round of prototyping complete. Test beam analysis ongoing but initial results show that we are going to meet performance spec. Needs 1 more round of small prototype plus preproduction.

1.4 HCal: Advanced. 2ND round of prototyping complete. Meets performance specs. Detector design complete. Full size mech prototype for IHCal exists. Full size prototype for OHCal complete at vendor in 2 weeks. Working on installation plans.

1.5 Calorimeter Electronics: Advanced. Hamamatsu SiPM chosen. Preamp design done except for optimization of form factor(board size and shape). Digitizer board done. Working on back plane and crate controller. Nine months from ready to start production.

1.6 DAQ/Trigger: Costed upgrade commercial equipment for existing DAQ. Trigger simulations to identify rejection requirements.

1.7 Min Bias Detector: Reuse of existing PHENIX Detector.


1.8 Magnet: Exists. Former BaBar magnet passed cold low-field test. Full-field test Sept 2017. Conceptual design exists for cryo, PS, controls.

1.9 Infrastructure: Early planning stages.

1.10 Integration & Installation: Conceptual design exists for outer detector. Engineering work started for inner detectors: TPC, INTT, MVTX, Min Bias Det.

1.11 Intermediate Tracker: First round of prototyping with Si strip ladder produced and being tested at BNL.

sPHENIX Critical Path EMCal through Installation



sPHENIX Extraordinary Project Rates



sPHENIX Upgrade and Support Projects
Composite Rates - Assumes Cost Accounts are under "DB" - NPP Directorate

Row Labels	Category	Description	EPR Rate	
			TMC FY 17 - FY18	VAB FY 19 - on
Low value material	300	PO Purchases	0.28	0.12
Travel	280	Foreign Travel	0.28	0.33
Capital Equipment	425	HI Value - Laboratory	0.11	0.12
High Value > 25k	216	R&D Sub- Contract	0.17	0.12
	190	Contract Labor	0.19	0.23
Salary	50	Labor	0.22	0.25

EPR - Extraordinary Project Rate
 TMC- Total Modified Cost
 VAB – Value Added Base

Major sPHENIX Procurements in FY19-FY21

Item

- OHCAL steel **\$5.3M**
- EMCAL W-powder **\$2.2M**
- EMCAL scint fibers **2X\$0.7M**
- CAL digitizing elec. **\$1.9M**
- CAL front end elec **\$0.4M**
- HCAL scint tiles **\$1.8M**
- TPC Fee board **\$0.7M**
- TPC DAM board **\$0.3M**
- SiPMs **\$1.0M**
- EMCAL blocks **\$0.8M**
- IHCAL assembly **2X\$150k**
- IHCAL stainless steel **\$1.5M**
- Magnet cryo system **\$1.1M**
- Detector Carriage **\$0.9M**

Aspects of Contract

- Competitive bid
- Sole source vendor?
- Only 2 known vendors
- Contract w/ Columbia Univ
- BNL order, 1st article + balance
- Russian vendor, would like sole source
- BNL order, 1st article + balance
- BNL order, 1st article + balance
- Japanese vendor. Catalog purchase
- Contract with Univ of Illinois
- Contract with Iowa St + Wayne St
- Competitive bid
- Vendor RFP
- Competitive bid

Total ~ \$20M