

First Look of the Beam Test at CERN PS T9 in Aug 2026


experimental setup and lessons learned

26.9.15 BIC ESB/System Testing Meeting


Jeongsu Bok

What we have done so far


KEK in May 2026:
preparation for
CERN PS



Detector Setup






Ancillary Detectors



Cherenkov counter (one of two)
Scintillator for beam monitoring
are equipped along the beam line


Detector Setup: Pb/SciFi



→ Bulk with SiPM+LG
(Previously bundled and
PMT)



Pb/SciFi Setup

- 1) bulk: 3x6 array of 32x3x3cm unit module: 32x9x18cm
- 2) Added SFILs
 - Added one then, electron calibration
 - Added one more, electron/muon calibration
 - Different LG length between , matching trapezoidal SFIL length for a sector.
- 3) Added SFILs without readout for checking shower response for each channel
- 4) Similar beam setup for two type of DAQs
 - FADC and H2GCROC




DAQ setup (Jongwon)

- Tested timestamp matching between H2GCROC timestamp and FADC in Korea (NOTICE Korea, 1 μ s coarse&8ns fine timestamp)
- So, Cherenkov will be available for H2GCROC data, as well as we collected electron-enriched data.




Matching events successfully based on timestamp difference with 10 ns. (NK: 20304, H2GCROC: 20312, Matched: 20301)



Prompt analysis for 3GeV electron (Notice Korea DAQ)


e- 3GeV Bulk Calibration & Compare IntADC

BIC Data IntADC/Simulation Edep by each Channel (2nd Row)



mu- 3GeV Bulk Calibration & Compare IntADC


BIC Data IntADC/Simulation Edep by each Channel (2nd Row) – Run # 765




e- 3GeV SFIL Calibration & Compare IntADC

BIC Data IntADC/Simulation Edep by each Channel

SFIL 7



SFIL 6



we had 3 bad channels at that time, we moved it to make 3x5 in one side

- 1) Bulk: looks OK for electrons. Muons should be checked with fine binning
- 2) SFIL: some channels do not seem to be good even in electrons. But we need to check more.
- 3) Anyway, this is Prompt analysis during the beam test to check the detectors were OK

Issues during the beam test - internal :)



- Overall, we were OK at KEK in May, but we faced issues when
 - the number of channels are increased (4→86)
 - and for new detector setup (SFILs)
- Optical coupling issue in SFIL: As usual in new setup
 - 3x6 bulk looked OK, but we found issues in SFILs, so we had to test only two SFILs within the beam time
 - Some channels in SFIL seems to be bad after fixing mechanical coupling, but we need investigation.
 - We will find a solution to secure optical coupling.
- FEE/cable issue:
 - As usual in new setup
 - it turned out that the boards are OK, it was a matter of debugging during the experiment. We lost some channels, but we could do experiment.
- More preparation may prevent some issues, but we learned from the experience and we have to-do-list in our hands. We expect smooth operation for the next beam test.

Concern for the next beam test (Pb/SciFi)

- Muon beam is not available
- Calibration for different LG coverage
 - Slightly different height may prevent good electron calibration
 - We will check the data to quantify the effect.
- Ensure optical coupling: We are collecting idea, we would appreciate any idea or advice.
- Plan for the next beam test
 - not confirmed yet, but we will begin discussion.
- KEK Application status
 - For Oct-Dec 2026 period: Applied, but we did not receive result yet.
 - We can apply Feb-Mar and May-June 2027

AstroPix 9-chip by Jinhyun and Sanghooon


- Data taken with following detector configuration (Stand-alone data taking, [Run log](#))
 - ☒ Beam injection to each sensor - Muon 5 GeV, Mixed 3 GeV
 - ☒ Beam injection to APIX module with 1 SFIL - Muon 5 GeV, Mixed 3 GeV
 - ☒ Beam injection to APIX module with 2 SFIL - Mixed 2/3/4/5/6/7/8/10 GeV(+ collimator scan), Electron 0.2/0.3/0.4 GeV
 - ☐ Beam injection to APIX module with 3 SFIL
 - ☐ Beam injection to APIX module with 4 SFIL
 - ☐ Beam injection to APIX module with 5 SFIL




APIX module
installed between
bulk and SFIL

- Slide from Jinhyun, we investigated effect by increasing hit rate
- We checked column-row matching probability for 9 chips under beam condition

Beam Profile: Delay Wire Chamber



- Electron beam
- Trigger overlapping region is expected to be about 15mm x 10 mm
- DWC data shows that ~20mm x 10mm
- We will study with cuts for beam position and angle




2024 Trg 1cmx1cm

Backup: AstroPix by Jinhyun

Brief summary



column-row matching probability





- Beam injection to center of module without any SFIL
- Matching efficiency among chips showed consistency (w/o chip 0)

! Since ToT value for specific chips(2, 5, 8) showed abnormal distribution, ToT condition wasn't used for hit matching


- During preparation, abnormal behavior of ToT distribution shown randomly → Need to be investigated in the future




Brief summary (Collimator scan - Mixed 3 GeV)




Collimator: 1.5 mm



Collimator: 14.0 mm



Collimator: 8 mm



Collimator: 20.0 mm