

AE68: Ramped Beam Generation Using Dielectric Wakefield Structures

PI: G. Andonian

Collaborators: S. Barber (LBNL), F. O'Shea, M. Harrison
(Radiabeam), N. Sudar, J. Rosenzweig, O. Williams (UCLA)
M. Babzien, M. Fedurin, K. Kusche, R. Malone, C. Swinson, BNL
(ATF)



Funding source: DOE SBIR Award # DE-SC0011271 + internal funds
committed for future runs

Status: * Awaiting final technical report


2019 ATF Users Meeting: Application for
Continuation

Scientific Case

- Efficiency of DWA: Transformer Ratio
- TR enhancement from ramped beams
 - Triangle distribution, etc.
- Techniques:
 - EEX, laser shaping, masking
 - Recent paper from AWA
- Shaping with self wakes
 - Analogous to bunch train with DWA
 - No charge loss at mask




Experimental Setup



- Second stage: TR measurement
 - Split beam into drive/witness pair
 - Observe energy shift of d/w at spectrometer
 - Alternate: use DWS upstream,
 - Then chicane + DWA


DWS+ DWA ($f=1.1$ THz) ($TR \sim 5$)



Progress:



First run: only shaping structure + chicane
CTR interferometry demonstrates beam shaping

G. Andonian, et al., PRL 118, 054802 (2017)




- Second run: first time deflector powered for e-beam use
- Compare CTR results to streaker


- Compression
- Asymmetry
- Good qualitative agreement w/ CTR results




Progress






Drive/witness + TCAV (2018 run)



Unperturbed beam



Sample images after structure + chicane



Simulations:
1) No structure
2) Structure

Plans

- Previous run results
 - Demonstrated ramped beam using CTR reconstruction
 - First deflector run showed good qualitative agreement
 - Second run with d/w beam showed ramped
- Next run
 - Send through second DWA to measure TR
 - Full LPS with dipole and TR
 - Characterize TCAV with slits for improved resolution
- Request for time
 - ~1-2 week for beamline setup + e-beam only run
 - Aligning structures - challenge
- Experimental requirements:
 - Need masking
 - Need complete deflector calibration
 - Dipole spectrometer for LPS
 - Bolometer/interferometer as backup?

Electron Beam Requirements

Parameter	Nominal	Requested Experiment Parameters
Beam Energy (MeV)	50-65	<i>50MeV</i>
Bunch Charge (nC)	0.1-0.5	<i>0.3nC</i>
Compression	Down to 100 fs (up to 1 kA peak current)	<i>No</i>
Transverse size at IP (sigma, μm)	30 – 100 (dependent on IP position)	<i>30μm round at IP, 30-40μm round at 2nd IP</i>
Normalized Emittance (μm)	1 (at 0.3 nC)	<i>1 mm-mrad</i>
Rep. Rate (Hz)	1.5	<i>1.5</i>
Trains mode	Single bunch	<i>Single bunch</i>

Special Equipment: TCAV, Mask, bolometer/interferometr

CO₂ Laser Requirements –NONE e-beam only

The following options are available at the laser source. Note that the maximum power available at your experiment interaction point will depend on the laser transport method.

OPTION 1 (full power, ~1 shot per minute)

regular gas in final amplifier (winter-spring 2018)

1 TW max (3.5 ps, 5 J, 30% of energy in post-pulses)

10.25 μm

$M^2 \sim 2$

linear polarization

isotopic final amplifier (may be available late 2018)

2 TW max (2 ps, 4 J, single pulse)

9.25 μm

$M^2 \sim 2$

linear polarization

OPTION 2 (regen only, 1.5 or 3 Hz)

3 GW max (2 ps, 6 mJ)

9.25 μm

$M^2 \sim 1.5$

linear polarization (circular available at slightly reduced power)

Interaction Point location: Laser room/ electron experiment hall - *delete as necessary*

2019 Experiment Time Estimates

Run Hours (include setup time in hours estimate):120hrs

Number of electron beam only hours: 80hrs

Number of CO₂ laser hours delivered to laser experiment hall ("FEL room"): 0

Number of CO₂ laser hours, + ebeam, delivered to electron beam experiment hall: 0

Overall % setup time: 50%

Hazards & installation requirements:

Large installation (chamber, insertion device etc...): Y (large chamber to house chicane)

Laser use (other than CO₂): Y (Local HeNe)

Cryogenics: Maybe (Helium for bolometer)

Introducing new magnetic elements: Y (mini-chicane)

Introducing new materials into the beam path: Y (dielectric structure)

Any other foreseeable beam line modifications: Y (BL2)