DUNE 35t Activity at BNL Status

B. Kirby- June 17, 2015 - BNL DUNE Local Meeting

The DUNE 35t Detector

- BNL responsible for testing DUNE 35t electronics, support installation and commissioning
 - Test board functionality at cryogenic temperature, measure performance
 - Work with instrumentation division to validate FEMBs and firmware
 - Develop calibration procedures
 - Integrate FEMB readout into 35t DAQ
 - Participate in electronics installation and commissioning
 - Contribute to electronics simulation in 35t code
- Current activity focused on board validation, DAQ integration
 - Delay in delivery board to Fermilab due to underestimate integration effort
 - Recent progress in DAQ integration, regular data-taking starting

Reminder - 35t FEMBs

- 35t Front End Mother Boards (FEMBs) contain analog, FPGA and ERNI interface boards
 - Full details in DocDb 10858, H. Chen
 - Analog board: 8 FE ASICs + digitizing ADC ASICs, 128 channels
 - FPGA board: Coordinates ASIC readout, streams data to backend
 - ERNI connector board: 4 GB transceiver cables connector board
 - 128:4 multiplexing

Front End Mezzanine Board (FEMB)




FPGA Board

Analog Board

Reminder - 35t DAQ

- Ongoing Fermilab VST is a full end-to-end test of electronics chain
- FEMBs integrated into DAQ, configuration and data streaming works



FE configuration & control done over same high-speed connections as signal, with dedicated I2C links as a backup

M. Graham, DocDB 10889

35t Production Board Validation Procedure


- 19 analog boards and 20 FPGA boards produced for 35t test
 - 16 required for full detector
- Extensive tests of FEMBs at room temperature and liquid nitrogen have been performed
- FEMBs validated in sequential tests:
 - On-board oscillator cryogenic screening prior to assembly
 - Post-assembly room temperature functionality test
 - Cryogenic functionality and performance validation
 - Final validation data-taking after cryogenic testing

Pre-Assembly On-board Oscillator Cryogenic Screening



Pre-screen off-the-shelf on-board oscillators for correct output frequency in liquid nitrogen before assembled on production FEMBs

Reduce ambiguity in subsequent test stages



Cryogenic Testing Status


- Require minimum of 16 FEMBs (FPGA + analog boards) for 35t
- All FEMBs pass room temperature functionality tests
- Currently 14 FEMBs pass cryogenic testing
 - 16 out of 20 FPGA boards pass as of June 17
 - 14 out of 18 analog boards pass as of June 17
 - 4 analog boards have at least 1 ASIC with decreased performance in LN2, replacing ASIC generally resolves this
- General comments on cryogenic testing to date:
 - 49 cryogenic tests performed (original plan was 1 test for each board)
 - 15 FE ASICs replaced, 2 ADC ASICs


Final Validation

- After board passes cryogenic testing, perform a set of validation data runs
- Measure baseline, noise, gain for every FEMB channel on multiple FE-ASIC configurations
- Check for board damage from cryogenic testing

Calibration constants measured for multiple FE-ASIC configurations
Significant amount of validation and calibration data recorded

No damage detected to date






DAQ Integration



RCE ADC Mean "histl" none



- 4 validated FEMBs installed on APA at Fermilab, integrated into 35t DAQ
- A few integration issues were discovered and resolved
 - Highlighted the need to establish integration test stand at BNL
- Regular data-taking underway, calibration pulser tests starting imminently

Summary

- 35t FEMB validation nearly complete, installation underway
 - Final boards will be shipped to Fermilab by next week
- Full readout chain being tested at Fermilab
 - FEMB readout successfully integrated into 35t readout
 - Moving into APA pre-installation "check-out" imminently, will try to install as quickly as possible
 - BNL group responsible for several commissioning tasks and in-situ calibration, support and debug FEMB readout
- Many lessons learned from FEMB validation, compiling into a report
 - Extensive validation process provides confidence that validated FEMBs will work correctly in 35t detector