



WBS 6.5: Muon Phase II Upgrade

Tom Schwarz
University of Michigan



US ATLAS Phase II Managers Meeting
April 1st, 2015

Phase II Muon Upgrade in Brief

Baseline trigger requirements for Phase-II

- ➔ L0 trigger accept rate up to 1 MHz within 6 μ s latency
- ➔ L1 trigger accept rate up to 400 kHz within 30 μ s latency
- ➔ MDT data integrated into L1 trigger to sharpen muon p_T trigger

Requires the replacement of the front-end electronics for the MDT system





Figure 2: An open chamber of monitored drift tubes (MDT) after assembly.




Phase II Muon Upgrade in Brief

Mezzanine Card


- ➔ Consists of an ADC and TDC which performs sampling, time-stamping, and buffering of candidate Level 1 hits

Chamber Service Module (CSM)

- ➔ Routes Level-I accepted hits to readout at USA15
- ➔ Passes timing information to the TDC for time-stamping
- ➔ Handles control and monitoring



Functional Diagram of current MDT readout system




Phase II Muon Upgrade in Brief

Two requirements most affecting design

- ➔ L0 trigger accept rate up to 1 MHz within 6 μ s latency
- ➔ MDT data integrated into L1 trigger to sharpen muon p_T trigger

Possible Design:




Phase II Muon Upgrade in Brief

Two requirements most affecting design

- ➔ L0 trigger accept rate up to 1 MHz within 6 μ s latency
- ➔ MDT data integrated into L1 trigger to sharpen muon p_T trigger


Possible Design:



Full resolution hits to USA 15
(Trigger Processing) in time
to be used for Level 1 \rightarrow 6 μ s

US Deliverables for Phase II in Muons

US Muons are late to the game, and so there's a great deal of uncertainty on what the FULL contribution will be - Below are possibilities



US Deliverables for Phase II in Muons

Deliverable

CSM Design/Construction


TDC Design/Construction

ASD Design/Construction

Mezzanine Design and Assembly

Motherboard/Cabling

FPGA to match hits for for Level 1 Trigger (@USA 15)






US Deliverables for Phase II in Muons


Deliverable	WBS #	US Institutions	Non-US	Funded US R&D	Construction Costs
CSM Design/Construction	6.5.1	Michigan		Yes	
TDC Design/Construction	6.5.2	BNL	CERN	sort of...	
ASD Design/Construction	6.5.3	BNL	MPI	sort of...	
Mezzanine Design and Assembly	6.5.4				
Motherboard/Cabling	6.5.5	Michigan? <i>I hope not...</i>		Yes	
FPGA to match hits for for Level 1 Trigger (@USA 15)	6.5.6		Japan?		

US Interests and Costs is current focus



CSM Construction Costs

- Starting point is a baseline Phase II design, including new FPGA and replacing some previous electronics with the GBT system of chips
- Assuming similar construction costs to the current ATLAS CSMs, accounting for new components, inflation, and exchange rates.
- Current CSM Construction costs taken from the 2003 ATLAS AGREEMENT 201-05 “*Production of CSM electronics for the ATLAS Muons Detector*”
- New Components, such as the GBT chips, are taken either from recent listed costs or from estimates of the developer/manufacturer (CERN for GBT)
- Fabrication, assembly and shipping costs per board for Phase II estimated from 201-05 w/ inflation applied
- Inflation Rates
 - ➔ 2003 - 2014 = 0.26
 - ➔ 2014 - 2021 assumed 0.03 per year
- Exchange Rate
 - ➔ 2003 = 0.74 CHF/USD
 - ➔ 2014 = 1.14 CHF/USD





CSM Construction Costs

- There are currently 624 chambers in the barrel and 546 in the end cap, which require 608 and 510 CSM boards, respectively.
- NSW will not require CSM, so subtract 64 CSM
- New chambers (BME/BMR, BOE/BOR, BMG) require 22 additional CSM
- Assume 85% yield and 10% spares → Go with same as 2003 = 1325

Components	Count	Cost / item
FPGA's	1325	\$279.323
PROM's	1325	\$15.802
GBLD, laser diode, housing	1325	\$105.154
GBT-SCA	1325	\$33.649
Misc Parts	1325	\$175.015
GBTx	1325	\$175.000
Fabrication and Assembly		\$157.400
Total Cost per Board		\$941

Basis of Estimate

Scaled costs from 2003


- Inflation Rates
 - 2003 - 2014 = 0.26
 - 2014 - 2021 = 0.03 per year
- Exchange Rate
 - 2003 = 0.74 CHF/USD
 - 2014 = 1.14 CHF/USD



CSM Construction Costs

- There are currently 624 chambers in the barrel and 546 in the end cap, which require 608 and 510 CSM boards, respectively.
- NSW will not require CSM, so subtract 64 CSM
- New chambers (BME/BMR, BOE/BOR, BMG) require 22 additional CSM
- Assume 85% yield and 10% spares → Go with same as 2003 = 1325

Components	Count	Cost / item
FPGA's	1325	\$279.323
PROM's	1325	\$15.802
GBLD, laser diode, housing	1325	\$105.154
GBT-SCA	1325	\$33.649
Misc Parts	1325	\$175.015
GBTx	1325	\$175.000
Fabrication and Assembly		\$157.400
Total Cost per Board		\$941



Basis of Estimate

- Scaled FGPA costs from 2003
- Additionally compared to costs of modern FPGA's in expected performance class



CSM Construction Costs

- There are currently 624 chambers in the barrel and 546 in the end cap, which require 608 and 510 CSM boards, respectively.
- NSW will not require CSM, so subtract 64 CSM
- New chambers (BME/BMR, BOE/BOR, BMG) require 22 additional CSM
- Assume 85% yield and 10% spares → Go with same as 2003 = 1325

Components	Count	Cost / item
FPGA's	1325	\$279.323
PROM's	1325	\$15.802
GBLD, laser diode, housing	1325	\$105.154
GBT-SCA	1325	\$33.649
Misc Parts	1325	\$175.015
GBTx	1325	\$175.000
Fabrication and Assembly		\$157.400
Total Cost per Board		\$941

Basis of Estimate

**Current Cost Estimates
Provided by CERN and
scaled to 2021**

- Inflation Rates
→ 2014 - 2021 = 0.03 per year
- Exchange Rate
→ 2014 = 1.14 CHF/USD



CSM Construction Costs

- There are currently 624 chambers in the barrel and 546 in the end cap, which require 608 and 510 CSM boards, respectively.
- NSW will not require CSM, so subtract 64 CSM
- New chambers (BME/BMR, BOE/BOR, BMG) require 22 additional CSM
- Assume 85% yield and 10% spares → Go with same as 2003 = 1325

Components	Count	Cost / item
FPGA's	1325	\$279.323
PROM's	1325	\$15.802
GBLD, laser diode, housing	1325	\$105.154
GBT-SCA	1325	\$33.649
Misc Parts	1325	\$175.015
GBTx	1325	\$175.000
Fabrication and Assembly		\$157.400
Total Cost per Board		\$941

$$1325 \times \$941 = \$1.25\text{M}$$



CSM Construction Costs

		FY18		FY19		FY20		FY21		FY22	
		%	\$ / hr	%	\$ / hr	%	\$ / hr	%	\$ / hr	%	\$ / hr
Personnel Effort and \$/hr	Sr. Engineer	0.5	\$93.48	1.0	\$96.28	1.0	\$99.17	1.0	\$102.15	0.5	\$105.21
	Jr. Engineer	0.5	\$57.90	1.0	\$59.64	1.0	\$61.43	1.0	\$63.27	0.5	\$65.17
	Elec. Technician	0.5	\$56.85	1.0	\$58.56	1.0	\$60.31	1.0	\$62.12	0.5	\$63.99
	Elec. Student	0.5	\$35.48	1.0	\$36.54	1.0	\$37.64	1.0	\$38.77	0.5	\$39.93

Basis of Estimate

- Standard wages for personnel at Michigan with 3% yearly increase
- Expected personnel levels based on previous experience developing CSM at U-M

Previous CSM Development Team at U-M

- ➔ Jay Chapman (Sr Engineer equivalent) - CSM Leader/Firmware Design
- ➔ Pietro Binchi (Engineer) - Board design, left midway through development
- ➔ Bob Ball (Engineer) - CSM Firware, Board design, hired after Pietro left
- ➔ Tiesheng Dai (Engineer) - Test fixtures for MiniDAQ, test and debug
- ➔ Jon Ameel (Engineer) - Production, parts, testing on-site CERN
- ➔ Jeff Gregor and Tuan Anh Bui (Students) - Test and debug, some development





CSM Construction Costs

		FY18		FY19		FY20		FY21		FY22	
		%	\$ / hr	%	\$ / hr	%	\$ / hr	%	\$ / hr	%	\$ / hr
Personnel Effort and \$/hr	Sr. Engineer	0.5	\$93.48	1.0	\$96.28	1.0	\$99.17	1.0	\$102.15	0.5	\$105.21
	Jr. Engineer	0.5	\$57.90	1.0	\$59.64	1.0	\$61.43	1.0	\$63.27	0.5	\$65.17
	Elec. Technician	0.5	\$56.85	1.0	\$58.56	1.0	\$60.31	1.0	\$62.12	0.5	\$63.99
	Elec. Student	0.5	\$35.48	1.0	\$36.54	1.0	\$37.64	1.0	\$38.77	0.5	\$39.93
Costs	Total Personnel Cost	\$216,414		\$445,814		\$459,188		\$472,964		\$243,576	
	Travel	\$8,000		\$8,000		\$8,000		\$8,000		\$8,000	
	Prototypes/Fixtures			\$35,000		\$20,000					
	Final Production							\$1,250,000			
	Shipping							\$35,000			
	Total Cost	\$224,414		\$488,814		\$487,188		\$1,765,964		\$251,576	
								Total		\$3,217,957	
w/out Contingency											




Motherboards/Cabling Costs

- Current CSM boards connected to mezzanine through a motherboard which re-routes the large # cables from the mezzanine to more compact pin connectors
 - ➡ Not clear whether these cables/motherboards can handle the increased data rates for Phase-II
 - ➡ Previously, motherboard was constructed in US ~ \$120/board with inflation/contingency
 - ➡ High-speed cables will range \$15-30 (Halogen Free)
- Much bigger issue is additional labor and time to replace them!



Front and back of the motherboard which serves to connect the many cables from the front-end boards to more compact pin connectors which attach to the CSM.

underneath





Motherboards/Cabling Costs

- Current CSM boards connected to mezzanine through a motherboard which re-routes the large # cables from the mezzanine to more compact pin connectors
 - ➡ Not clear whether these cables/motherboards can handle the increased data rates for Phase-II
 - ➡ Previously, motherboard was constructed in US ~ \$120/board with inflation/contingency
 - ➡ High-speed cables will range \$15-30 (Halogen Free)
- Much bigger issue is additional labor and time to replace them!

# Cables in Barrel	# Cables in Endcap (EM + EO)	Total	Contingency and Spares	\$/cable	Total Cost
8054	5648	13702	15000	17	\$255K

Number of Chambers	\$/motherboard with connectors	Contingency 10%	Total Cost
1070	\$111	\$121	\$129K

Motherboards/Cabling Labor Costs


- Not directly a US deliverable, but very much worth mentioning
- In-cavern Effort, assuming three sets of 2-person teams working 24 hrs
 - ➔ Mezzanine and CSM replacement only (~ 40 min/chamber) ➔ **Completed in 6.5 weeks**
 - ➔ Cable replacement (additional ~ 90 min/chamber) ➔ **Completed in 21 weeks**



Summary

Deliverable	WBS #	US Institutions	Non-US	Funded US R&D	Construction Costs
CSM Design/Construction	6.5.1	Michigan		Yes	\$3,200k
TDC Design/Construction	6.5.2	BNL	CERN	sort of...	
ASD Design/Construction	6.5.3	BNL	MPI	sort of...	
Mezzanine Design and Assembly	6.5.4				
Motherboard/Cabling	6.5.5	Michigan? <i>I hope not...</i>		Yes	\$384k
FPGA to match hits for for Level 1 Trigger (@USA 15)	6.5.6		Japan?		


- ➡ Phase II interest is currently being fleshed out in US Muon community (NSW construction is dominating everyone's focus)
- ➡ Only “known” contribution is the CSM (costs have been estimated)
- ➡ As new Phase II R&D interest is gauged US deliverables will become clear






Backup

Phase II Muon Upgrade




Looking further inside this functional diagram...



Phase II Muon Upgrade

- ➔ Higher bandwidth from TDC's to CSM and CSM to USA15 and deeper buffers for mezzanine and CSM to handle the higher rates and longer latencies
- ➔ New trigger path - mezzanine sends pre-trigger data to CSM to be passed to USA15 before Level-0 decision decides to use it or not for Level-1 trigger algorithms
- ➔ Timing, Trigger, and Control (TTC) and GOL will be replaced by CERN GBT system
- ➔ Configure and Monitoring performed by GBT-SCA
- ➔ Front-end link exchange system (FELIX) will replace ROD-ROS to perform data collection from CSM



1. System-wide prep tasks:

- A. Procurement of cables 1 month
 - B. Design of motherboards 2 month
 - C. Fabrication/procurement of mother boards 2 month
 - D. Design/setup test station for MB + cables 2 month
 - E. Cable prep 7 person-months
 - (print out labels, sort cables, apply to cables for 15,000 cables 5 min/cable, cable testing)
 - Can be done with 4 students in parallel process in 6 weeks.
 - F. Mother board + cable pre-assembly
 - cable selection , mounting on MB +
 - testing of assembled units = $1/2 \text{ hr} * 1100 = 3 \text{ person-months}$
 - crating and shipping to CERN 1 week
 - receiving at CERN, storage until installation 1 day
- → total prep tasks Labor only: 10 person-months

Replacement efforts – in cavern

1. On chamber tasks removal of the old hardware: 30 - 70 min/chamber
 - A. positioning the crane or platform 10 min/chamber
 - B. removal of outer Faraday cage shell 5 min/chamber
 - C. removal of old cables
 - remove fasteners: 15 min/chamber
 - remove ground screws & unplug: 15 min/chamber
 - remove motherboard assembly w/old CSM: 20 min/chamber
 - store in box on crane 5 min./chamber
2. Install new stuff: 7 – 60 min/chamber
 - A. mount new motherboard assembly: 20 min
 - B. plug in power supply line & strain relief: 3 min
 - C. route 16 cables & mount strain relief to each mezzanine: 30 min
 - D. install new mezz cards: 1 min
 - E. re-install outer FC shell: 5 min
 - F. plug in cables: 0.25 min

→ 40– 130 min/chamber

- mezz card replacement only
- mezz card + cable replacement