

sPHENIX Calorimeter Electronics

L2 Managers Meeting

E.J. Mannel

May 12, 2016





The Cast and Crew

- L2 Manager: E. Mannel
- L3 Managers:
 - SiPMs: S. Stoll
 - Frontend EMCal/Hcal Electronics: S. Boose
 - Digitizer Electronics: C. Chi
- Institutions:
 - Design and prototyping:
 - BNL
 - Nevis Labs, Columbia University
 - Testing and evaluation
 - BNL: EMCal/HCal
 - Colorado: HCal
 - Debrecen: SiPMs
 - Iowa State: Hcal
 - Georgia State University: HCal
 - Nevis Labs, Columbia Univ.
 - UIUC: EMCal
 - Univ. of Michigan: SiPMs

Recent Work

- Designed and fabricated EMCal (64 channel) and HCal (32 channel) frontend electronics with associated controllers.



Inner HCal Prototype




5/12/16



Controllers

Similar controllers for EMCaL/HCaL
Provide temperature/leakage current monitoring
Bias voltage adjustment
LED Pulser control for testing



Electronics rack at test beam;
Digitizers, trigger electronics, controllers.

The Success Story




EMCAL LED's at Fermilab
Friday April 1, 2016

After ~900 miles on a truck:



And the effort of a number of
sPHENIX Test Beam participants
(BNL/ISU/GSU/UM/UIUC/WSU)

Photos and plots courtesy of
J. Haggerty, J. Huang and
S. Stoll




Inner and Outer HCAL LED's at Fermilab
Thursday March 31, 2016

Digitizers



- Based on PHENIX Hadron Blind Detector (HBD) system
- Digitizer:
 - 64 channels per board
 - 14 bit ADC
 - 60 MHz sampling frequency
 - Capable of generating trigger primitives
- XMIT Module
 - Transmits data from multiple (4) Digitizers
 - 8/10 Bit encoding
 - Compatible with DCM-II
- Crate Controller
 - JSEB-2 interface for slow control and readback
 - Internal clock option

First Boards



ADC Board

Controller



Backplane-
Nevis Transport Bus

Pictures from C. Chi

5/12/16



Digitizer Status

- Current status @ Nevis
 - 3 ADC boards functional
 - 1 Controller board works
 - 1 XMIT board is under going tests, XMIT->DCM-II link functional
 - Working on preparing a BNL Test Stand
- Near term plans
 - Understand noise issues with alternate power supplies
 - Setup test stand for transfer to BNL- Target date July 2016
 - Crate
 - Controller
 - ADC module
 - XMIT module
 - Software and documentation ala Chi with input from S. Campbell

The Near Future (May 2016-Feb 2017)

- Irregular bi-weekly meetings on Wednesday's at 1330
- Evaluate electronics performance in test beam
 - First meeting, 11-May-2016
- Evaluate digitizer prototype
 - May-August
- Specify design changes necessary for next test beam effort
 - May to July
- Implement and test design changes
 - July to November
- Setup test beam electronics
 - November to December
 - Includes full chain through new 64 channel digitizers and DCM-II
- Test beam participation
 - January-February