

Longitudinal Instability and Bunch-by-bunch Damper


Kevin Mernick
July 25, 2013
RHIC Retreat

A row of eleven sharpened colored pencils in various colors: yellow, orange, red, green, blue, dark blue, black, purple, brown, and black. The pencils are arranged in a slightly curved line, with their tips pointing upwards.



***stay tuned at the end of our program for a short preview
of coming bunch-by-bunch damper attractions**

Background


- Proton bunches at nominal intensity are unstable with just the 9 MHz RF system
- There are multiple modes of instabilities – dipole mode, quad mode, dancing bunches (multiple higher order modes)
- The existing RF system damped coherent dipole mode oscillations, but does not have the bandwidth to damp incoherent bunch-by-bunch oscillations
- Landau cavities keep the other modes mostly under control
- We built the damper specifically to address the incoherent bunch-by-bunch dipole oscillations





Damper System Overview




- The damper is built around the LLRF platform
- Bunch-by-bunch phase measurements come from the existing bunch-to-bucket phase detector and are processed in the “system controller” DSP (4 o’clock)
- The kicker waveform is synthesized with custom DAC (“arb”) firmware with bucket-by-bucket amplitude modulation capability (2 o’clock)
- The RF master clock and Update Link (with the bunch-by-bunch corrections) are broadcast to 2 o’clock on fiber optics
- The DAC waveform is amplified with 500W QEIs driving 2m stripline pairs
- This gives a maximum kick of about 100 V per turn








Damper Results




Commissioning in blue went well



Damper Results





Yellow was a little more difficult



Damper Results


- The damper was used operationally at injection starting from March 7
- Changed filter response to allow running with higher gains – this allowed us to get the system running




But there were problems on the ramp

Damper Results

- The damper was used operationally on ramps starting from April 18
- This only required a short period of time to setup delay compensation and worked the first try



**bunch phase
without damper**





bunch phase with damper







Periodic Transient Beam Loading

- The beam driven response of the RF cavities are affected by the fill pattern – they see a transient from the abort gap (or any other empty buckets) that is periodic at the revolution frequency
- This means that different bunches see a different RF voltage (amplitude and phase)

Bouncer Cavity Response





Periodic Transient Beam Loading





Periodic Transient Beam Loading

- This is an issue because it makes injection matching difficult – tuning up bunch 1 doesn't optimize all the bunches
- This shows injection oscillations for all bunches in a fill
- The early bunches are better matched than the ones in the middle to end of the train in this case




PTBL Compensation (part 1)

To compensate for the injection error, we adjusted the ATR synchro phase target based on the measured phase of previous bunches to try to match the new bunch to the phase of the transient




- This keeps the injection phase error more or less constant over the course of a fill
- A further improvement would be to correct that error as well (essentially giving an automatic "Apply P" correction on every shot)




Measuring Transient Beam Loading

- The “bucket-by-bucket” phase detector was developed during the run






- Vector sum here is the combination of the 9 MHz common and bouncer cavities – it only accounts for about 1/3 of beam phase



PTBL Compensation (part 2)

Once we had the bucket-by-bucket cavity phase measurements, we could attempt to flatten the transient with feedback





- This only fixed about 1/3 of the beam phase
- Ran well with low intensity ($\sim 1.2e11$), but had problems at higher intensities ($\sim 1.8e11$)
- But useful to learn about possible future progress

Longitudinal Instability Summary



- We built the damper specifically to address the incoherent bunch-by-bunch dipole oscillations and it works for this
- In the early part of the run, we had some bunch-by-bunch dipole mode instabilities, but once we settled on good settings for the damper, we didn't see those again
- We still need enough Landau voltage to prevent bunch shape oscillations
- The yellow instability threshold is clearly lower than blue, but we couldn't really figure out why – broadband impedance measurements for both rings give essentially the same answer
- We attempted to quantitatively determine instability thresholds for both rings – with the damper on and Landaus off, the yellow “threshold” is between $1e11$ and $1.25e11$ and blue is between $1.5e11$ and $1.75e11$

Longitudinal Instability Summary



above instability threshold

below instability threshold
but probably not what we
want for a physics store



From the people who brought you Longitudinal Bunch-by-bunch Damping

- We are working on designing and building a transverse bunch-by-bunch damper now
- The motivation for building this now is to damp the transverse mode coupling instability which may be excited when running high-intensity proton beams with the E-Lens, but it will also be beneficial at injection and on the ramp
- The hardware will be very similar to the longitudinal damper
- We plan to use existing arc BPMs for the pickups – the signals from the selected BPMs will be split at the cryostat, similar to the way the “RF BPMs” are shared by the RHIC orbit system and the LLRF system
- The BPM signal processing and damper processing will all be handled using the LLRF platform
- The kickers will be dual-plane 2 meter 50 Ω striplines – we are working on simplifying the existing design to be able to build more – driven by broadband (100 kHz – 30 MHz) RF power amplifiers

Transverse Bunch-by-bunch Damper

- The plan is to install the new kickers in the sector 5 warm bore – we need 4 meters of beam line in each ring
- The electronics will go in the 1005E service building

