# RHIC Computing Facility

DRAFT

Eric Lançon August 23, 2016



a passion for discovery



#### **Outline**

- Status of RCF, synergies with ATLAS Tier-1
- Performance in recent RHIC runs
- Future technological and data challenges
- Synergies with BNL Computing Initiative
- B725 infrastructure project




### Status of RCF, synergies with ATLAS Tier-1


- RCF performed well during 2016 run
- Resources are ~fully utilised
- Hardware (CPU) is getting old, migration to new tape generation needed (space in HPSS)
- Synergy with ATLAS Tier-1
  - Economy of scale (operation, purchase,...)
  - Common procedures and configurations (resilience)
  - Common tools (batch system, storage, network)
  - Expertise from RCF benefit to ATLAS (and vis versa)
  - Access to Grid and cloud computing expertise




#### Performance in recent RHIC runs


- No issue in
  - data transfer from experiments to facility
  - Writing to tape
- give some numbers







HPSS Data Growth - Phenix Raw



# **CPU** usage of the farms

- STAR farm almost continuously saturated while PHENIX farm is not
- PHENIX farm used by STAR analysis jobs
  - Optimisation of batch system (Condor) performed, STAR workflow optimisation to be done
  - STAR reconstruction cannot use PHENIX resources because STAR storage is distributed on CPU nodes
- Lessons for the future
  - Computing models (workflow management, data organisation, ...) and technological choices (storage, CPU,...) of experiments should not be too different in order to benefit from a global pool of resources




### Future technological and data challenges

- Future of computing is multi-core
  - New hardware are multi-core 8, 16, 32, 64,.... with less memory per core (or at a higher price)
  - Could software of RHIC experiments be multi-core? is it worst for existing experiments?
- Object store technology, ATLAS is migrating
- RHIC hardware is getting old ~22% older than 6 years
- Tape technology
  - 2 generations behind in tape technology
  - Move to new generation (LT07) to gain in capacity / media
  - ONLY one copy of RAW on tape
    - In moving data to new media 2 copies are made
    - xxx months for migration
    - But the 2 copies will be in the same building



### **Computational Science Initiative: CSI**

- CSI: Integrating data-intensive science expertise and investments across the Laboratory to tackle "big data" challenges
  - Leverage investments across multiple programs
  - Patterns: universities
    (Columbia, Cornell, New York
    University, Stony Brook, and
    Yale) and companies
    including IBM Research.
- Scientific Data and Computing Center: SDCC
- Computer...
- Computational...
- Center for....





## Scientific Data and Computing Center: SDCC

- Within CSI: an integrated scientific data, computing and networking infrastructure across BNL
- RACF the RHIC and ATLAS Computing Facility is the core of SDCC:
  - A world class HEP and NP facility
  - Expertise and infrastructure necessary for leadership & innovation in data-driven discovery
- SDCC is operating
  - The Lab's new Institutional Computing system (IC)
  - A series of novel architecture research systems,
  - As well as computing and data services for other thirdparty clients.



### Synergies with BNL Computing Initiative

- CSI is purchasing or complementing purchases in the area of HPC computing
  - Institutional cluster (Fall 2016)
  - Knight Landings (KNL) Intel farm (Fall 2016). Initiated by BNL QCD group and RIKEN, CSI doubled the capacity.
- These resources will be made available to RHIC program in opportunistic mode
- Issue : manpower to port RHIC codes?




#### SDCC evolution over the next months


- Institutional Cluster (IC)
  - Fall 2016 : 108 nodes (Intel Xeon + Nvidia K80 GPU + InfiniBand)
  - 2 x mid-2017
- Intel Knights Landing (KNL) cluster:
  - Fall 2016 : 144 nodes (Intel Xeon Phi + Omni-Path)
  - for RBRC (RIKEN and BNL Research Center)
  - and for CSI partners

End of 2016

70k cores

HPC: 22%





Brookhaven Science Associat

BROOKHAVEN NATIONAL LABORATORY


# **B725** infrastructure project




# Computing room(s) - Issues



- OLD installations
- Limited cooling and power distribution
- Limited raised floor (cannot accommodate cooling for denser new equipments)
- Limited space






**New computing room** 




# Core Facility Revitalisation – Conceptual Design

**NSLS-I Building** 



## CFR – Preliminary Schedule

Preliminary CFR Funding Analysis - 1 Yr CR 2017 (Renovation Alternative)



- In phase with LHC Long Shutdown 2 and RHIC
  - ATLAS Tier 1 MoU: Uptime 99%

Years	Beam Species and Energies
2016	High statistics Au+Au d+Au energy scan
2017	High statistics Pol. p+p at 510 GeV
2018	<sup>96</sup> Zr+ <sup>96</sup> Ru isobar run
2019-20	7.7-20 GeV Au+Au (BES-2)
2021	No Run?
2022-23	200 GeV Au+Au with upgraded detectors Pol. p+p, p+Au at 200 GeV
2024	Program TBD

15

# CFR Design – An Incremental Approach

#### Power

- Day-one capability (2021) 2.4 MW IT power (dedicated computing power). This is approximately double current RACF IT power.
- Provide provision for future 1.2 MW IT power increments to 6MW Max.

### Cooling

- Day-one cooling capability to support 2.4 MW IT power
- Provide provision for future 1.2 MW IT power deployments

#### Space

- Day-one Accommodate approximately 33% footprint expansion (Racks) within defined spaces.
- Day-one Accommodate approximately 3,500 SF additional, unassigned space.
- Provide opportunity for future (long term) growth within the balance of the 725 facility. Both computing and offices.



# **Summary**

