

Further Details on TPC Cost/Schedule/Resources



KLAUS DEHMELT

**ASSOCIATE LABORATORY DIRECTOR'S DESIGN REVIEW OF
THE sPHENIX TRACKER
SEPTEMBER 07, 2016**



Stony Brook University


| The State University of New York



Project Schedule

2

WBS	Task Name	Duration	Start	Cost	2014	2015	2016	2017	2018	2019	2020	2021	2022
1.3.1	Tracker Management	1432 days	Thu 10/1/15	\$0									
1.3.1.1	Manage L2 Tracker Subsystem	1161 days	Tue 11/1/16	\$0									
	Complete Commissioning	0 days	Wed 6/30/21	\$0									
1.3.1.3	TPC L3 Management	1161 days	Tue 11/1/16	\$0									
	Start Pre R&D	0 days	Thu 10/1/15	\$0									
1.3.1.5	Start Pre R&D	0 days	Thu 10/1/15	\$0									
1.3.1.6	Receive DOE CD-0	0 days	Tue 11/1/16	\$0									
1.3.1.7	Receive DOE CD-1	0 days	Wed 11/1/17	\$0									
1.3.1.8	Receive DOE CD-2/3	0 days	Wed 8/1/18	\$0									
1.3.2	Time Projection Chamber	1105 days	Thu 10/1/15	\$4,827,405									



Project Schedule

2


WBS	Task Name	Duration	Start	Cost	2014	2015	2016	2017	2018
1.3.2.1	TPC Prototyping	685 days	Thu 10/1/15	\$1,190,556					
1.3.2.1.1	TPC Prototype v1	490 days	Thu 10/1/15	\$474,455					
1.3.2.1.1.1	v1 Field Cage Prototype	375 days	Thu 10/1/15	\$271,598					
1.3.2.1.1.2	v1 Module Prototyping	190 days	Wed 12/14/16	\$202,857					
1.3.2.1.1.2.1	v1 Gas Enclosure	65 days	Wed 12/14/16	\$26,883					
1.3.2.1.1.2.2	v1 Common Module Mechanics	40 days	Thu 12/15/16	\$65,105					
1.3.2.1.1.2.3	v1a Module Prototype	95 days	Thu 12/15/16	\$55,434					
1.3.2.1.1.2.4	v1b Module Prototype	95 days	Wed 5/3/17	\$55,434					
1.3.2.1.1.2.5	v1 Module Prototyping Complete	0 days	Mon 9/18/17	\$0					
1.3.2.1.2	v1 Magnet Test (v1a module)	20 days	Thu 6/1/17	\$28,952					
1.3.2.1.3	v1 Performance Review	10 days	Tue 9/19/17	\$14,800					
1.3.2.1.4	TPC v1 Prototype Complete	0 days	Mon 10/2/17	\$0					
1.3.2.1.5	TPC Prototype v2	250 days	Tue 4/4/17	\$565,963					
1.3.2.1.5.1	v2 Field Cage Prototype	245 days	Tue 4/4/17	\$366,318					
1.3.2.1.5.2	v2 Module Prototyping	190 days	Wed 6/28/17	\$199,646					
1.3.2.1.6	Performance review v2 prototype	10 days	Fri 4/6/18	\$8,312					
1.3.2.1.7	TPC Prototype v2 Complete	0 days	Thu 4/19/18	\$0					
1.3.2.1.8	TPC Preproduction Prototype	164 days	Wed 11/1/17	\$98,074					



Project Schedule

2

WBS	Task Name	Duration	Start	Cost	2018 H2 H1 H
1.3.2.1.8	TPC Preproduction Prototype	164 days	Wed 11/1/17	\$98,074	
1.3.2.1.8.1	v2 Field Cage Modifications	65 days	Fri 3/30/18	\$12,995	
1.3.2.1.8.1.1	Design v2 Field Cage Modifications	5 days	Fri 3/30/18	\$7,400	
1.3.2.1.8.1.2	Procure v2 Field Cage Modification Parts	40 days	Fri 4/6/18	\$5,595	
1.3.2.1.8.1.3	Perform Modification of v2 Field Cage	10 days	Mon 6/4/18	\$0	
1.3.2.1.8.1.4	Test Modified v2 Field Cage	10 days	Mon 6/18/18	\$0	
1.3.2.1.8.1.5	v2 Field Cage Modifications Complete	0 days	Fri 6/29/18	\$0	
1.3.2.1.8.2	Site Prep for Production Factories	40 days	Wed 11/1/17	\$36,000	
1.3.2.1.8.2.1	R1 Factory Preparation	40 days	Wed 11/1/17	\$12,000	
1.3.2.1.8.2.2	R2 Factory Preparation	40 days	Wed 11/1/17	\$12,000	
1.3.2.1.8.2.3	R3 Factory Preparation	40 days	Wed 11/1/17	\$12,000	
1.3.2.1.8.3	Design R1,R2,R3 Modules (strongback, frame, grid, pad, GEMs)	40 days	Wed 11/1/17	\$0	
1.3.2.1.8.4	Procure R1,R2,R3 Stongbacks	40 days	Thu 1/4/18	\$11,595	
1.3.2.1.8.5	Procure R1,R2,R3 Frames	40 days	Thu 1/4/18	\$8,595	
1.3.2.1.8.6	Procure R1,R2,R3 Grids	20 days	Thu 1/4/18	\$4,298	
1.3.2.1.8.7	Procure R1,R2,R3 Pad Planes	40 days	Thu 1/4/18	\$4,595	
1.3.2.1.8.8	Procure R1,R2,R3 GEMs	40 days	Thu 1/4/18	\$12,595	
1.3.2.1.8.9	Assemble R1 Module in R1 Factory	40 days	Mon 3/5/18	\$0	
1.3.2.1.8.10	Assemble R2 Module in R2 Factory	40 days	Mon 3/5/18	\$0	
1.3.2.1.8.11	Assemble R3 Module in R3 Factory	40 days	Mon 3/5/18	\$0	
1.3.2.1.8.12	Test R1,R2,R3 Modules after Shipping to BNL	20 days	Mon 4/30/18	\$0	
1.3.2.1.8.13	Production Readiness Review	5 days	Tue 5/29/18	\$7,400	
1.3.2.1.8.14	Preproduction Prototype Accepted	0 days	Mon 6/4/18	\$0	



Description of Project Plan

3

- sPHENIX TPC has multi-stage R&D program:
 - *v1* prototype
 - *v2* prototype
 - *Pre-production* prototype
- Much R&D on GEM-based detectors done via the eRD6 program → EIC Detector R&D
- R&D should address “scaling issue” of large MPGD already at *v1* level
- Propose to keep and use the *v2* (*v1*?) field cage for the actual sPHENIX experiment
- *v1* phase has received funds from SBU and LDRD → must be considered in MS Project file correctly

Project Items

4

v1 Field Cage Prototype

188,718

(including 20% cont.)

Item	Vendor	Min Units	Ordered	Price	Total	Status	Basis of Estimate	SubComponent Total
FR4520 tooling Foam	General Plastics	6	7	623.14	\$4,361.98	ORDERED		
2" diameter 9' long shaft	Technico	1	1	335	\$335.00	DELIVERED		
RSF-14B-30-F100-24B	Harmonic Drive	1	1	1330	\$1,330.00	ORDERED		
SHA32A161SG-B12BLV-10S17b-AN	Harmonic Drive	1	1	4674	\$4,674.00	ORDERED		
8020	McMaster-Carr				\$4,277.84	DELIVERED		
Laminate Trimmer	Grainger	1	1	155	\$155.00	DELIVERED		
Position Encoders	Renishaw				\$1,202.00	DELIVERED		
Adhesive, lab supplies	McMaster-Carr				\$1,440.43	DELIVERED		
Lead Screw	Lin Tech				\$3,456.00	DELIVERED		
2" flanged Collars for motor/encoder	McMaster-Carr				\$371.66	DELIVERED		
USB microscope	Microscope Store				\$143.00	DELIVERED		
Motor Controllers	Copley Controls				\$1,637.00	DELIVERED		
SM encoder	Automation Direct				\$67.25	DELIVERED		
SM motor	MicroMo				\$253.49	DELIVERED		
Wire/connectors	DigiKey				\$352.41	DELIVERED		
PS for translation motor (24 V 24 A)	Automation Direct				\$415.00	DELIVERED		
PS for shaft motor (48 V 24 A)	Acopian				\$1,170.00	ORDERED		
Motor Controller Access. Kits	Copley Controls				\$276.00	ORDERED		
Web Tension Applicator Toolset	F.W. Hall Company				\$4,000.00	Pending	Web Search	\$29,918.06
Honeycomb	Plascorp	4	6	270.18	\$1,621.08	DELIVERED		
Striped circuit cards	All-flex	5	8	2925	\$23,400.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	2	3	7260	\$21,780.00	Pending	Manufacturer Quote	
3 mil kapton 22" x 108 LF	Dunmore	4	5	4070	\$20,350.00	Pending	Manufacturer Quote	
FR4 outer sheets 4' x 4'	ePlastics	8	10	114.58	\$1,145.80	Pending	Manufacturer Quote	
HVPW resistors	DigiKey	800	1000	1.17	\$1,170.00	Pending	Manufacturer Quote	
High Voltage Cable	Dielectric Sciences				\$600.00	Pending	Web Search	\$70,066.88
Striped circuit cards	All-flex	5	8	1500	\$12,000.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	1	1	7260	\$7,260.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	1	2	4070	\$8,140.00	Pending	Manufacturer Quote	
FR4 Sheets 4' x 4'	ePlastics	2	2	114.58	\$229.16	Pending	Manufacturer Quote	
HVPW Resistors	DigiKey	800	1000	1.17	\$1,170.00	Pending	Manufacturer Quote	\$28,799.16
Central Membrane					\$8,000.00		Experience	\$8,000.00
End Caps					\$20,000.00		Experience	\$20,000.00

Project Items

4

v1 Field Cage Prototype

188,718

(including 20% cont.)

Item	Vendor	Min Units	Ordered	Price	Total	Status	Basis of Estimate	SubComponent Total
FR4520 tooling Foam	General Plastics	6	7	623.14	\$4,361.98	ORDERED		
2" diameter 9' long shaft	Technico	1	1	335	\$335.00	DELIVERED		
RSF-14B-30-F100-24B	Harmonic Drive	1	1	1330	\$1,330.00	ORDERED		
SHA32A161SG-B12BLV-10S17b-AN	Harmonic Drive	1	1	4674	\$4,674.00	ORDERED		
8020	McMaster-Carr				\$4,277.84	DELIVERED		
Laminate Trimmer	Grainger	1	1	155	\$155.00	DELIVERED		
Position Encoders	Renishaw				\$1,202.00	DELIVERED		
Adhesive, lab supplies	McMaster-Carr				\$1,440.43	DELIVERED		
Lead Screw	Lin Tech				\$3,456.00	DELIVERED		
2" flanged Collars for motor/encoder	McMaster-Carr				\$371.66	DELIVERED		
USB microscope	Microscope Store				\$143.00	DELIVERED		
Motor Controllers	Copley Controls				\$1,637.00	DELIVERED		
SM encoder	Automation Direct				\$67.25	DELIVERED		
SM motor	MicroMo				\$253.49	DELIVERED		

v2 Field Cage Prototype

188,718

(including 20% cont.)

Motor Controller Access. Kits	Copley Controls				\$276.00	ORDERED		
Web Tension Applicator Toolset	F.W. Hall Company				\$4,000.00	Pending	Web Search	\$29,918.06
Honeycomb	Plascorp	4	6	270.18	\$1,621.08	DELIVERED		
Striped circuit cards	All-flex	5	8	2925	\$23,400.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	2	3	7260	\$21,780.00	Pending	Manufacturer Quote	
3 mil kapton 22" x 108 LF	Dunmore	4	5	4070	\$20,350.00	Pending	Manufacturer Quote	
FR4 outer sheets 4' x 4'	ePlastics	8	10	114.58	\$1,145.80	Pending	Manufacturer Quote	
HVPW resistors	DigiKey	800	1000	1.17	\$1,170.00	Pending	Manufacturer Quote	
High Voltage Cable	Dielectric Sciences				\$600.00	Pending	Web Search	\$70,066.88
Striped circuit cards	All-flex	5	8	1500	\$12,000.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	1	1	7260	\$7,260.00	Pending	Manufacturer Quote	
3 mil kapton 44" x 108 LF	Dunmore	1	2	4070	\$8,140.00	Pending	Manufacturer Quote	
FR4 Sheets 4' x 4'	ePlastics	2	2	114.58	\$229.16	Pending	Manufacturer Quote	
HVPW Resistors	DigiKey	800	1000	1.17	\$1,170.00	Pending	Manufacturer Quote	\$28,799.16
Central Membrane					\$8,000.00		Experience	\$8,000.00
End Caps					\$20,000.00		Experience	\$20,000.00



Stony Brook University


The State University of New York



Project Items

5

WBS	Task Name	Durati	Cost	Fixed Cost	18	2019				
					Q2	Q3	Q4	Q1	Q2	Q3
1.3.2.2	TPC Production	280 days	\$1,368,161	\$0						
1.3.2.2.1	TPC Module Production	280 days	\$695,527	\$0						
1.3.2.2.1.1	Train Technician to work in CERN Shop	2 mons	\$39,080	\$39,080						
1.3.2.2.1.2	Production of GEM foils (includes Technician)	6 mons	\$191,089	\$191,089						
1.3.2.2.1.3	Procure frames	40 days	\$45,920	\$40,000						
1.3.2.2.1.4	Procure strongbacks (R1, R2, R3 modules)	40 days	\$50,920	\$45,000						
1.3.2.2.1.5	Procure Pad Planes	40 days	\$2,595	\$0						
1.3.2.2.1.6	Procure Grids	40 days	\$2,595	\$0						
1.3.2.2.1.7	Build modules	6 mons	\$155,712	\$0						
1.3.2.2.1.8	Test modules	6 mons	\$0	\$0						
1.3.2.2.1.9	Assemble detector	6 mons	\$155,712	\$0						
1.3.2.2.1.10	Test Detector Prior to installation	80 days	\$51,904	\$0						
1.3.2.2.1.11	TPC Ready to install	0 days	\$0	\$0						
1.3.2.2.2	TPC Laser System	174 days	\$241,907	\$0						
1.3.2.2.3	TPC Gas System	230 days	\$260,997	\$0						
1.3.2.2.4	TPC Cooling System	202 days	\$169,730	\$0						



Project Items

5


WBS	Task Name	Durati	Cost	Fixed Cost	18 Q2	Q3	Q4	2019 Q1	Q2	Q3
1.3.2.2	Train technician		39,080							
1.3.2.2.1										
1.3.2.2.1.1	Train Technician to work in CERN Shop	2 mons	\$39,080	\$39,080						
1.3.2.2.1.2	Production of GEM foils (includes Technician)	6 mons	\$191,089	\$191,089						
1.3.2.2.1.3	Procure frames	40 days	\$45,920	\$40,000						
1.3.2.2.1.4	Procure strongbacks (R1, R2, R3 modules)	40 days	\$50,920	\$45,000						
1.3.2.2.1.5	Procure Pad Planes	40 days	\$2,595	\$0						
1.3.2.2.1.6	Procure Grids	40 days	\$2,595	\$0						
1.3.2.2.1.7	Build modules	6 mons	\$155,712	\$0						
1.3.2.2.1.8	Test modules	6 mons	\$0	\$0						
1.3.2.2.1.9	Assemble detector	6 mons	\$155,712	\$0						
1.3.2.2.1.10	Test Detector Prior to installation	80 days	\$51,904	\$0						
1.3.2.2.1.11	TPC Ready to install	0 days	\$0	\$0						9/13/19
1.3.2.2.2	▸ TPC Laser System	174 days	\$241,907	\$0						
1.3.2.2.3	▸ TPC Gas System	230 days	\$260,997	\$0						
1.3.2.2.4	▸ TPC Cooling System	202 days	\$169,730	\$0						



Project Items

5

WBS	Task Name	Durati	Cost	Fixed Cost	18 Q2	Q3	Q4	2019 Q1	Q2	Q3
1.3.2.2	Train technician		39,080							
1.3.2.2.1	Production of GEM foils		191,089							
1.3.2.2.1.1										
1.3.2.2.1.2	Production of GEM foils (includes Technician)	6 mons	\$191,089	\$191,089						
1.3.2.2.1.3	Procure frames	40 days	\$45,920	\$40,000						
1.3.2.2.1.4	Procure strongbacks (R1, R2, R3 modules)	40 days	\$50,920	\$45,000						
1.3.2.2.1.5	Procure Pad Planes	40 days	\$2,595	\$0						
1.3.2.2.1.6	Procure Grids	40 days	\$2,595	\$0						
1.3.2.2.1.7	Build modules	6 mons	\$155,712	\$0						
1.3.2.2.1.8	Test modules	6 mons	\$0	\$0						
1.3.2.2.1.9	Assemble detector	6 mons	\$155,712	\$0						
1.3.2.2.1.10	Test Detector Prior to installation	80 days	\$51,904	\$0						
1.3.2.2.1.11	TPC Ready to install	0 days	\$0	\$0						
1.3.2.2.2	▸ TPC Laser System	174 days	\$241,907	\$0						
1.3.2.2.3	▸ TPC Gas System	230 days	\$260,997	\$0						
1.3.2.2.4	▸ TPC Cooling System	202 days	\$169,730	\$0						



Project Items

5

Train technician	39,080	
Production of GEM foils	191,089	(including technician)

3.1. Cost of GEM foils

Cost in CHF calculated per month, using 1 FSU technician.

Cost/month/batch (CHF):

Raw material	2750
Chemistry, photoresist, other consumables	1650
Personnel (1 FSU)	9000
TOTAL (100% yield)	13400
TOTAL (85% yield)	15410

Our production is based upon the rates shown in the above table as a scaling for the fact that we shall cover 1/3 the area of the ALICE upgrade.

Project Items

6

WBS	Task Name	Cost	Fixed Cost	16	Q2	Q3	Q4	2017	Q1	Q2	Q3	Q4	2018	Q1	Q2	Q3	2019	Q1	Q2	Q3
1.3.2.2	TPC Production	\$1,368,161	\$0																	
1.3.2.2.1	TPC Module Production	\$695,527	\$0																	
1.3.2.2.2	TPC Laser System	\$241,907	\$0																	
1.3.2.2.2.1	Design Laser System & Safety	\$59,200	\$0																	
1.3.2.2.2.2	Procure lasers	\$94,987	\$90,000																	
1.3.2.2.2.3	Procure optics with mirrors	\$52,494	\$50,000																	
1.3.2.2.2.4	Procure mirror bundles with supports	\$17,494	\$15,000																	
1.3.2.2.2.5	Install lasers	\$1,946	\$0																	
1.3.2.2.2.6	safety interlocks and paper work	\$8,650	\$2,000																	
1.3.2.2.2.7	Install optics with mounts	\$5,190	\$0																	
1.3.2.2.2.8	Install mirror bundles and supports	\$1,946	\$0																	
1.3.2.2.3	TPC Gas System	\$260,997	\$0																	
1.3.2.2.3.1	Design TPC Gas Handling System	\$64,880	\$0																	
1.3.2.2.3.2	Procure mass flow meters	\$11,494	\$9,000																	
1.3.2.2.3.3	Procure gas analyzer, 2 for redundancy	\$62,494	\$60,000																	
1.3.2.2.3.4	Procure scrubbers	\$6,494	\$4,000																	
1.3.2.2.3.5	Procure oxygen and water sensors	\$6,494	\$4,000																	
1.3.2.2.3.6	Assemble gas system controls	\$43,915	\$0																	
1.3.2.2.3.7	Set up computer control system	\$5,494	\$3,000																	
1.3.2.2.3.8	plumbing and assembly	\$48,422	\$7,000																	
1.3.2.2.3.9	Set up interlocks	\$7,156	\$3,000																	
1.3.2.2.3.10	safety reviews and paper work	\$4,156	\$0																	
1.3.2.2.4	TPC Cooling System	\$169,730	\$0																	
1.3.2.2.4.1	Design TPC Cooling System	\$83,624	\$0																	
1.3.2.2.4.2	Procure equipment(pumps,heat exchanger, PH control, enc	\$38,880	\$30,000																	
1.3.2.2.4.3	Install pumps	\$1,946	\$0																	
1.3.2.2.4.4	Install heat exchanger	\$1,946	\$0																	
1.3.2.2.4.5	Install PH control	\$1,946	\$0																	
1.3.2.2.4.6	Install end cap manifolds	\$6,488	\$0																	
1.3.2.2.4.7	Install tanks	\$1,946	\$0																	
1.3.2.2.4.8	Install plumbing	\$23,464	\$4,000																	
1.3.2.2.4.9	Set up controls	\$6,244	\$3,000																	
1.3.2.2.4.10	Set up interlocks	\$3,244	\$0																	



Project Items

6

WBS	Task Name	Cost	Fixed Cost	16	Q2	Q3	Q4	2017	Q1	Q2	Q3	Q4	2018	Q1	Q2	Q3	2019	Q1	Q2	Q3
1.3.2.2	TPC Production	\$1,368,161	\$0																	
1.3.2.2.1	TPC Module Production	\$695,527	\$0																	
1.3.2.2.2	TPC Laser System	\$241,907	\$0																	
1.3.2.2.2.1	Design Laser System & Safety	\$59,200	\$0																	
1.3.2.2.2.2	Procure lasers	\$94,987	\$90,000																	
1.3.2.2.2.3	Procure optics with mirrors	\$52,494	\$50,000																	
1.3.2.2.2.4	Procure mirror bundles with supports	\$17,494	\$15,000																	
1.3.2.2.2.5	Install lasers	\$1,946	\$0																	
1.3.2.2.2.6	safety interlocks and paper work	\$8,650	\$2,000																	
1.3.2.2.2.7	Install optics with mounts	\$5,190	\$0																	
1.3.2.2.2.8	Install mirror bundles and supports	\$1,946	\$0																	
1.3.2.2.3	TPC Gas System	\$260,997	\$0																	
1.3.2.2.3.1	Design TPC Gas Handling System	\$64,880	\$0																	
1.3.2.2.3.2	Procure mass flow meters	\$11,494	\$9,000																	
1.3.2.2.3.3	Procure gas analyzer, 2 for redundancy	\$62,494	\$60,000																	
1.3.2.2.3.4	Procure scrubbers	\$6,494	\$4,000																	
1.3.2.2.3.5	Procure oxygen and water sensors	\$6,494	\$4,000																	
1.3.2.2.3.6	Assemble gas system controls	\$43,915	\$0																	
1.3.2.2.3.7	Set up computer control system	\$5,494	\$3,000																	
1.3.2.2.3.8	plumbing and assembly	\$48,422	\$7,000																	
1.3.2.2.3.9	Set up interlocks	\$7,156	\$3,000																	
1.3.2.2.3.10	safety reviews and paper work	\$4,156	\$0																	
1.3.2.2.4	TPC Cooling System	\$169,730	\$0																	
1.3.2.2.4.1	Design TPC Cooling System	\$83,624	\$0																	
1.3.2.2.4.2	Procure equipment(pumps,heat exchanger, PH control, enc	\$38,880	\$30,000																	
1.3.2.2.4.3	Install pumps	\$1,946	\$0																	
1.3.2.2.4.4	Install heat exchanger	\$1,946	\$0																	
1.3.2.2.4.5	Install PH control	\$1,946	\$0																	
1.3.2.2.4.6	Install end cap manifolds	\$6,488	\$0																	
1.3.2.2.4.7	Install tanks	\$1,946	\$0																	
1.3.2.2.4.8	Install plumbing	\$23,464	\$4,000																	
1.3.2.2.4.9	Set up controls	\$6,244	\$3,000																	
1.3.2.2.4.10	Set up interlocks	\$3,244	\$0																	



Project Items

7

- **Details of the Base Estimate (explanation of the Work)**: Procure Laser \$90k, Optics and Mirrors \$50k
 - Laser of appropriate power and pulse length must be purchased. sPHENIX called upon expertise of H. Wieman to select and cost appropriate laser for our needs based upon similar system used in ALICE
- **Assumptions Used in Developing Estimate**
 - Power and pulse length requirements on laser for sPHENIX well matched to those of ALICE

Project Items

8

- **Details of the Base Estimate (explanation of the Work)**: Procure Gas Analyzer \$60k
 - We shall use same gas analyzer systems as used for ALICE, costs of devices was shared with us by H. Wieman
- **Assumptions Used in Developing Estimate**
 - Cost of the gas analyzer will be similar when making our measurements
 - Quality of device should be same as in ALICE, latter criterion is conservative since ALICE operates away from drift velocity plateau and is more vulnerable to impurities

Bottoms-up Cost Estimate

9

- TPC MIE and Support Labor Costs fully burdened with BNL Project rates as applicable, escalated, and 40% contingency applied across the board. BNL Labor rates where appropriate. Reductions for BNL LDRD and SBU funding were applied.

sPHENIX TPC Tracking								
Summary Estimate								
	2016	2017	2018	2019	2020	2021	2022	Grand Total
sPHENIX Labor								
Fixed FY16 Direct Labor w/fringe		372,981	493,559	551,504	149,820			\$1,567,864
Estimated Composite Indirect on Labor@36.9%	0	137,630	182,123	203,505	55,284	0	0	578,542
Fixed FY16 Fully Loaded Labor	0	510,611	675,682	755,009	205,104	0	0	2,146,406
Escalation @ 3.0%	0	15,318	41,149	69,989	25,740	0	0	152,197
Subtotal AY \$	0	525,929	716,831	824,998	230,844	0	0	2,298,603
Contingency at 40%	0	210,372	286,733	329,999	92,338	0	0	919,441
Budgeted Labor	0	736,301	1,003,564	1,154,998	323,182	0	0	3,218,044
Adjusted sPHENIX M&S - TPC								
Estimated Composite Indirect	0	30,635	69,421	84,210	472	0	0	184,737
Subtotal FY 16 \$	\$0	\$355,501	\$805,590	\$977,210	\$5,472	\$0		\$2,143,772
Escalation @ 2% per FY	0	7,110	32,546	59,813	451	0		99,920
Estimate with Escalation	\$0	\$362,611	\$838,136	\$1,037,023	\$5,923	\$0		\$2,243,692
Contingency at 40%	0	145,044	335,254	414,809	2,369	0	0	897,477
Budgeted Material	\$0	\$507,655	\$1,173,390	\$1,451,832	\$8,292	\$0	\$0	\$3,141,169
Total AY \$ with Contingency Estimate	\$0	\$1,243,956	\$2,176,954	\$2,606,830	\$331,473	\$0	\$0	\$6,359,213
Overall contingency %								40.0% TPC 40.0% TEC



Outlook

10

- Suggest we take on Drill-Down Exercise




Project Scope

11

- Build a Time Projection Chamber (TPC)
 - Field Cage (FC)
 - Endplate (EP)
 - ✦ Modules
 - ✦ Electronics
 - Central Membrane (CM)
 - Readout Electronics



Field Cage subdivided in
Outer (O-FC)
Inner (I-FC)



Cutaway of a TPC


Project Scope

12




Project Scope

13



$l = 2110.0 \text{ mm (83.1 in)}$
 $OR = 780.0 \text{ mm (30.7 in)}$



$IR = 200.0 \text{ mm (7.9 in)}$



Project Scope

14

