


EMCal Module Production for 2017 prototype

Anne Sickles for NPL Group
August 11, 2017





fiber filling: 3D printed frame
with spacers between meshes

time to fill: 40-60 minutes
depends on experience and
skill



mold for 2D projective modules


- bathtub style, partially reusable
 - base, vacuum channels provided by Delrin base
 - module shape and mesh placement provided by printed spacers



mold for 2D projective modules (2)



- fiber assembly placed in mold
- U pieces then filled in between meshes
- this design prevents the most challenging part of the 1D modules—putting the fiber assembly in the mold



epoxy uniformity




August 10,
module about to be
filled

U-pieces quick
epoxied into mold
prior to filling

- if there are too many paths for the epoxy to follow without being uniform in the module, we will get dry spots
- main optimization now is epoxy flow



this morning!
still ~1cm dry part along the
bottom, but improving



- next step: modify the meshes to remove bottom fiber free region

fully 3D printed mold

- printed mold: 80 print job
- U pieces: 2 x 7 hour print job
- U pieces provide easier and safer loading of the fibers into the mold
- both use 3D printed pieces to provide the shapes to the modules
- issue of many different molds not relevant since these pieces are not reused



U-pieces

- 2x7 hours on the 3D printer
 - can print a total of 2 sets / day with 2 3D printers
- also looking into injection molding
 - especially for full detector
 - prices seem reasonable for the quantities per size we would need

meshes

- ~1 month from ordering to delivery with the tooling already made
- the first time we had to have the tooling made and it took about a month too...
- we should finalize the meshes and order them to have them by mid-September