

# Electromagnetic Calorimetry and Calorimeter Electronics

Anne Sickles  
November 9, 2015



I L L I N O I S

UNIVERSITY OF ILLINOIS AT URBANA-CHAMPAIGN

# EMCal Performance Specs


---

- energy resolution:
  - $<15\%/\sqrt{E}$ , driven by  $\gamma$  and  $e^\pm$  measurement
- segmentation to allow  $\gamma$  and  $e^\pm$  reconstruction in central AuAu collision
- acceptance over  $2\pi$  and  $\pm 1.1$  in  $\eta$
- together with HCal provide good jet reconstruction in central AuAu collisions
- high density to minimize radial space inside solenoid (allow room for inner HCal & tracking)
- $>90\times \pi$  rejection @ 70% electron eff. (=50%  $Y$  eff.)

# W-Fiber EMCal


- tungsten powder-epoxy embedded into matrix of scintillating fibers
- fibers
  - diameter: 0.47mm
  - spacing:  $\sim 1\text{mm}$
- density  $\sim 10\text{g/cm}^3 \rightarrow X_0 = 7\text{mm}$ ,  $R_M = 2.3\text{cm}$
- can point the fibers back to collision point in 1 (or 2) dimensions to generate 1D (2D) projectivity
- tower size:  $\sim 1'' \times 1''$ ,  $0.025 \times 0.025$  in  $\Delta\eta \times \Delta\phi$

tungsten-fiber  
cross section




# light collection & electronics

- light collection via acrylic light guides
- SiPM readout
  - 4 tiled per tower
  - $\sim 25\text{k}$  towers  $\rightarrow \sim 100\text{k}$  SiPMs
  - Hamamatsu S12572-33-015P;  $15\mu\text{m}$  pixels
    - $3\times 3\text{mm}^2$ , 40k pixels,  $\sim 10^4$  dynamic range (5MeV - 50 GeV)
- read out from the inner radius of the calorimeter
- preamps with temperature compensation to provide gain stabilization of SiPM gain variation with T
- digitizer design based on those already used in PHENIX
  - 14 bit ADC, 65 MHz digitization






# EMCal geometry



$\eta=0$





$\eta=1$

sector


		Value
Inner radius (envelope)	mm	900
Outer radius (envelope)	mm	1161
Length (envelope)	mm	$2 \times 1495 = 2990$
Number of towers in azimuth ( $\Delta\phi$ )		256
Number of towers in pseudorapidity ( $\Delta\eta$ )		$2 \times 48 = 96$
Number of electronic channels (towers)		$256 \times 96 = 24576$
Number of SiPMs per tower		4
Number of towers per module		$2 \times 8 = 16$
Number of modules per sector		24
Number of towers per sector		384
Number of sectors		$2 \times 32 = 64$
Sector weight (estimated)	kg	326
Total weight (estimated)	kg	20890
Average sampling fraction		2.3%

# EMCal scope


 $\eta=0$ 

 $\eta=1$ 

sector




- 4 SiPM/tower: ~100k SiPM
- 3 rounds of prototyping
- module production, QA, and assembly
  - 384 towers/sector
  - 64 sectors in full detector
  - 4 SiPM/tower
  - calibration and integration into sPHENIX



# design drivers—EMCal

- segmentation and energy resolution
- reconstruction of 5 GeV electrons in central HI environment
- $<15\%/\sqrt{E} \rightarrow$  EMCal will not limit photon resolution
- 2D projectivity
  - driven by electron ID requirements in central HI environment for  $\Upsilon$  reconstruction
- with only 1D projectivity electron-hadron separation degrades with increasing  $|\eta|$ 
  - reduce statistics of already statistics limited measurement

EMCal energy:  
central HIJING event



# design drivers—electronics


---

- as common as possible for EMCal and HCal
  - same sensors for both systems
  - large gain
  - work in magnetic field
  - compact
    - SiPMs
- LED monitoring/calibration system
- provide L1 trigger information from EMCal & HCal
- utilize existing PHENIX DAQ, event rate  $\sim 15\text{kHz}$ 
  - digitizer design based on those already used in PHENIX



# schedule drivers

- R&D on 2D projective design
  - 1D projective modules (2x1 towers) have been successfully produced at UCLA, Tungsten Heavy Powder (industry), Illinois and BNL
    - production process well under control
  - 2D projective production process being developed
    - 2D projective blocks (1x1 tower) have been produced at BNL and Illinois
    - goal: 2D projective modules for v2 prototype (10/16) with a production process that will scale to full detector
    - want to make blocks bigger than 1x1 tower



# cost/schedule drivers

---

- assembly/testing of sectors
  - large number of towers/SiPMs
  - current schedule based on university based module production assembly and testing
  - pursuing alternate industry based module production (THP), university based assembly and testing
  - understand feasibility of both module production options
    - unclear how industry module production affects cost—this will be more clear after prototyping process

# EMCal schedule summary


---

v1 prototype	ongoing-Jun '16
v2 prototype	Jun '16- Aug '17
preproduction	Aug '17 - Aug '18
conceptual design	Apr '16 - Dec '17
technical design	Dec '17 - Jul '18
initiate production	Jul '18
tower fabrication	Feb '19 - Oct '20
supermodule	May '19 - Mar '21
ready for detector	Mar '21

# organization: EMCal & electronics

## EMCal

## Calorimeter Electronics






# technical/project status

---

- 1D projective modules (2x1 towers) have been successfully produced at UCLA, Tungsten Heavy Powder (industry), Illinois and BNL
  - density:  $\sim 10\text{g/cm}^3$
- v1 prototyping:
  - produced both at Illinois Nuclear Physics Lab & THP
  - to be assembled, tested at BNL
- v2 prototyping:
  - ongoing work to develop 2D projective production



# technical/project status

- sector structure designed
- issues of cabling, cooling and electronics in empty space to be done
- deflection analysis to be done



# technical status—SiPMs

- SiPMs subject to damage from MeV neutrons
- neutron fluence  $\sim 2 \times 10^{10} \text{ n/cm}^2/\text{run}$  year
- measurements at STAR show increased leakage current but stable MIP peak
- expect leakage current in 3 yrs of sPHENIX will not significantly impact signals of interest



# issues & concerns

---

- 1D vs 2D modules
  - need to develop 2D production process to mass produce modules
    - v2 prototype targeted to answer this question
  - work underway at BNL, Illinois
- where are the modules to produced?
  - industry or university
    - both options being pursued, cost/schedule of industry solution not known yet
    - v1 prototype: constructed partially at both Illinois Nuclear Physics Lab and THP
- development of monitoring/calibration scheme