



WBS 6.5.2.4, 6.5.4.4

Low Voltage Power Supply Production and Box Assembly Technical Overview

Haleh Hadavand Dhiman Chakraborty

UT Arlington Northern Illinois University

Conceptual Design Review of the High luminosity LHC Detector Upgrades

National Science Foundation

Arlington, Virginia

March 8-10, 2016



LVPS Production



LVPS Production Expert

- Haleh Hadavand, Assistant Professor of Physics, has been part of the ATLAS experiment since 2005
- Integral part of Cosmics commissioning online and offline monitoring for the LAr Calorimeter in close collaboration with the Tile Calorimeter community
- Developed ATLAS' Data Quality Monitoring software and installed and integrated system for Calorimeter use
- Charged Higgs Convener for the ATLAS collaboration
- Recent addition to Tile Calorimeter



UT Arlington

- **Physics Personnel:**
 - Faculty: Haleh Hadavand (LVPS), Andrew Brandt (LVPS)
 - Graduate H. Akafzade and undergrad students
- **Engineering Personnel:**
 - Faculty: Ali Davoudi, EE
 - Electrical Associate: Seyedali Moayedi
 - Electrical Technician: Michael Hibbard

LVPS Requirements




Figure 5. Picture of a brick test fixture



Figure 8. Close-up view showing connectivity of a brick in the Burn-in Station



Fig. 1. TileCal Module



Fig. 2. Electronics drawer





Fig. 3. LVPS mounted on module

Requirements: Vout 10 V, 7 A nominal, 14 A redundancy, 11A over voltage protection


Front End Electronics



- 3-in-1 Front-end boards: Shaping of PMT signals for digitization, calibration and luminosity monitoring
- Main board: Digitize shaped PMT pulses, control attached 3-in-1 Front-end boards, power management from LVPS
- Daughter board: High speed link to the off-detector electronics for commands, On-detector monitoring / control and LHC clock extraction and distribution
- PPR: Off detector data stored in pipeline for trigger decision, interface to DAQ, and DCS

Power Connectivity

- Each power brick provides power to half a mini drawer
- However each brick capable of powering entire mini drawer through diode or in main board





-
- The diagram illustrates a 200V isolated DC-DC converter with feedback and protection. The input is 200V AC, which passes through an LC Filter and a shunt resistor R_{SHUNT} to provide V_{IN} and I_{IN} to the 'Startup & Shutdown Control' block. This block is connected to an 'ELMB (Control Interface)' and provides 'Startup', 'Shutdown', and 'Monitor Voltages' signals. It also outputs 'Run', 'Stop', and 'Over Temp' signals to the 'LT1681 Controller Chip'. The controller drives a 'FET Driver' (two MOSFETs) which switches the primary of a 'Transformer'. The primary is connected to 'GND_{PRI}' and 'V_{PRI}'. The secondary provides 'SEC Power' with V_{SEC} and 'GND_{SEC}'. The secondary output is regulated by an 'OpAmp' (feedback) and an 'Opto Isolator' (feedback and current sense). The feedback signal V_{FB} is fed back to the controller. The current sense signal I_{FB} is fed back to the 'Startup & Shutdown Control' block. The secondary output is filtered by an 'LC Buck' and an 'LC Filter' to provide the output voltage V_{out} and current I_{out} through a shunt resistor R_{SHUNT} . The output is also connected to 'GND_{SEC}'.



LVPS Plans

- Major R&D phase completed by Argonne National Labs (ANL) under Gary Drake and Jimmy Proudfoot
- Transition of knowledge from ANL to UTA in progress
- Setting up test stand now and to get several bricks from Argonne
- Pre-pre-production of 8 bricks to happen in a few months
 - Use test stand for checkout and burn in
- Pre-production of 10%+1%(failure rate) of bricks (111) to happen in 2018
- Production of half of total bricks, 1024, to start in latter half of 2020 and lasts for ~2 years
- Send bricks to Northern Illinois University to be assembled into boxes



BOE for LVPS Production

- Labor: Based on labor from version of bricks in detector but with adjustments for UTA to ramp up expertise and to compensate for personnel overturn
 - Parts procurement
 - Basic checkout and burn in
 - Repairs to 10-20% of bricks
 - Management of project
- Material : Very good estimate from cost of brick production for the Demonstrator
 - Stock parts
 - Transformer
 - Thermal post
 - PCB Fab and Assembly
 - Test Stands
- Travel: Going onsite to vendors for procurement and instructions for fabrication and assembly



LVPS Box



Box Assembly Expert

- Dhiman Chakraborty, Professor of Physics, Northern Illinois University
- Member of ATLAS and the Tile Calorimeter team since NIU joined in 2007
- US ATLAS Level-3 manager for Tile Calorimeter Calibration Database (2012-present)
- In charge of NIU's institutional responsibilities on ATLAS TileCal (next nu). Other current members of the TileCal group at NIU are
 - Iuori Smirnov (Research Scientist),
 - Pawel Klimek (Post-doc),
 - Blake Burghgrave (Graduate Student),
 - Puja Saha (Graduate Student).
- Will have additional personnel to help on this project
 - Electrical Engineer (Nicholas Pohlman OR suitable alternative)
 - Electrical Technician (Alexandre Dychkant OR Kurt Francis)
 - Undergraduate students (to be named)








Northern Illinois U

- The NIU ATLAS group has been participating in TileCal tasks since joining the collaboration in 2007
 - Institutional responsibilities in software projects (hardware done by then).
 - Contributed to the development and coordination of the Data Quality Monitoring system for online and offline use, signal reconstruction.
 - Full responsibility for maintenance, continued development, and user support for the TileCal calibration (conditions) database.
 - Scientists and grad students serve(d) in leadership roles on TileCal operations and maintenance.
- NIU is interested in contributing to hardware development for the HL-LHC upgrade. Have
 - In-house experience
 - Strong support from University, Northern Illinois Center for Accelerator and Detector Development

TileCal LVBOX deployment


Low Voltage power to each module (in green) is supplied by one “box” containing: 8 independent DC/DC converters (bricks), an **ELMB Motherboard**, an **ELMB module**, 200V DC distribution **Fuse Board**, **internal cable set**, and **chassis** and a water cooled heat sink.






LVPS Box

box of 8 bricks




Use same 72 pin
Harting Connector









Range of Voltages: 1:1 \Rightarrow One Brick Design
Range of Currents: ~2:1 * \Rightarrow Factor of 2 for redundancy

LVBOX I/O connections

Internal view of Harting connector 72 pins from inside the LV box



LVBOX assembly from components



- LVPS “box” V7.5 assembly done at CERN by CERN/Prague
- V8 for HL-LHC will be similar, production shared 50-50 by NIU and Prague




BoE for LVBOX production

- Labor: FTE estimates based on experience from previous campaigns. NIU components are
 - Vendor selection, component selection, BoM
 - Burn-in and basic check-out (of half of the total of 256 boxes)
 - Diagnose and repair failures
 - Inventory, crate and ship to CERN
- Material: estimates based on procurement for v7.5
 - For maximum uniformity, procurement of each component is assigned to a single institution.
 - NIU will procure the fuse boards, connectors and cables, including fabrication.
 - A test-stand and burn-in station will have to be set up at NIU.
- Travel: for pre-production at CERN

Demonstrator

- Version 8.0.8 installed
- Good performance





Backup



WBS 6.5.4.4

WBS	Deliverable	Task	Labor Hrs	Labor \$	M&S \$	Travel \$	Total \$
6.5.4.4	LVPs Assembly		2,526	232,419	193,950	19,275	445,644
	Final design	LV4010	355	44,306	0	3,855	48,161
	Engineers		355				
	Technicians		0				
	Student labor		0				
	Preproduction procurement	LV4020	355	44,306	18,750	0	63,056
	Engineers		355				
	Technicians		0				
	Student labor		0				
	Preproduction assembly	LV4030	80	7,196	0	3,855	11,051
	Engineers		40				
	Technicians		40				
	Student labor		0				
	Preproduction burn-in and checkout	LV4040	80	7,196	0	7,710	14,906
	Engineers		40				
	Technicians		40				
	Student labor		0				
	Preproduction diagnostics and repair	LV4050	80	7,196	0	0	7,196
	Engineers		40				
	Technicians		40				
	Student labor		0				
	Test equipment	LV4060	480	44,470	20,000	0	64,470
	Engineers		240				
	Technicians		240				
	Student labor		0				
	Production procurement	LV4120	136	10,593	128,000	0	138,593
	Engineers		40				
	Technicians		96				
	Student labor		0				
	Production Assembly	LV4130	120	10,045	0	3,855	13,900
	Engineers		40				
	Technicians		80				
	Student labor		0				
	Production burn-in and checkout	LV4140	480	23,706	4,000	0	27,706
	Engineers		80				
	Technicians		80				
	Student labor		320				
	Production diagnostics and repair	LV4150	320	30,994	4,000	0	34,994
	Engineers		160				
	Technicians		160				
	Student labor		0				
	Shipping	LV4210	40	2,411	19,200	0	21,611
	Engineers		0				
	Technicians		40				
	Student labor		0				



WBS 6.5.2.4

Student labor		0				
Basic checkout and burn-in	LV2040	888	33,888	0	0	33,888
Engineers		0				
Technicians		444				
Student labor		444				
Repairs	LV2050	296	19,305	0	2,000	21,305
Engineers		0				
Technicians		296				
Student labor		0				
Test Equipment	LV2070	74	4,344	15,000	0	19,344
Engineers		0				
Technicians		74				
Student labor		0				
Parts Procurement	LV2120	167	19,305	221,000	0	240,305
Engineers		111				
Technicians		56				
Student labor		0				
PCB Fab and assy	LV2130	222	11,757	110,000	6,000	127,757
Engineers		0				
Technicians		222				
Student labor		0				
Basic checkout and burn-in	LV2140	8,066	196,390	0	0	196,390
Engineers		0				
Technicians		962				
Student labor		7,104				
Repairs	LV2150	475	44,590	5,000	0	49,590
Engineers		197				
Technicians		278				
Student labor		0				