


# The Cornell/BNL FFAG-ERL Test Accelerator: C $\beta$ eRHIC prototype

Georg Hoffstaetter (Cornell) for the C $\beta$  collaboration

- Project Leader: Dejan Trbojevic
- Project Monitor: Wolfram Fischer
- Cornell Principal Investigator: Georg Hoffstaetter
- Cornell Project Manager: Bruce Dunham

CAD – MAC meeting  
21 September 2015





Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)

**BROOKHAVEN**  
NATIONAL LABORATORY



*a passion for discovery*





- eRHIC uses two FFAG beamlines to do multiple recirculations. (FFAG-I: 1.3-5.4 GeV, FFAG-II: 6.6-21.2 GeV)
- All sections of a FFAG beamline is formed using a same FODO cell. Required bending in different sections is arranged by proper selection of the offsets between cell magnets (or, alternatively, with dipole field correctors).
- Permanent magnets can be used for the FFAG beamline magnets (no need for power supplies/cables and cooling).

@S.Brooks, D.Trbojevic




Orbits in Detector bypass section

Quad offsets evolve adiabatically

Orbits in Transition section


Each of two eRHIC FFAGs contain 1066 FFAG cells



Some of the most important risk items for eRHIC:


- 1) FFAG loops with a factor of 4 in momentum aperture.
  - a) Precision, reproducibility, alignment during magnet and girder production.
  - b) Stability of magnetic fields in a radiation environment.
  - c) Matching and correction of multiple simultaneous orbits.
  - d) Matching and correction of multiple simultaneous optics.
  - e) Path length control for all orbits.
  
- 2) Multi-turn ERL operation with a large number of turns.
  - a) HOM damping.
  - b) BBU limits.
  - c) LLRF control and microphonics.
  - d) ERL startup from low-power beam.






# ERL as extension of CESR

ERL@CESR, Cornell







## Science with an Energy Recovery Linac




Cornell Energy Recovery Linac

Ju

June 2013


## Cornell Energy Recovery Linac:

## Project Definition Design Report




June 2013


- Science case gathered in international workshops
- Design report
  - 530 pages between conceptual design and engineering design
  - Access at [www.classe.cornell.edu/ERL/PDDR](http://www.classe.cornell.edu/ERL/PDDR)
- Also
  - Electron beam construction (from RI)
  - Cryoplant (from Linde and Air Liquide)




- NS-FFAG arcs, four passes (like first eRHIC loop)
- Momentum aperture of x4, as for eRHIC (EMMA achieved x1.7, planned x2)
- Uses Cornell DC gun, injector (ICM), dump, SRF CW Linac (MLC)
- Prototyping of essential components of eRHIC design








- Cornell DC gun
- 100mA, 6MeV SRF injector (ICM)
- 600kW beam dump
- 100mA, 6-cavity SRF CW Linac (MLC)







Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)

# The Cornell-BNL FFAG-ERL Test Accelerator

## White Paper

A white paper has been written to  
outline the C $\beta$  concept:  
arXiv:1504.00588

A Conceptual Design Report (CDR)  
is in preparation.

The C $\beta$  collaboration has:


- Started collaborative discussions in July 2014.
- Weekly phone meetings.
- Three face to face collaboration meetings of about 20 participants. Next one mid June at Stony Brook University.

Ivan Bazarov, John Dobbins, Bruce Dunham, Georg Hoffstaetter,  
Christopher Mayes, Ritchie Patterson, David Sagan


*Cornell University, Ithaca NY*

Ilan Ben-Zvi, Scott Berg, Michael Blaskiewicz, Stephen Brooks,  
Kevin Brown, Wolfram Fischer, Yue Hao, Wuzheng Meng,  
François Méot, Michiko Minty, Stephen Peggs, Vadim Ptitsin,  
Thomas Roser, Peter Thieberger, Dejan Trbojevic, Nick Tsoupas.

*Brookhaven National Laboratory, Upton NY*



December 16, 2014



## Electrons



Current  $I$  of up to 320mA in the linac (eRHIC has 700mA in the Linac)

Bunch charge  $Q$  of up to 2nC [funded by DOE-NP] (eRHIC 5.3nC)  
[to be copied for BNL]


Bunch repetition rate of 1.3GHz/N (e.g. 422.5MHz/13 for eRHIC cavity)

Energy  $E$  up to 250 MeV, operating only one cavity in the MLC

Beams of 100mA for 1 turn and 40mA for 4 turns








# ERL Readiness: high current beam

CLASSE



- Peak current of 75mA (world record)


- NaKSb photocathode
- High rep-rate laser
- DC-Voltage source

Source achievements:


- 2.6 day 1/e lifetime at 65mA
- 8h at 65mA
- With only 5W laser power (20W are available)
- now pushing to 100mA

Simulations accurately reproduce photocathode performance with no free parameters, and suggest strategies for further improvement.


✓ Source current can meet ERL needs



20 pC/bunch



80 pC/bunch




Normalized rms emittance (horizontal/vertical) 90% beam,  $E \sim 8$  MeV, 2-3 ps  
0.23/0.14 mm-mrad                      0.51/0.29 mm-mrad

Normalized rms core\* emittance (horizontal/vertical) @ core fraction (%)  
0.14/0.09 mm-mrad @ 68%                      0.24/0.18 mm-mrad @ 61%

*\*Phys. Rev. ST-AB 15 (2012) 050703  
ArXiv: 1304.2708*


✓ At 5 GeV this gives 20x the world's highest brightness (Petra-III)



## Target specs:

Bunch charge (pC)	Peak current target (A)	Peak current measured (A)	Emittance Target (95%, $\mu\text{m}$ )	Emittance measured (95%, $\mu\text{m}$ )
20	5	5	0.25	H: 0.18, V: 0.19
100	10	11.5	0.40	H: 0.32, V: 0.30
300	30	32	0.60	H: 0.62, V: 0.60

## Horizontal phase spaces




Dec. 12, 2014


Patterson

BNL-JLAB-Cornell in NYC


## Current profiles








Cavity surface was prepared for high  $Q_0$  while keeping it as simple as possible: bulk BCP, 650C outgassing, final BCP, very uniform 120C bake, HF rinse.



The achievement of high  $Q$  is relevant not only to Cornell's ERL but also to Project-X at Fermilab, to the Next Generation Light Source, to Electron-Ion colliders, spallation-neutron sources, and accelerator-driven nuclear reactors.



Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)


## MLC construction at Cornell

CLASSE

### Main Linac Cryomodule

Assembly completed November 20, 2014. Ready for testing.






What BNL gets out of the collaboration: Risk reduction and prototyping.

- R&D and prototyping of eRHIC systems, e.g. multi-beam feedback, [timing and synchronization](#), [high-current halo control](#), [collimation](#), [LLRF control](#), ions, CSR, etc.
- Proof of FFAG capabilities, e.g. [momentum acceptance of x4](#), [orbit and optics correction with real tolerances](#), reproducibility of magnet and girder construction, [adiabatic FFAG transitions](#), [resonant beam separation](#), etc.
- Proof of multi-turn ERL operation, BBU studies for 4 turns, operational stability, multi-beam diagnostics possibly for pilot bunches, [merger matching](#).
- After replacing the MLC by an eRHIC cavity: Proof of eRHIC-cavity capabilities, e.g. current limits, RF stability, microphonics control, HOM heating, etc.




Cornell gets out of the collaboration:


- [Forefront research in ERL physics](#).
- Excellent opportunities to [educate accelerator physics students](#) (e.g. for eRHIC).
- A [high-brightness beam of moderate energy](#) for physics experiment.









- Temperature stabilized using NiFe cross hatches or bars: a few  $10^{-4}$  between 20 and 30°C.
- Comfortable field strengths
- Well controlled cross talk
- Budgetary estimates obtained from 1-year delivery from Radiabeam.







**Gradient can be  
Changed by adjusting  
PM thickness**









Cell




-3.6 deg

Focus	Defocus
8 cm	11 cm
42.5 T/m	-27.5 T/m
-0.104 T	-0.5044 T

Arc-to-Straight (10 cells)









500 um rms x offset errors



SVD correction given BPM readings  
for separate beams and correction  
coils on every other dipole




Full FFAG arc




Full FFAG arc










Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)

# L0E cleaned out for C $\beta$ ERL

CLASSE









Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)

L0E cleaned with  $C\beta$  ERL

CLASSE










Cornell Laboratory for  
Accelerator-based Sciences and  
Education (CLASSE)

1<sup>st</sup> stage: 1-turn ERL for 67 MeV



CLASSE















- $C\beta$  will be the first accelerator in the world to include any of the following things, which are all required by the eRHIC design

- ERL using FFAG recirculating arcs
- Linear field FFAG with momentum range of 4x
- Adiabatic transition from curved to straight FFAG
- Permanent magnets (PMs) used in an FFAG
- NdFeB PMs used for main beam steering
- PMs used in ERL return arcs
- Multi-pass superconducting ERL


Phase 1&2

← Phase 3&4




- Deliverables:
  - Completed eRHIC prototype accelerator (Cornell University site location)
  - Commission the ERL NS-FFAG eRHIC prototype.
  - Perform eRHIC related experiments: accelerate 4 times in energy with the energy recovery for four energies, perform the orbit, gradient, time of flight correction, etc.
- Key Performance Parameters (KPP)
  - Demonstrate orbit corrections for all energies
  - Demonstrate a factor of 4 momentum acceptance in the FFAG
  - Demonstrate 4-pass recirculation with energy recovery at an average current of 1 mA
  - Demonstrate extraction for the highest energy pass
- Ultimate Performance Parameters (UPP)
  - Demonstrate 4-pass recirculation with energy recovery at an average current of 40 mA, with extraction of the highest energy






10/01/2016	Design and prototyping complete
10/01/2017	Construction complete with Cornell's ERL linac
03/01/2018	4-pass ERL operation with low current
10/01/2018	4-pass ERL operation with high current
01/01/2019	eRHIC linac installation
07/01/2019	4-pass ERL operation with eRHIC linac
10/01/2019	4-pass ERL operation with high current

This is based on the monthly resolution of activities listed in the next pages.





Oct 2015 Complete magnet designs for 2 competing options  
Optics design  
Order RF solid state amplifiers  
Order cryogenic pump skids

Nov 2015 Optics design  
Build prototypes for 2 magnet types  
design trim coils for quad and correction

Dec 2015 Optics design  
Test prototype magnets  
Choose magnet type  
complete trim coil design

Jan 2016 Optics design  
Obtain vendor quotes for magnets  
Finalize radiation shielding design  
Move injector klystrons into position

Feb 2016 Optics design complete  
Order permanent magnets  
Start clearing out remainder of exp. Hall  
Order trim coils

Mar 2016 prototype complete FFAG arc cell structure  
Order conventional magnets & PS  
Move linac, lcn and gun into final position  
Move cryogenic valve box, cryo lines

Apr 2016 Complete MLC RF system installation  
vacuum and support structure design  
specify and design diagnostic systems  
Complete cryo line installation


May 2016 prepare for linac full power tests  
vacuum and support structure design  
design diagnostic systems  
Radiation Permit preparation

Jun 2016 Linac full power tests  
design diagnostic systems  
continue vacuum design  
Radiation permit preparation

Jul 2016 Move CESR RF system, water system  
Complete vacuum chamber design  
Complete support girder design  
Begin shielding block shipping

Aug 2016 prepare for magnet QA  
Move CESR RF system, water system  
build/order vacuum components  
build/order support girders

Sep 2016 prepare for magnet QA  
Move CESR RF System, water system  
Complete area preparation  
Shielding block installation



Oct 2016 PM magnet acceptance and QA  
Conventional magnet acceptance and QA  
support girder acceptance  
shielding block installation

Apr 2017 construct magnet girder assemblies  
Control system installation  
safety system installation

Nov 2016 PM magnet QA  
Conventional magnet QA  
assemble/test FFAG girder  
shielding block installation

May 2017 construct magnet girder assemblies  
install magnet girders  
install magnet power supplies  
Control system installation

Dec 2016 vacuum chamber acceptance/testing  
order bpm electronics  
safety system installation  
radiation permit approval

Jun 2017 install magnet girders  
install magnet power & water & controls  
subsystem tests: vacuum, magnets, diagnostics  
Control system installation

Jan 2017 vacuum chamber acceptance/testing  
safety system installation

Jul 2017 install magnet girders  
install magnet power & water & controls  
subsystem tests: vacuum, magnets, diagnostics  
Control system installation


Feb 2017 construct magnet girder assemblies  
preliminary safety system checkout

Aug 2017 install magnet girders  
install magnet power & water & controls  
subsystem tests: vacuum, magnets, diagnostics  
safety system testing

Mar 2017 construct magnet girder assemblies  
Control system installation  
safety system installation

Sep 2017 subsystem tests: vacuum, magnets, diagnostics  
safety system certification





Oct 2017 Initial beam commissioning in pulsed mode  
Beam through first pass, linac phasing  
path length adjustment  
dump optics setup

Apr 2018 2, 3 and 4 pass setup  
high current operations  
BBU measurements

Nov 2017 demonstrate energy recovery for 1 pass  
optics in spreaders/recombiners  
second pass, path length adjust

May 2018 higher current tests, > 1 mA

Dec 2017 third pass, spreaders/recombiners  
beam quality measurements  
correction schemes

Jun 2018 chromaticity and emittance growth  
measurements  
higher current tests, > 1 mA

Jan 2018 fourth pass, spreaders recombiners  
path length adjustments  
beam quality measurements


Jul 2018 resonant beam extraction

Feb 2018 beam optics verifications, pulsed beam  
energy acceptance measurements

Aug 2018 high current tests  
beam quality measurements

Mar 2018 high current setup, 1 mA 1  
pass and energy recovery

Sep 2018 high current tests  
beam quality measurements



Oct 2018 Install eRHIC cryogenic adjustments

Apr 2019 high current setup, 1 mA 1  
pass and energy recovery

Nov 2018 Install eRHIC amplifiers, RF connectors, power, water,  
etc.

May 2019 2, 3 and 4 pass setup  
high current operations

Dec 2018 Install eRHIC cryomodule

Jun 2019 BBU measurements

Jan 2019 Beam commissioning in pulsed mode  
Beam through first pass, linac phasing  
path length adjustment  
dump optics setup


Jul 2019 higher current tests, > 1 mA

Feb 2019 demonstrate energy recovery for 1 pass  
beam quality measurements

Aug 2019 high current tests  
beam quality measurements


Mar 2019 beam optics verifications, pulsed beam  
energy acceptance measurements

Sep 2019 high current tests  
beam quality measurements




# Personnel needs by quarters

CLASSE








Neither an FFAG loop with a factor of 4 momentum acceptance nor a multi-turn ERL has been built before. **The C $\beta$  FFAG ERL at Cornell will address both of these risk factors for eRHIC** adequately and rather completely.

Cornell and BNL have started to collaborate on the creation of this prototyping facility at Cornell, using ERL components from Cornell

- A DC electron gun
- A low-emittance and high-current injector linac,
- An ERL-merger
- A 10m long CW SRF accelerator module
- A beam stop.

The collaboration has become rather active clearing space, testing components, producing WBS for detailed costing and timeline, and providing an organizing structure.

**1<sup>st</sup> Important eRHIC-ERL prototyping results can be available in 2018 !**  
**Afterwards, the eRHIC cavity can be tested with beam for HOM heating and BBU !**



# Questions ?